PROJECT NO.	SHEET NO.	TOTAL NO.
2026CPT.08.11.10771, 2026CPT.08.11.20771	20	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	BEGIN MP	END MP	1245000000-E SHOULDER RECONSTRUCTION	1260000000-E AGGREGATE SHOULDER BORROW	1297000000-E 1.5" MILLING	1330000000-E INCIDENTAL MILLING	1503000000-E INTERMEDIATE COURSE, I19.0C	1519000000-E SURFACE COURSE, S9.5B	1523000000-E SURFACE COURSE, S9.5C	1575000000-E ASPHALT BINDER FOR PLANT MIX	1704000000-E PATCHING EXISTING PAVEMENT	1841000000-E GENERIC PAVING ITEM - MILLED RUMBLE STRIPS (12")	2830000000-N ADJUST MANHOLES	2845000000-N ADJUST METER OR VALVE BOX	5255000000-N PORTABLE LIGHTING	7444000000-E INDUCTIVE LOOP SAWCUT
								MI	FT			SMI	TON	SY	SY	TONS	TONS	TONS	TONS	TONS	LF	EA	EA	LS	LF
2026CPT.08.11.10771	Richmond	1	US-74 W	FROM MARKS CREEK BRIDGE TO SR 1108 (MIZPAH RD.)	1	2	2WD	5.020	25	6.480	11.500			74,363	2,240			7,078	430	253					
TOTAL FOR MAP NO. 1								**5.020**						**74,363**	**2,240**			**7,078**	**430**	**253**					
2026CPT.08.11.10771	Richmond	2	US-74 E	FROM SR 1108 (MIZPAH RD.) TO BRIDGE AT MARKS CREEK	1	2	2WD	5.040	25	6.250	11.290			74,013	2,755			7,091	422	83					
TOTAL FOR MAP NO. 2								**5.040**						**74,013**	**2,755**			**7,091**	**422**	**83**					
2026CPT.08.11.10771	Richmond	3	RMP-5404 OI	FROM BACK OF GORE TO BACK OF RADIUS (MP 0.3)	2	1		0.247	25	0.053	0.300	0.48	67.00	4,155				384	23		55				
TOTAL FOR MAP NO. 3								**0.247**				**0.48**	**67.00**	**4,155**				**384**	**23**		**55**				
2026CPT.08.11.10771	Richmond	4	RMP-5405 OI	FROM BACK OF RADIUS (MP 0.02) TO BACK OF GORE	2	1		0.211	25	0.020	0.231	0.42	58.86	3,022				279	16		50				
TOTAL FOR MAP NO. 4								**0.211**				**0.42**	**58.86**	**3,022**				**279**	**16**		**50**				
2026CPT.08.11.10771	Richmond	5	RMP-5406 OI	FROM BACK OF GORE TO BACK OF RADIUS (MP 0.31)	2	1		0.250	25	0.060	0.310	0.50	69.73	4,015				371	22		50			1	
TOTAL FOR MAP NO. 5								**0.250**				**0.50**	**69.73**	**4,015**				**371**	**22**		**50**				
2026CPT.08.11.10771	Richmond	6	RMP-5407 OI	FROM BACK OF RADIUS (MP 0.02) TO BACK OF GORE	2	1		0.205	25	0.020	0.225	0.38	53.03	2,722				252	15		50				
TOTAL FOR MAP NO. 6								**0.205**				**0.38**	**53.03**	**2,722**				**252**	**15**		**50**				
TOTAL FOR PROJ NO. 2026CPT.08.11.10771								**10.973**				**1.78**	**248.62**	**162,290**	**4,995**			**15,455**	**928**	**336**	**205**			**1**	
2026CPT.08.11.20771	Richmond	7	SR-1608 / BOYD LAKE RD	FROM SCOTLAND CO. LINE TO SR 1613 (COLES STORE RD.)	3	2	2WU	2.900	20	0.000	2.900	5.65	790.81		1,050		3,201		213	103					
TOTAL FOR MAP NO. 7								**2.900**				**5.65**	**790.81**		**1,050**		**3,201**		**213**	**103**					
2026CPT.08.11.20771	Richmond	8	SR-1903 / MCDONALD AV	FROM END OF SIDEWALK/ C&G TO SR 1909 (HYLAN AVE)	3	2	2WU	1.090	24	0.650	1.740	2.18	300.00		950		1,427		95	38		1	3		
TOTAL FOR MAP NO. 8								**1.090**				**2.18**	**300.00**		**950**		**1,427**		**95**	**38**		**1**	**3**		
2026CPT.08.11.20771	Richmond	9	SR-1324 / ALLRED RD	FROM SR 1153 (COUNTY LINE RD.) TO SR 1321 (CAPEL MILL RD.)	3	2	2WU	1.650	16	0.000	1.650	3.24	453.70		411		1,452		96	32					
TOTAL FOR MAP NO. 9								**1.650**				**3.24**	**453.70**		**411**		**1,452**		**96**	**32**					
2026CPT.08.11.20771	Richmond	10	SR-1162 / ALVIN HARRIS RD	FROM SR 1159 (PEE DEE CHURCH RD.) TO SR 1164 (DAVIS HAYWOOD RD.)	3	2	2WU	2.920	20	0.000	2.920	5.49	768.14		900		2,932		194	76					
TOTAL FOR MAP NO. 10								**2.920**				**5.49**	**768.14**		**900**		**2,932**		**194**	**76**					
2026CPT.08.11.20771	Richmond	11	SR-1230 / ENTERPRISE DR	FROM SR 1139 (SILVER GROVE CHURCH RD.) TO D.E.	4	2	2WU	0.500	25	0.000	0.500	0.96	359.76		556	1,139		671	103	187					
TOTAL FOR MAP NO. 11								**0.500**				**0.96**	**359.76**		**556**	**1,139**		**671**	**103**	**187**					
2026CPT.08.11.20771	Richmond	12	SR-1903 / MCDONALD AV	FROM NC HWY 177 (MALBORO ST.) TO END OF SIDEWALK/C&G (ALEXANDER DR.)	5,6	2	2WU	0.650	27	0.000	0.650			11,371	1,427		1,161		75			5	3		360
TOTAL FOR MAP NO. 12								**0.650**						**11,371**	**1,427**		**1,161**		**75**			**5**	**3**		**360**
2026CPT.08.11.20771	Richmond	13	SR-1648 / ROCKINGHAM RD	FROM MP 0.00 TO US 74 BUS (EAST BROAD AVE)	7,8,9,1	2		1.740	26	0.000	1.740	1.69	236.52	33,500	2,075		3,228		212	48		12	6		2,880
TOTAL FOR MAP NO. 13								**1.740**				**1.69**	**236.52**	**33,500**	**2,075**		**3,228**		**212**	**48**		**12**	**6**		**2,880**
TOTAL FOR PROJ NO. 2026CPT.08.11.20771								**11.450**				**19.21**	**2,908.93**	**44,871**	**7,369**	**1,139**	**13,401**	**671**	**988**	**484**		**18**	**12**		**3,240**
GRAND TOTAL								**22.423**				**20.99**	**3,157.55**	**207,161**	**12,364**	**1,139**	**13,401**	**16,126**	**1,916**	**820**	**205**	**18**	**12**	**1**	**3,240**