PROJECT NO.	SHEET NO.	TOTAL NO.
2026CPT.10.15.10901 20262CPT.10.15.20901 2026CPT.10.15.20902	19	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	BEGIN MP	END MP	0241000000-E GENERIC GRADING ITEM SOIL CEMENT BASE (FULL DEPTH RECLAMATION)	1187000000-E PORTLAND CEMENT FOR SOIL CEMENT BASE	1220000000-E INCIDENTAL STONE BASE	1245000000-E SHOULDER RECONSTRUCTION	1260000000-E AGGREGATE SHOULDER BORROW	1330000000-E INCIDENTAL MILLING	1491000000-E BASE COURSE, B25.0C	1519000000-E SURFACE COURSE, S9.5B	1523000000-E SURFACE COURSE, S9.5C	1524000000-E LEVELING COURSE, S9.5C	1575000000-E ASPHALT BINDER FOR PLANT MIX	1704000000-E PATCHING EXISTING PAVEMENT	1814500000-E ASPHALT SURFACE TREATMENT, SINGLE SEAL	1838000000-E EMULSION FOR ASPHALT SURFACE TREATMENT	1838500000-N VACUUM TRUCK	1881000000-E 18" CENTERLINE SINUSOIDAL MILLED RUMBLE STRIPS	2612000000-E 6" DRIVEWAYS
								MI	FT			SY	TON	TONS	SMI	TON	SY	TONS	TONS	TONS	TONS	TONS	TONS	SY	GAL	WK	LF	SY
2026CPT.10.15.10901	Union	1	NC-205 ROUTE ID 30000205090	FROM SR 1002 ANSONVILLE RD TO SR 1006 OLIVE BRANCH RD MP 3.56 TO MP 5.40	2,8	2	2WU	1.84	22	3.56	5.4			180	3.68	510	3,039			2,235	184	196	1,104					
TOTAL FOR MAP NO. 1								1.84						180	3.68	510	3,039			2,235	184	196	1,104					
TOTAL FOR PROJ NO. 2026CPT.10.15.10901								1.84						180	3.68	510	3,039			2,235	184	196	1,104					
2026CPT.10.15.20901	Union	2	SR-1002 ANSONVILLE RD ROUTE ID 40001002090	FROM SR 1719 MARSHVILLE-OLIVE BRANCH RD TO SR 1720 LANESBORO RD MP 8.76 TO MP 9.79	2	2	2WU	1.03	18	8.76	9.79			65	2.06	286	300			1,005	103	95	618					
TOTAL FOR MAP NO. 2								1.03						65	2.06	286	300			1,005	103	95	618					
2026CPT.10.15.20901	Union	3	SR-1627 NEW SALEM RD ROUTE ID 40001627090	FROM NC 200 TO SR 1633 RILLA HAMILTON RD MP 0.00 TO MP 1.93	2,8	2	2WU	1.93	22	0	1.93			85	3.86	535	1,923			2,322	193	211	1,305					
TOTAL FOR MAP NO. 3								1.93						85	3.86	535	1,923			2,322	193	211	1,305					
2026CPT.10.15.20901	Union	4	SR-1006 OLIVE BRANCH RD ROUTE ID 40001006090	FROM NC 205 TO SR 1719 MARSHVILLE-OLIVE BRANCH RD MP 9.12 TO MP 13.83	1,7	2	2WU	4.71	20	9.12	13.83			240	9.42	1,306	1,382		5,075			482	3,179				24,867	
TOTAL FOR MAP NO. 4								4.71						240	9.42	1,306	1,382		5,075			482	3,179				24,867	
2026CPT.10.15.20901	Union	5	SR-1658 NEW HOPE CHURCH RD ROUTE ID 40001658090	FROM NC 205 TO SR 1627 NEW SALEM RD MP 0.00 TO MP 1.12	4,6,8	2	2WU	1.12	20	0	1.12			100	2.24	311	861	760		1,232		139	672					126
TOTAL FOR MAP NO. 5								1.12						100	2.24	311	861	760		1,232		139	672					126
2026CPT.10.15.20901	Union	6	SR-1658 NEW HOPE CHURCH RD ROUTE ID 40001658090	FROM SR 1627 NEW SALEM RD TO SR 1657 HAIGLER GIN RD MP 1.12 TO MP 2.74	4	2	2WU	1.62	20	1.12	2.74			100	3.24	449	580	1,154		1,765		204	1,000					90
TOTAL FOR MAP NO. 6								1.62						100	3.24	449	580	1,154		1,765		204	1,000					90
2026CPT.10.15.20901	Union	7	SR-1635 SINCERITY RD ROUTE ID 40001635090	FROM NC 200 TO SR 1627 NEW SALEM RD MP 0.00 TO MP 1.81	3	2	2WU	1.81	20	0	1.81			170	3.62	502	417	1,290	1,967			225	815					468
TOTAL FOR MAP NO. 7								1.81						170	3.62	502	417	1,290	1,967			225	815					468
2026CPT.10.15.20901	Union	8	SR-1649 SUGAR AND WINE RD ROUTE ID 40001649090	FROM SR 1627 HEW SALEM RD TO SR 1658 NEW HOPE CH RD MP 5.13 TO MP 7.09	3	2	2WU	1.96	20	5.13	7.09			125	3.92	543	595	1,447	2,167			249	900					90
TOTAL FOR MAP NO. 8								1.96						125	3.92	543	595	1,447	2,167			249	900					90
2026CPT.10.15.20901	Union	9	SR-1920 ZION CHURCH RD ROUTE ID 40001920090	FROM SR 1921 STATE LINE RD TO SR 1919 CANAL RD MP 1.27 TO MP 2.15	5	2	2WU	0.89	20	1.27	2.16			15	1.78	247			948			62						
TOTAL FOR MAP NO. 9								0.89						15	1.78	247			948			62						
2026CPT.10.15.20901	Union	10	SR-1914 ZION CHURCH RD ROUTE ID 40001914090	FROM SR 1921 SMITH TOWN RD TO EOM MP 0.00 TO MP 0.48	5	2	2WU	0.48	20	0	0.48			15	0.96	133			531			35						18
TOTAL FOR MAP NO. 10								0.48						15	0.96	133			531			35						18
TOTAL FOR PROJ NO. 2026CPT.10.15.20901								15.55						915	31.10	4,312	6,058	4,651	10,688	6,324	296	1,702	8,489				24,867	792
2026CPT.10.15.20902	Union	9	SR-1920 ZION CHURCH RD ROUTE ID 40001920090	FROM SR 1921 STATE LINE RD TO SR 1919 CANAL RD MP 1.27 TO MP 2.15	5	2	2WU	0.89	20	1.27	2.16	11,487	379											10,442	3,655	0.50		
TOTAL FOR MAP NO. 9								0.89				11,487	379											10,442	3,655	0.50		
2026CPT.10.15.20902	Union	10	SR-1914 ZION CHURCH RD ROUTE ID 40001914090	FROM SR 1921 SMITH TOWN RD TO EOM MP 0.00 TO MP 0.48	5	2	2WU	0.48	20	0	0.48	6,194	204											5,631	1,975	0.50		
TOTAL FOR MAP NO. 10								0.48				6,194	204											5,631	1,975	0.50		
TOTAL FOR PROJ NO.2026CPT.10.15.20902								1.37				17,681	583											16,073	5,630	1.00		
GRAND TOTAL								18.76				17,681	583	1,095	34.78	4,822	9,097	4,651	10,688	8,559	480	1,898	9,593	16,073	5,630	1.00	24,867	792