

PROJECT NO.	SHEET NO.	TOTAL NO.
2026CPT.10.15.10901 2026CPT.10.15.20901 2026CPT.10.15.20902	20	

### THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	BEGIN MP	END MP	4413000000-E	4457000000-N	4685000000-E	4688000000-E	4709000000-E	4720000000-E	4810000000-E	4895000000-N				
												WORK ZONE ADVANCE/GENERAL WARNING SIGNING	TEMPORARY TRAFFIC CONTROL	4" X 90 M WHITE THERMO	4" X 90 M YELLOW THERMO	6" X 90 M WHITE THERMO	6" X 90 M YELLOW THERMO	THERMOPLASTIC PAVEMENT MARKING LINES (24", 90 MILS)	THERMO MSG STOP 90 M	THERMO MSG AHEAD 90 M	4" WHITE PAINT	4" YELLOW PAINT	POLYCARBONATE H-SHAPED SNOWPLOWABLE DELINEATION MARKERS
								MI	FT			SF	LS	LF	LF	LF	LF	EA	EA	LF	LF	EA	
2026CPT.10.15.10901	Union	1	NC-205 ROUTE ID 30000205090	FROM SR 1002 ANSONVILLE RD TO SR 1006 OLIVE BRANCH RD MP 3.56 TO MP 5.40	2,8	2	2WU	1.84	22	3.56	5.4	206	*	19,430	18,364			60	16	5			121
TOTAL FOR MAP NO. 1								1.84				206		19,430	18,364			60	16	5			121
TOTAL FOR PROJ NO. 2026CPT.10.15.10901								1.84				206	*	19,430	18,364			60	16	5			121
														37,794		21							
2026CPT.10.15.20901	Union	2	SR-1002 ANSONVILLE RD ROUTE ID 40001002090	FROM SR 1719 MARSHVILLE-OLIVE BRANCH RD TO SR 1720 LANESBORO RD MP 8.76 TO MP 9.79	2	2	2WU	1.03	18	8.76	9.79	115								21,752	21,752		
TOTAL FOR MAP NO. 2								1.03				115									21,752	21,752	
2026CPT.10.15.20901	Union	3	SR-1627 NEW SALEM RD ROUTE ID 40001627090	FROM NC 200 TO SR 1633 RILLA HAMILTON RD MP 0.00 TO MP 1.93	2,8	2	2WU	1.93	22	0	1.93	217		20,380	16,142		40	24	10				
TOTAL FOR MAP NO. 3								1.93				217		20,380	16,142		40	24	10				
2026CPT.10.15.20901	Union	4	SR-1006 OLIVE BRANCH RD ROUTE ID 40001006090	FROM NC 205 TO SR 1719 MARSHVILLE-OLIVE BRANCH RD MP 9.12 TO MP 13.83	1,7	2	2WU	4.71	20	9.12	13.83	528				49,734	44,894	4	5				
TOTAL FOR MAP NO. 4								4.71				528				49,734	44,894	4	5				
2026CPT.10.15.20901	Union	5	SR-1658 NEW HOPE CHURCH RD ROUTE ID 40001658090	FROM NC 205 TO SR 1627 NEW SALEM RD MP 0.00 TO MP 1.12	4,6,8	2	2WU	1.12	20	0	1.12	125						4	5	23,656	23,656		
TOTAL FOR MAP NO. 5								1.12				125						4	5	23,656	23,656		
2026CPT.10.15.20901	Union	6	SR-1658 NEW HOPE CHURCH RD ROUTE ID 40001658090	FROM SR 1627 NEW SALEM RD TO SR 1657 HAIGLER GIN RD MP 1.12 TO MP 2.74	4	2	2WU	1.62	20	1.12	2.74	181	*					4	5	34,216	29,790		
TOTAL FOR MAP NO. 6								1.62				181						4	5	34,216	29,790		
2026CPT.10.15.20901	Union	7	SR-1635 SINCERITY RD ROUTE ID 40001635090	FROM NC 200 TO SR 1627 NEW SALEM RD MP 0.00 TO MP 1.81	3	2	2WU	1.81	20	0	1.81	203								38,228	38,228		
TOTAL FOR MAP NO. 7								1.81				203									38,228	38,228	
2026CPT.10.15.20901	Union	8	SR-1649 SUGAR AND WINE RD ROUTE ID 40001649090	FROM SR 1627 HEW SALEM RD TO SR 1658 NEW HOPE CH RD MP 5.13 TO MP 7.09	3	2	2WU	1.96	20	5.13	7.09	220								41,396	37,676		
TOTAL FOR MAP NO. 8								1.96				220									41,396	37,676	
2026CPT.10.15.20901	Union	9	SR-1920 ZION CHURCH RD ROUTE ID 40001920090	FROM SR 1921 STATE LINE RD TO SR 1919 CANAL RD MP 1.27 TO MP 2.15	5	2	2WU	0.89	20	1.27	2.16	100											
TOTAL FOR MAP NO. 9								0.89				100											
2026CPT.10.15.20901	Union	10	SR-1914 ZION CHURCH RD ROUTE ID 40001914090	FROM SR 1921 SMITH TOWN RD TO EOM MP 0.00 TO MP 0.48	5	2	2WU	0.48	20	0	0.48	54											
TOTAL FOR MAP NO. 10								0.48				54											
TOTAL FOR PROJ NO. 2026CPT10.15.20901								15.55				1,743	*	20,380	16,142	49,734	44,894	40	36	25	159,248	151,102	
														36,522		94,628		61		310,350			
2026CPT.10.15.20902	Union	9	SR-1920 ZION CHURCH RD ROUTE ID 40001920090	FROM SR 1921 STATE LINE RD TO SR 1919 CANAL RD MP 1.27 TO MP 2.15	5	2	2WU	0.89	20	1.27	2.16												
TOTAL FOR MAP NO. 9								0.89															
2026CPT.10.15.20902	Union	10	SR-1914 ZION CHURCH RD ROUTE ID 40001914090	FROM SR 1921 SMITH TOWN RD TO EOM MP 0.00 TO MP 0.48	5	2	2WU	0.48	20	0	0.48												
TOTAL FOR MAP NO. 10								0.48															
TOTAL FOR PROJ NO. 2026CPT10.15.20902								1.37															
GRAND TOTAL								18.76				1,949	1,000	39,810	34,506	49,734	44,894	100	52	30	159,248	151,102	121
														74,316		94,628		82		310,350			