Docusign Envelope ID: ECB627AE-5F74-4559-A4D8-C61397E2CB50

TIP NO.	SHEET NO.
HL-0008I	SIGN-2

APPROVED: DocuSigned by: Faith E. Jahnke — 8D02B5BCE7C9466...

DATE: 2/2/2026

SEAL

NORTH CAROLINA PROFESSIONAL ENGINEER SEAL 046981 FAITH E. JAHNKE

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

Prepared in the Office of: SUMMIT DESIGN AND ENGINEERING SERVICES — NC FIRM LICENSE No: C-5176, 320 Executive Ct., Hillsborough, NC 27278, (919) 732-3883, (919) 732-6676 (FAX)

401 QUANTITY REQ'D: 5



W3-3
30'' X 30''
ONE "U" POST PER SIGN

402 QUANTITY REQ'D: 2

R3-4
36" X 36"
ONE "U" POST PER SIGN

403 QUANTITY REQ'D: 2

R6-1R
48" X 18"
TWO "U" POSTS PER SIGN
MOUNT ABOVE SIGN 407
IN 1 INSTALLATION

404 QUANTITY REQ'D: 4

R2-1
30" X 36"
ONE "U" POST PER SIGN

405 QUANTITY REQ'D: 8

R4-7
24" X 30"
ONE "U" POST PER SIGN

406 QUANTITY REQ'D: 1

M4-4
24" X 12"
MOUNT ABOVE SIGN 402
IN 1 INSTALLATION

407 QUANTITY REQ'D: 1

R1-1
30'' X 30''
ONE "U" POST PER SIGN

408 QUANTITY REQ'D: 1

W1-2L
36'' X 36''
ONE "U" POST PER SIGN

409 QUANTITY REQ'D: 1



W2-2
30'' X 30''
ONE "U" POST PER SIGN

410 QUANTITY REQ'D: 2

R3-7
36'' X 36''
ONE "U" POST PER SIGN

411 QUANTITY REQ'D: 1



W12-1
36'' X 36''
ONE "U" POST PER SIGN

412 QUANTITY REQ'D: 1

OM1-3
18" X 18"
MOUNT BELOW SIGN 405
IN 1 INSTALLATION

413 QUANTITY REQ'D: 3

R6-1L
48" X 18"
TWO "U" POSTS PER SIGN

414 QUANTITY REQ'D: 1

W13-1P
18" X 18"
ONE "U" POSTS PER SIGN
MOUNT BELOW SIGN 408
IN 1 INSTALLATION

415 QUANTITY REQ'D: 1

R5-1
36'' X 36''
ONE "U" POST PER SIGN

416 QUANTITY REQ'D: 1

R4-21
24'' X 30''
ONE "U" POST PER SIGN

TYPE "E" SIGNS

2/2/2026
N:\2019\19-0205.105 HL-0008I\Transportation\Design\Traffic\Signing\CADD\Signing Layout Plans\HL-0008I_SIGN_3.dgn
USER:faith.jahnke