PROJECT NO.	TOTAL NO.
2026CPT.03.07.10101,ETC	21

SUMMARY OF QUANTITIES

														0106000000-E	1121000000-E	1220000000-E	1245000000-E	1297000000-E	1330000000-E	1491000000-E	1519000000-E	1523000000-E	1526000000-E	1575000000-E
PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	WARM MIX ASPHALT	LENGTH	WIDTH	BEGIN MP	END MP	BORROW EXCAVATION	AGGREGATE BASE COURSE	INCIDENTAL STONE BASE	SHOULDER RECONSTRUCTION	1.5" MILLING	INCIDENTAL MILLING	BASE COURSE, B25.0C	SURFACE COURSE, S9.5B	SURFACE COURSE, S9.5C	SURFACE COURSE, S4.75A	ASPHALT BINDER FOR PLANT MIX
									MI	FT			CY	TONS	TON	SMI	SY	SY	TONS	TON	TON	TON	TON
2026CPT.03.07.10101	Brunswick	1	NC-133 / RIVER RD	FROM 0.50 MILES SOUTH OF BRIDGE NO.67 TO 0.07 MILES NORTH OF NS-95842(MORECAMBLE BLVD) [MP 21.50 - MP 25.50]	1	2	2WU	YES	4.00	26	21.50	25.50	489			8.00	15,850	1,353			6,800		421
TOTAL FOR MAP NO. 1									**4.00**				**489**			**8.00**	**15,850**	**1,353**			**6,800**		**421**
2026CPT.03.07.10101	Brunswick	20A	NC-133 / RIVER RD	MP14.44 - MP14.63	7	2		NO	0.19	26	14.44	14.63											
TOTAL FOR MAP NO. 20A									**0.19**														
TOTAL FOR PROJ NO. 2026CPT.03.07.10101									**4.19**				**489**			**8.00**	**15,850**	**1,353**			**6,800**		**421**
2026CPT.03.07.20101	Brunswick	2	SR-1125 / CEDAR GROVE RD SW	FROM SR 1115 (STONE CHIMNEY RD) TO SR1130 (SW MT. PISGAH RD) [MP 0.00 - MP 2.84]	3	2	2WU	YES	2.84	23	0.00	2.84	343	122		5.61		370	1,877	3,126			292
TOTAL FOR MAP NO. 2									**2.84**				**343**	**122**		**5.61**		**370**	**1,877**	**3,126**			**292**
2026CPT.03.07.20101	Brunswick	3	SR-1120 / SABBATH HOME RD SW	FROM SR 1122 (VARNAMTOWN RD) TO NC 130 [MP 0.00 - MP 2.02]	3	2	2WU	YES	2.02	27	0.00	2.02	241	74		3.95		501	1,385	2,919			261
TOTAL FOR MAP NO. 3									**2.02**				**241**	**74**		**3.95**		**501**	**1,385**	**2,919**			**261**
2026CPT.03.07.20101	Brunswick	4	SR-1124 / STANBURY RD SW	FROM SR 1119 (STONE CHIMNEY RD SW) TO NC 130 [MP 0.00 - MP 2.85]	3	2		YES	2.85	23	0.00	2.85	346	206		5.67		296	1,989	3,342			311
TOTAL FOR MAP NO. 4									**2.85**				**346**	**206**		**5.67**		**296**	**1,989**	**3,342**			**311**
2026CPT.03.07.20101	Brunswick	5	SR-1181 / TURKEY TRAP RD SW	FROM SR 1125 (SW CEDAR GROVE RD) TO SR 1124 (SW STANBURY RD) [MP 0.00 - MP 1.21]	3	2	2WU	YES	1.21	24	0.00	1.21	145	72		2.37		136	832	1,474			135
TOTAL FOR MAP NO. 5									**1.21**				**145**	**72**		**2.37**		**136**	**832**	**1,474**			**135**
2026CPT.03.07.20101	Brunswick	6	SR-1300 / CALABASH RD NW	FROM SR 1303 (NW HICKMAN RD) TO US 17 [MP 11.02 - MP 13.35]	5	2	2WU	YES	2.33	20	11.02	13.35	273	66		4.47		208		2,949			196
TOTAL FOR MAP NO. 6									**2.33**				**273**	**66**		**4.47**		**208**		**2,949**			**196**
2026CPT.03.07.20101	Brunswick	7	SR-1313 / BELLAMY RD NW	FROM NC904 TO SR1315 RUSSTOWN RD NW	5	2		YES	0.98	20	0.00	0.98	115	46		1.88		111		957			69
TOTAL FOR MAP NO. 7									**0.98**				**115**	**46**		**1.88**		**111**		**957**			**69**
2026CPT.03.07.20101	Brunswick	8	SR-1461 / HEWETT-BURTON RD SE	FROM US17 TO EOM	5	2		YES	0.75	18	0.00	0.75	84	32		1.38		114		720			51
TOTAL FOR MAP NO. 8									**0.75**				**84**	**32**		**1.38**		**114**		**720**			**51**
TOTAL FOR PROJ NO. 2026CPT.03.07.20101									**12.98**				**1,547**	**618**		**25.33**		**1,736**	**6,083**	**15,487**			**1,315**
2026CPT.03.07.20102	Brunswick	9	SR-1814 / SEAGULL WAY SW	FROM SR1155 / GOOSE CREEK RD TO SR1817 / SANDPIPER DR	6	2		YES	0.36	18	0.00	0.36		26				56				192	13
TOTAL FOR MAP NO. 9									**0.36**					**26**				**56**				**192**	**13**
2026CPT.03.07.20102	Brunswick	10	SR-1815 / DOVE DR SW	FROM SR1814 / SEAGULL WAY TO SR1816 / MOCKINGBIRD LN	6	2		YES	0.05	16	0.00	0.05		2								27	3
TOTAL FOR MAP NO. 10									**0.05**					**2**								**27**	**3**
2026CPT.03.07.20102	Brunswick	11	SR-1816 / MOCKINGBIRD LN SW	FROM SR 1815 (DOVE DR) TO NS-95204(SANDPIPER DR SW) [MP 0.00 - MP 0.10]	6	2		YES	0.10	16	0.00	0.10		12								47	4
TOTAL FOR MAP NO. 11									**0.10**					**12**								**47**	**4**
2026CPT.03.07.20102	Brunswick	12	SR-1820 / SEAGULL WAY SW	FROM SR1817 SANDPIPER DR TO SR1819 BIRDWATCHER PL	6	2		YES	0.18	16	0.00	0.18		8								97	8
TOTAL FOR MAP NO. 12									**0.18**					**8**								**97**	**8**
2026CPT.03.07.20102	Brunswick	13	SR-1818 / CRANE RD SW	FROM SR1817 / SANDPIPER DR FROM SR1819 / BIRDWATHCHER PL	6	2		YES	0.18	16	0.00	0.18		12								108	9
TOTAL FOR MAP NO. 13									**0.18**					**12**								**108**	**9**
2026CPT.03.07.20102	Brunswick	14	SR-1819 / BIRDWATCHER PL SW	FROM SR1818 / CRANE RD TO SR1820 / SEAGULL WAY	6	2		YES	0.05	16	0.00	0.05										22	3
TOTAL FOR MAP NO. 14									**0.05**													**22**	**3**
2026CPT.03.07.20102	Brunswick	15	SR-1817 / SANDPIPER DR SW	FROM SR 1155 (GOOSE CREEK RD) TO NS-95204(SANDPIPER DR SW) [MP 0.00-MP0.10]	6	2		YES	0.10	16	0.00	0.10		4								54	5
TOTAL FOR MAP NO. 15									**0.10**					**4**								**54**	**5**
2026CPT.03.07.20102	Brunswick	16	SR-1456 / SCHOOL HOUSE RD NE	FROM SR1426 / MT. MISERY RD NE TO EOM	6	2		YES	0.21	20	0.00	0.21		8				56				189	16
TOTAL FOR MAP NO. 16									**0.21**					**8**				**56**				**189**	**16**
2026CPT.03.07.20102	Brunswick	17	SR-1534 / SHEPARD RD SE	FROM SR1528 E MOORE ST TO EOM	6	2		YES	0.73	20	0.00	0.73		6				111				473	37
TOTAL FOR MAP NO. 17									**0.73**					**6**				**111**				**473**	**37**
2026CPT.03.07.20102	Brunswick	18	SR-1199 / CEDAR LANDING RD SW	FROM NC 130 TO ROW LIMITS [MP 0.00 - MP 0.18]	6	2		YES	0.18	24	0.00	0.18			20					228			16
TOTAL FOR MAP NO. 18									**0.18**						**20**					**228**			**16**
TOTAL FOR PROJ NO. 2026CPT.03.07.20102									**2.14**					**78**	**20**			**223**		**228**		**1,209**	**114**
50975.3.50	Brunswick	20	NC-133 / RIVER RD	FROM SR1518 DAWS CREEK RD TO SR1551 BLACKWELL RD	7	2		NO	7.70	26	18.69	26.39											
TOTAL FOR MAP NO. 20									**7.70**														
50975.3.50	Brunswick	4A	SR-1124 / STANBURY RD SW	FROM SR 1119 (STONE CHIMNEY RD SW) TO NC 130	7	2	2WU	NO	2.85	4	0.00	2.85											
TOTAL FOR MAP NO. 4A									**2.85**														
TOTAL FOR PROJ NO. 50975.3.50									**10.55**														
3C.010109	Brunswick	19	SR-1766 / ROBIN LN NE	FROM SR 1492 (DAVIDSON AVE NE) TO SR 1488(NATIONAL AVE NE) [MP 0.00-MP0.11]	4	2	2WU	YES	0.11	22	0.00	0.11			4	0.22				123			8
TOTAL FOR MAP NO. 19									**0.11**						**4**	**0.22**				**123**			**8**
TOTAL FOR PROJ NO. 3C.010109									**0.11**						**4**	**0.22**				**123**			**8**
3C.010104	Brunswick	18A	SR-1199 / CEDAR LANDING RD SW	FROM END OF PAVEMENT TO END OF MAINTENANCE	4	2	2WU	YES	0.04	22	0.11	0.15			40	0.08		50		60			4
TOTAL FOR MAP NO. 18A									**0.04**						**40**	**0.08**		**50**		**60**			**4**
TOTAL FOR PROJ NO. 3C.010104									**0.04**						**40**	**0.08**		**50**		**60**			**4**
GRAND TOTAL									**30.080**				**2,036**	**696**	**64**	**33.63**	**15,850**	**3,362**	**6,083**	**15,898**	**6,800**	**1,209**	**1,862**