



NOTES:

1. INSTALL NEW 144-FIBER AND NEW 96-FIBER BEFORE DISCONNECTING EXISTING FIBER.
2. REMOVE EXISTING CCTV AND REPLACE WITH PORTABLE CCTV THROUGHOUT CONSTRUCTION PHASES.
3. BACK PULL 72-FIBER. REINSTALL IN NEW CONDUIT TO NEW SPLICE ENCLOSURE.
4. IN PHASE 1, REMOVE FIBER FROM CONDUIT, CUT CONDUIT 30" BELOW GRADE, AND ABANDON IN PLACE.
5. IN FINAL PHASE, INSTALL NEW CCTV ON 50' METAL POLE AS SHOWN IN PLANS.

PHASE 1

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

	<p>COMMUNICATIONS CABLE AND CONDUIT ROUTING PLANS</p>	
	<p>Division 9 Forsyth County Winston-Salem</p>	<p>Winston-Salem</p>
<p>750 N. Greenfield Pkwy., Garner, NC 27529</p>	<p>PLAN DATE: FEBRUARY 2026</p>	<p>REVIEWED BY: N. DOMINGUEZ, PE</p>
<p>SCALE: 0 N/A</p>	<p>PREPARED BY: L.E. NEAL</p>	<p>REVISIONS: _____</p>
<p>DocuSigned by: Nathan Dominguez</p>	<p>INIT. DATE</p>	<p>DATE</p>