Docusign Envelope ID: CAB76B9D-839C-4E85-823A-B322CCC359A2

PROJECT REFERENCE NO.	SHEET NO.
R-5858	Sig. 3.2

OUTPUT CHANNEL CONFIGURATION

Front Panel
Main Menu >Controller >More>Channels>Channels Config

Web Interface
Home >Controller >Advanced IO>Channels>Channels Configuration

Channel Configuration

Channel	Control Type	Control Source	Flash Yellow	Flash Red	Flash Alt	MMU Channel
1	Phase Vehicle	1		X	X	1
2	Phase Vehicle	2		X		2
3	Phase Vehicle	3		X	X	3
4	Phase Vehicle	4		X		4
5	Phase Vehicle	5		X		5
6	Phase Vehicle	6		X	X	6
7	Phase Vehicle	7		X		7
8	Phase Vehicle	8		X	X	8
9	Overlap	1		X	X	9
10	Overlap	2		X	X	10
11	Overlap	3		X		11
12	Overlap	4		X		12
13	Phase Ped	2				13
14	Phase Ped	4				14
15	Phase Ped	6				15
16	Phase Ped	8				16
17	Overlap	5		X	X	17
18	Overlap	6		X		18

NOTICE CHANNEL 2 FLASHES RED →
NOTICE CHANNEL 6 FLASHES RED →
NOTICE CHANNEL 9 FLASHES RED →
NOTICE CHANNEL 11 FLASHES RED →

MAXTIME STARTUP AND SOFTWARE FLASH PROGRAMMING DETAIL

Front Panel
Main Menu >Controller >Unit

Web Interface
Home >Controller >Unit

Modify parameters as shown below and save changes.

Start Up Parameters

StartUp Clearance Hold
6

Unit Flash Parameters

All Red Flash Exit Time
6

Front Panel
Main Menu >Controller >Overlap >Overlap Parameters/Overlap Timings

Web Interface
Home >Controller >Overlap Configuration >Overlaps

Overlap Plan 1

Overlap	1	2	3	4
Type	Normal	Off	Normal	Off
Included Phases	1,8		4,5	
Modifier Phases				
Modifier Overlaps	-	-		
Trail Green	0		0	
Trail Yellow	0.0		0.0	
Trail Red	0.0		0.0	

FLASHER CIRCUIT MODIFICATION DETAIL

IN ORDER TO INSURE THAT SIGNALS FLASH CONCURRENTLY ON THE SAME APPROACH, MAKE THE FOLLOWING FLASHER CIRCUIT CHANGES:

1. ON REAR OF PDA - REMOVE WIRE FROM TERM. T2-4 AND TERMINATE ON T2-2.
2. ON REAR OF PDA - REMOVE WIRE FROM TERM. T2-5 AND TERMINATE ON T2-3.
3. REMOVE FLASHER UNIT 2.

THE CHANGES LISTED ABOVE TIES ALL PHASES AND OVERLAPS TO FLASHER UNIT 1.

THIS ELECTRICAL DETAIL IS FOR
THE SIGNAL DESIGN: 02-0247
DESIGNED: April 2026
SEALED: 04-08-2026
REVISED: N/A

GFT Infrastructure, Inc.
One Glenwood Avenue, Suite 900
Raleigh, NC 27603
919-420-7660
NC Lic. No. F-0270

Electrical Detail - Sheet 2 of 2

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

Electrical and Programming Details For:

NC 24 (W.B. McClean Drive)
at
NC 58

Division 2 Carteret County Cape Carteret

PLAN DATE:	April 2026	REVIEWED BY:	D. Hartland
PREPARED BY:	JT Rowe	REVIEWED BY:	

REVISIONS	INIT.	DATE

Prepared in the Offices of:
Transportation Mobility and Safety Division, State of North Carolina, Department of Transportation, Traffic Engineering Branch, Signals Management Section
750 N. Greenfield Pkwy, Garner, NC 27529

SEAL
NORTH CAROLINA PROFESSIONAL SEAL 008453 ENGINEER JOHN T. ROWE III
DocuSigned by: John T. Rowe, III 4/8/2026
SIGNATURE DATE
SIG. INVENTORY NO. 02-0247

$$$$$$SYST_TIME$$$$$$
$$$$$$SYST_DATE$$$$$$
$$$$$$SECTIONS$$$$$$$$$$$$$$$$$$$$$$
$$$$USERNAME$$$$