PROJ. REFERENCE NO.	SHEET NO.
U-5743	X1-B

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY

Approximate quantities only. Unclassified excavation, fine grading, clearing and grubbing, and removal of existing pavement will be paid for at the lump sum price for "Grading".

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

Station L LT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
15+00.00	0	0
15+50.00	2	12
16+00.00	3	60
16+50.00	1	113
17+00.00	0	152
17+50.00	0	160
18+00.00	0	167
18+50.00	0	114
19+00.00	0	42
19+50.00	0	42
20+00.00	0	49
20+50.00	0	55
21+00.00	0	49
21+25.00	0	15
	6	1030

Station L RT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
15+00.00	0	0
15+50.00	4	1
16+00.00	5	173
16+50.00	1	443
17+00.00	0	576
17+50.00	0	513
18+00.00	13	448
18+50.00	15	434
19+00.00	9	304
19+50.00	17	142
20+00.00	23	44
20+50.00	43	18
21+00.00	48	13
21+25.00	20	6
	198	3115

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
21+25.00	0	0
22+00.00	16	14
22+50.00	16	74
23+00.00	7	110
23+50.00	9	101
24+00.00	26	88
24+50.00	56	64
25+00.00	91	49
25+50.00	74	47
26+00.00	26	42
26+50.00	15	33
27+00.00	10	56
27+50.00	2	94
28+00.00	1	116
28+50.00	0	236
29+00.00	1	298
29+50.00	19	195

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
30+00.00	31	183
30+50.00	22	219
31+00.00	13	217
31+50.00	9	223
31+53.34	2	12
31+61.34	7	18
32+00.00	42	81
32+50.00	50	110
33+00.00	19	128
33+50.00	7	176
34+00.00	33	182
34+45.00	139	169
	743	3335

Station L LT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
34+45.00	0	0
34+50.00	24	3
35+00.00	215	26
35+50.00	142	26
36+00.00	69	34
	450	89

Station L RT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
34+45.00	0	0
34+50.00	0	18
35+00.00	2	173
35+50.00	4	217
36+00.00	4	233
	10	641

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
36+00.00	0	0
36+50.00	25	256
37+00.00	13	270
37+50.00	35	255
38+00.00	26	253
38+50.00	0	317
39+00.00	0	407
39+50.00	0	460
40+00.00	0	453
40+50.00	3	371
41+00.00	4	259
41+50.00	2	194
42+00.00	3	193
42+50.00	3	206
43+00.00	4	159
43+50.00	5	212
44+00.00	3	322
44+50.00	4	303
45+00.00	5	264

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
45+50.00	5	185
46+00.00	5	108
46+50.00	19	70
47+00.00	21	54
47+50.00	13	56
48+00.00	14	75
48+50.00	9	126
49+00.00	11	132
49+50.00	15	96
50+00.00	21	74
50+50.00	19	69
51+00.00	9	60
51+50.00	8	67
52+00.00	9	66
52+50.00	9	51
53+00.00	9	47
53+50.00	8	47
54+00.00	4	23
	343	6560

Station Y1	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+20.05	0	0
10+50.00	0	43
11+00.00	8	68
11+50.00	19	59
12+00.00	20	56
12+50.00	21	49
13+00.00	34	23
13+50.00	49	6
14+00.00	27	4
	178	**308**

Station Y2	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+20.00	0	0
10+50.00	32	8
11+00.00	108	9
11+50.00	181	6
12+00.00	118	10
12+50.00	40	12
13+00.00	46	8
13+25.00	13	1
	538	**54**

Station Y5	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+32.00	0	0
10+50.00	130	7
11+00.00	379	9
11+50.00	293	10
12+00.00	119	26
12+50.00	42	23
13+00.00	18	7
	981	**82**

Station Y6	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
11+50.00	0	0
12+00.00	15	8
12+50.00	31	15
13+00.00	23	157
13+50.00	6	268
14+00.00	0	323
14+46.38	0	383
	75	**1154**

Station Y7	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+15.00	0	0
10+40.00	9	4
10+50.00	7	3
11+00.00	15	83
11+37.68	0	114
	31	**204**

Station Y8	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+20.89	0	0
10+50.00	30	35
10+75.00	31	19
11+00.00	19	4
	80	**58**

Station DR1	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+12.00	0	0
10+25.00	28	0
10+50.00	63	11
10+75.00	36	12
10+87.08	1	0
	128	23