

STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Approximate quantities only. Shoulder borrow, fine grading, clearing and grubbing, and removal of existing asphalt pavement will be paid for at the contract lump sum price for "Grading."

Station	Uncl. Exc.	Embt	Station	Uncl. Exc.	Embt	Station	Uncl. Exc.	Embt	Station	Uncl. Exc.	Embt
-L-	(cu. yd.)	(cu. yd.)	-LPA-	(cu. yd.)	(cu. yd.)	-RPA-	(cu. yd.)	(cu. yd.)	-Y1-	(cu. yd.)	(cu. yd.)
20+69.18	0	0	10+00.00	0	0	20+00.00	629	3	17+00.00	0	0
21+00.00	10	0	10+50.00	12	34	20+50.00	832	14	17+50.00	8	6
21+50.00	15	0	11+00.00	12	27	21+00.00	997	48	18+00.00	9	11
22+00.00	17	4	11+50.00	14	21	21+50.00	1308	52	18+50.00	11	26
22+50.00	19	5	12+00.00	16	20	22+00.00	1806	16	19+00.00	12	32
23+00.00	23	1	12+50.00	11	46	22+50.00	2548	0	19+50.00	13	29
23+50.00	23	10	13+00.00	20	57	23+00.00	3480	0	20+00.00	15	49
24+00.00	20	43	13+50.00	99	21	23+50.00	4236	0	20+50.00	27	40
24+50.00	21	108	14+00.00	337	0	24+00.00	3635	0	21+00.00	32	24
25+00.00	23	134	14+50.00	743	0	24+50.00	2427	20	22+00.00	34	39
25+50.00	25	226	15+00.00	1146	0				22+50.00	10	3
26+00.00	27	173	15+50.00	1041	0	Station	Uncl. Exc.	Embt	23+00.00	11	6
26+50.00	32	12	16+00.00	448	67						
27+00.00	42	9	16+50.00	247	150	-RPB-	(cu. yd.)	(cu. yd.)	Station	Uncl. Exc.	Embt
27+50.00	58	4	17+00.00	274	206	21+00.00	0	0			
28+00.00	74	0	17+50.00	421	232	21+50.00	2	346	-Y1-	(cu. yd.)	(cu. yd.)
28+50.00	84	0	18+00.00	533	303	22+00.00	10	133	27+00.00	84	44
29+00.00	85	0	18+50.00	388	328	22+50.00	25	24	27+50.00	11	1
29+50.00	89	0	19+00.00	766	137	23+00.00	50	7	28+00.00	8	4
30+00.00	109	0	19+50.00	616	352	23+50.00	170	7	28+50.00	5	7
30+50.00	110	0	20+00.00	36	2223	24+00.00	180	4	29+00.00	3	15
31+00.00	116	13	20+50.00	2	3442	24+50.00	86	0	29+50.00	4	30
31+50.00	185	29	21+00.00	8	2680	25+00.00	90	0	30+00.00	4	34
32+00.00	301	37	21+50.00	12	1693	25+50.00	75	0	30+50.00	1	30
32+50.00	475	46	22+00.00	5	723	26+00.00	64	0	31+00.00	10	30
33+00.00	619	25	22+50.00	78	202	26+50.00	164	0	31+50.00	14	24
33+50.00	716	0	23+00.00	165	128				32+00.00	9	20
34+00.00	864	0	23+50.00	159	113	Station	Uncl. Exc.	Embt	32+50.00	10	19
34+50.00	987	0	24+00.00	237	76				33+00.00	10	17
35+00.00	1027	62				-RPC-	(cu. yd.)	(cu. yd.)	33+50.00	10	11
35+50.00	906	125	Station	Uncl. Exc.	Embt	21+50.00	0	0	34+00.00	10	8
36+00.00	485	134				22+00.00	12	0	34+50.00	0	0
36+50.00	135	242	-RPA-	(cu. yd.)	(cu. yd.)	22+50.00	13	0	35+00.00	0	0
37+00.00	95	467	15+50.00	0	0	23+00.00	15	4	35+10.00	3	1
37+50.00	84	321	16+00.00	25	0	23+50.00	17	13			
38+00.00	57	48	16+50.00	26	1	24+00.00	18	16			
38+50.00	49	48	17+00.00	26	1	24+50.00	17	9			
39+00.00	53	44	17+50.00	26	0	25+00.00	16	10			
39+50.00	60	44	18+00.00	106	4	25+50.00	15	18			
40+00.00	56	49	18+50.00	223	7	26+00.00	15	19			
40+50.00	43	54	19+00.00	170	6	26+50.00	16	17			
41+00.00	33	57	19+50.00	270	4	27+00.00	13	18			
41+50.00	39	60				27+50.00	15	12			
42+00.00	41	63				28+00.00	23	3			
42+50.00	41	69									
43+00.00	28	68									
43+50.00	103	32									
44+00.00	100	0									
44+50.00	9	0									
45+00.00	10	0									
45+50.00	332	0									
46+00.00	426	12									
46+50.00	116	33									

5/1/2016 11:44:568 - NCDDOT - I-5716 - I-40 Lenoir-Rhine Interchange V05-CAD\15716-Roadkey\Xsc\15716-rdy.xpl_X-1A.dgn