

COMPUTED BY : SEM DATE : 10/16/2024
 CHECKED BY : LAC DATE : 10/16/2024
 REVISED BY : TTZ DATE : 4/8/2026

(9-17-24)

PROJECT NO. HB-0035	SHEET NO. 3G-1
------------------------	-------------------

STATE OF NORTH CAROLINA
 DIVISION OF HIGHWAYS

SUMMARY OF SUBSURFACE DRAINAGE

LINE	Station	Station	Location LT/RT/CL	Drain Type* UD/BD/SD	LF
CONTINGENCY				SD	200
				TOTAL LF:	200

*UD = Underdrain
 *BD = Blind Drain
 *SD = Subsurface Drain

SUMMARY OF AGGREGATE SUBGRADE/STABILIZATION

LINE	Station	Station	Aggregate Type* ASU(1/2)/ AST	Aggregate Thickness INCHES [8" for ASU(2)]	Shallow Undercut CY	Class IV Subgrade Stabilization TONS	Geotextile for Subgrade Stabilization SY	Stabilizer Aggregate TONS	Class IV Aggregate Stabilization TONS
-L-	23+25	25+25	ASU 1	12	-	627	961	-	-
CONTINGENCY			ASU (1)	12	100	200	300		
					TOTAL CY/TONS/SY:	100	827**	1261**	0

*ASU(1/2) = Aggregate Subgrade (Type 1 or 2)
 *AST = Aggregate Stabilization
 **Total tons of "Class IV Subgrade Stabilization" and total square yards of "Geotextile for Subgrade Stabilization" are only the estimated quantities for ASU(1/2)/AST and may only represent a portion of the subgrade stabilization and geotextile quantities shown in the Item Sheets of the Proposal.

SUMMARY OF ROCK PLATING

LINE	Beginning Slope (H:V)	Approx. Station	Ending Slope (H:V)	Approx. Station	Location LT/RT	Rock Plating Detail No. 1/2/3/4	Riprap Class* 1/2/B	Rock Plating SY
-L-	1.75:1	17+45	1.75:1	17+75	RT	1	*	80
							TOTAL SY:	80

*Use Class 1, 2 or B riprap if riprap class is not shown for rock plating location.