5/26/20

DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA

SOIL STABILIZATION SUMMARY SHEET

SLOPE MATTING FOR EROSION CONTROL

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
4	-L-	17+45	18+35	RT	465
4	-L-	17+50	20+50	LT	918
4	-L-	23+45	25+30	RT	846
4	-L-	23+50	24+50	LT	467
4	-L-	10+18	10+63	LT	122
				SUBTOTAL	2818
			SUBTOTAL FROM EC-3A		495
	MISCELLANEOUS MATTING TO BE INSTALLED AS DIRECTED BY THE ENGINEER				1000
				TOTAL	4313
				SAY	4325

PERMANENT SOIL REINFORCEMENT MAT (TYPE 3)

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
4	-L-	17+50	17+93	LT	35
				SUBTOTAL	35
	MISCELLANEOUS MATTING TO BE INSTALLED AS DIRECTED BY THE ENGINEER				0
				TOTAL	35
				SAY	35

HB-0035
EC-3B

NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
ROCKINGHAM COUNTY

PLANS PREPARED BY:
SUMMIT DESIGN AND ENGINEERING SERVICES
NC FIRM LICENSE No: C-5176
1000 Social St, Suite 800,
Raleigh, NC 27609
(919) 732-3883
(919) 732-6676 (FAX)