PROJ. REFERENCE NO.	SHEET NO.
17BP.7.R.114	X-1A

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

Approximate quantities only. Unclassified excavation, fine grading, clearing and grubbing, and removal of existing pavement will be paid for at the lump sum price for "Grading".

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Station Y	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+00.00	0	0	10+12.06	0	0
10+50.00	11	12	10+50.00	9	268
11+00.00	35	28	10+75.00	4	161
11+50.00	41	32	11+00.00	1	137
12+00.00	25	36	11+25.00	0	85
12+50.00	11	123	11+50.00	6	23
13+00.00	2	255	11+75.00	16	3
	125	486		36	677

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
13+00.00	0	0
13+50.00	0	454
14+00.00	0	925
14+50.00	0	1485
15+00.00	0	1583
15+50.00	0	1329
16+00.00	0	965
16+50.00	0	625
	0	7366

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
16+50.00	0	0
17+00.00	0	465
17+50.00	0	347
18+00.00	0	302
18+50.00	0	262
19+00.00	9	110
	9	1486

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
19+40.00	0	0
19+50.00	1	2
20+00.00	4	34
20+45.00	3	36
	8	72

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
20+45.00	0	0
20+45.00	1	2
21+00.00	11	29
21+50.00	35	25
22+00.00	26	6
	73	62