DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA

SOIL STABILIZATION SUMMARY SHEET

DITCH MATTING FOR EROSION CONTROL

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
5	-L-	26+91	27+50	LT	35
5	-L-	26+00	26+55	RT	25
5	-L-	26+55	26+75	RT	15
		(EXCELSIOR) SUBTOTAL			75
MISCELLANEOUS MATTING TO BE INSTALLED AS DIRECTED BY THE ENGINEER					25
		(EXCELSIOR) TOTAL			100

SLOPE MATTING FOR EROSION CONTROL

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
4	-L-	17+75	19+00	LT	850
4	-L-	19+75	21+25	LT	1730
4	-L-	23+00	24+50	LT	860
4	-L-	19+75	21+50	RT	1310
4	-L-	23+25	24+50	RT	970
4	-RPA-	11+00	12+25	LT	900
4	-RPB-	13+00	13+50	RT	170
4	-RPC-	12+75	13+25	LT	610
4	-RPC-	12+75	13+25	RT	290
4	-RPD-	14+50	15+25	LT	580
		(EXCELSIOR) SUBTOTAL			8270
MISCELLANEOUS MATTING TO BE INSTALLED AS DIRECTED BY THE ENGINEER					7710
		(EXCELSIOR) TOTAL			15980
		SAY (INCLUDING DITCH MATTING)			16080