PROJ. REFERENCE NO.	SHEET NO.
BR-099	X-1A

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

Approximate quantities only. Unclassified excavation, fine grading, clearing and grubbing, breaking of existing pavement and removal of existing pavement will be paid for at the lump sum price for "Grading".

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

STATION -L-	UNCL. EXC. (CY)	UN. EMBT. (CY)
17+00.00	0	0
17+50.00	10	1
17+54.34	10	11
18+00.00	14	117
18+50.00	6	271
19+00.00	4	157
19+50.00	3	2
20+00.00	1	467
20+50.00	0	912
21+00.00	0	767
21+50.00	0	1170
22+00.00	0	849
22+50.00	0	0
23+00.00	0	950
23+50.00	0	1245
24+00.00	0	674
24+50.00	0	616
25+00.00	0	263
25+50.00	0	26
26+00.00	1	2
26+50.00	3	3
27+00.00	6	5
27+50.00	11	5

STATION -RPA-	UNCL. EXC. (CY)	UN. EMBT. (CY)
11+00.00	0	0
11+50.00	0	0
12+00.00	0	0
12+50.00	0	18

STATION -RPB-	UNCL. EXC. (CY)	UN. EMBT. (CY)
13+00.00	0	0
13+50.00	0	34
14+00.00	0	116
14+50.00	0	115

STATION -RPD-	UNCL. EXC. (CY)	UN. EMBT. (CY)
14+50.00	0	0
15+00.00	3	53
15+50.00	2	82

STATION -Y1-	UNCL. EXC. (CY)	UN. EMBT. (CY)
26+55.00	0	0
27+00.00	91	10
27+50.00	104	15
28+00.00	107	18
28+50.00	106	22
29+00.00	111	20
29+50.00	131	21
30+00.00	168	24
30+50.00	153	25
31+00.00	117	28
31+50.00	121	28
32+00.00	139	28

STATION -Y1-	UNCL. EXC. (CY)	UN. EMBT. (CY)
32+50.00	165	25
33+00.00	175	21
33+50.00	175	14
34+00.00	166	9
34+50.00	144	11
35+00.00	124	12
35+10.00	24	2

STATION -RPC-	UNCL. EXC. (CY)	UN. EMBT. (CY)
13+00.00	0	0
13+50.00	5	400