

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
SUMMARY OF EARTHWORK

CHAIN	BEGINNING STATION	ENDING STATION	UNCL. EXCA. C.Y.	UNDERCUT C.Y.	EMBANK. +% C.Y.	BORROW C.Y.	WASTE C.Y.
PHASE I							
-Y1-	15+00.00	17+50.00	3,754		7		3,747
-Y1-	18+50.00	19+50.00			2,275	2,275	
-Y1-	23+00.00	25+50.00	2,257		2		2,255
-DR18-	10+12.44	11+35.00	725				725
-RAB1-	11+25.00	12+75.00			5,717	5,717	
-L-	11+00.00	29+00.00	4,066		5,027	961	
-DR17-	11+00.00	11+50.00	3		5	2	
-DET-	12+00.00	18+50.00	48		10,819	10,771	
-Y3DET-	10+11.38	12+50.00	1,323		283		1,040
-L-	40+50.00	47+00.00	897	1,250	23,396	22,499	
-DR8-	10+85.00	11+23.59	19		1		18
-DR8-	12+24.40	13+21.20	9		1,342	1,333	
-Y5-	10+12.31	12+75.00	141		259	118	
-DR9-	10+11.88	11+65.00	118		337	219	
-L-	51+50.00	52+80.00			5,024	5,024	
-Y6-	10+19.89	12+00.00	1		769	768	
-RAB2-	12+25.00	13+25.00			6,966	6,966	
-Y8A-	10+10.31	13+18.25	2		1,699	1,697	
-L2-	54+54.00	57+00.00	9		4,753	4,744	
-L2-	57+00.00	66+00.00	690		761	71	
-Y9-	10+12.45	11+10.00	1		22	21	
-L2-	66+50.00	80+50.00	3,811		1,479		2,332
-Y11_DET-	11+86.00	17+68.07	2,856		2,000		856
-DR24_DET-	10+11.15	10+57.30	68				68
-DR25_DET-	10+12.89	10+84.40	78				78
-L3-	82+50.00	87+00.00	4	1,250	16,010	16,006	
-L3-	90+29.00	101+86.00	28,864		9,863		20,083
-L-	47+00.00	51+50.00	1,263		1,976	713	
SUBTOTAL			50,963	2,500	99,665	79,903	33,701
PHASE II							
-DET-	18+50.00	19+50.00	1,799		8		1,791
-L-	51+00.00	52+80.00			1,079	1,079	
-Y7-	19+50.00	21+40.00	13		1,704	1,691	
-L2-	57+50.00	80+50.00	2,339		6,898	4,559	
-RAB3-	10+00.00	13+58.14			17,128	17,128	
-Y11-	10+50.00	15+00.00	4		5,150	5,146	
-L3-	82+00.00	82+50.00	2		4,870	4,868	
-L3-	87+50.00	106+00.00	18,946		1,260		17,686
-DR101_2-	12+75.00	13+57.06	892				892
-L-	34+50.00	37+00.00	39,839		1,227		38,612
-DR2-	10+21.51	14+72.19	18,841				18,841
-DR2-	10+80.00	12+50.00	1,423				1,423
-L-	29+50.00	34+50.00	42,751		28		42,723
-L2-	66+00.00	77+00.00	2,181		140		2,041
-Y10-	10+12.29	11+25.00	5		3		2
SUBTOTAL			128,477		39,496	34,471	123,452
PHASE III							
-Y4-	10+50.00	13+00.00	302		3,496	3,194	
-DR5-	10+40.00	12+11.00	202		12		191
-DR4-	10+12.00	12+08.00	32		1,745	1,713	
-L-	30+64.06	33+39.60	9		526	517	
-Y3-	14+00.00	16+50.00	289		1,929	1,640	
-L-	37+00.00	40+50.00	5,774		5,592		182
-DR3-	12+60.00	14+97.04	245		3,315	3,070	
SUBTOTAL			6,853		16,614	10,133	372

[illegible]