

12/06/07

5/27/2026
R:\Roadway\Proj\U-5810_Rdy_psh03B_3_4.dgn
jch

COMPUTED BY: JHH DATE: 02/6/2026

CHECKED BY: JTC DATE: 03/04/2026

STATE OF NORTH CAROLINA

DIVISION OF HIGHWAYS

TEMPORARY GUARDRAIL SUMMARY

PROJECT REFERENCE NO. SHEET NO.

U-5810 3B-4

SURVEY LINE	BEG. STA.	END STA.	LOCATION	LENGTH			WARRANT POINT		"N" DIST. FROM E.O.L.	TOTAL SHOUL WIDTH	FLARE LENGTH		W		ANCHORS										IMPACT ATTENUATOR TYPE 350		SINGLE FACED CONCRETE BARRIER	CONCRETE MEDIAN BARRIER	TYPE "T" DBL FACE CONCRETE BARRIER	REMOVE GUARDRAIL	REMARKS				
				STRAIGHT	SHOP CURVED	DOUBLE FACED	APPROACH END	TRAILING END			APPROACH END	TRAILING END	APPROACH END	TRAILING END	XI MOD	XI	GREU TL-3	GREU TL-2	TYPE III	CAT-1	AT-1	B-77	TES	G	NG										
DET	11+52.28	14+60.00	LT	300.00			11+77.28	14+35.00	8.00'	11.00'	25.00'	25.00'						2																	
DET	15+30.00	18+39.96	RT	300.00			15+55.00	18+14.96	8.00'	11.00'	25.00'	25.00'						2																	
-DR2-	10+58.00	12+30.00	LT	206.25			10+64.25	12+36.25	0'	6.00'	6.25'	6.25'									2														
-Y1-	17+24.00	19+09.00	RT	187.50			17+49.00	18+84.00	2.00'	5.00'	25.00'	25.00'						2																	
TOTAL				993.75														6.00			2.00														
LESS ANCHOR DEDUCTIONS																																			
		QUANTITY	LF PER EA	TOTAL LF																															
	GREU TL-2	6.00	25	150.00																															
	AT-1	2.00	6.25	12.50																															
TOTAL GUARDRAIL (LF)				831.25																															
SAY (LF)				850.00			5 ADDITIONAL POSTS											6.00			2.00														