PROJECT REFERENCE NO.	SHEET NO.
U-5810	SIGN-3

APPROVED: DocuSigned by: David T Sears — 069183F28E5741E...

DATE: 7/2/2026

SEAL

NORTH CAROLINA PROFESSIONAL SEAL 044558 ENGINEER DAVID T. SEARS

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

(401) QUANTITY REQ'D 6

24" X 30"
R2-1

ONE "U" POST PER SIGN

(402) QUANTITY REQ'D 9

30" X 30"
W2-6

ONE "U" POST PER SIGN

(403) QUANTITY REQ'D 9

30" X 30"
W3-2

ONE "U" POST PER SIGN

(404) QUANTITY REQ'D 18

36" X 36" x 36"
R1-2

ONE "U" POST PER SIGN

(405) QUANTITY REQ'D 9

36" X 12"
R6-1R

ONE "U" POST PER SIGN

(406) QUANTITY REQ'D 4

30" X 30"
W14-2

ONE "U" POST PER SIGN

(407) QUANTITY REQ'D 9

30" X 30"
R1-1

ONE "U" POST PER SIGN

(408) QUANTITY REQ'D 1

18" X 18"
W13-1P

MOUNT BELOW SIGN 406 IN ONE INSTALLATION

(409) QUANTITY REQ'D 2

24" X 12"
W16-7PL

COLOR: FLUORESCENT YELLOW-GREEN

MOUNT BELOW SIGN 410 IN TWO INSTALLATIONS

(410) QUANTITY REQ'D 2

30" X 30"
W11-2

COLOR: FLUORESCENT YELLOW-GREEN

ONE "U" POST PER SIGN

(411) QUANTITY REQ'D 1



30" X 30"
W3-3

ONE "U" POST

(412) QUANTITY REQ'D 3

30" X 30"
W3-1

ONE "U" POST PER SIGN

(413) QUANTITY REQ'D 2

30" X 30"
W14-1

ONE "U" POST PER SIGN

(414) QUANTITY REQ'D 9

18" X 18"
W13-1P

MOUNT BELOW SIGN 402 IN NINE INSTALLATIONS

(415) QUANTITY REQ'D 9

OM-3L

PAID FOR AS
"TYPE 3 FLEXIBLE GROUND MOUNTED OBJECT MARKERS"
SEE SPECIAL PROVISION FOR DETAILS

(416) QUANTITY REQ'D 1

24" X 30"
R2-1

ONE "U" POST

RK&K
P: (919) 878-9560
8601 Six Forks Road, Forum 1,Suite 700
Raleigh, North Carolina 27615-3960
NC License No. F-0112
Engineers | Construction Managers | Planners | Scientists
www.rkk.com
Responsive People | Creative Solutions

06/18/26
U5810_SGN_E.dgn

TYPE "E" SIGNS