PROJ. REFERENCE NO.	SHEET NO.
U-5810	X-1D

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY PHASE 2

NOTE: QUANTITIES ARE APPROXIMATE ONLY. THE RESIDENT ENGINEER WILL RECROSS-SECTION THE WORK ACCURATELY WHEN THE PROJECT IS STAKEDOUT. THESE CROSS-SECTION NOTES WILL BE USED IN COMPUTING THE FINAL QUANTITIES FOR WHICH THE CONTRACTOR WILL BE PAID.

NOTE: EMBANKMENT DOES NOT INCLUDE BACKFILL FOR UNDERCUT

Station L2	Uncl. Exc. (cu. yd.)	Undercut (cu. yd.)	Embt (cu. yd.)
66+00.00	0		0
66+50.00	243		2
67+00.00	211		2
67+50.00	148		9
68+00.00	136		9
68+50.00	162		2
69+00.00	154		4
69+50.00	123		5
70+00.00	110		4
70+50.00	121		5
71+00.00	130		4
71+50.00	72		4
72+00.00	16		17
72+50.00	1		33
73+00.00	1		18
73+50.00	5		1
74+00.00	38		1
74+50.00	56		1
75+00.00	37		1
75+50.00	116		0
76+00.00	143		0
76+50.00	43		0
77+00.00	115		0

Station Y10	Uncl. Exc. (cu. yd.)	Undercut (cu. yd.)	Embt (cu. yd.)
10+12.29	0		0
10+50.00	3		1
11+00.00	2		2
11+25.00	0		0