

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
CROSS-SECTION SUMMARY PHASE 3

NOTE: QUANTITIES ARE APPROXIMATE ONLY. THE RESIDENT ENGINEER WILL RECROSS-SECTION THE WORK ACCURATELY WHEN THE PROJECT IS STAKEDOUT. THESE CROSS-SECTION NOTES WILL BE USED IN COMPUTING THE FINAL QUANTITIES FOR WHICH THE CONTRACTOR WILL BE PAID.

NOTE: EMBANKMENT DOES NOT INCLUDE BACKFILL FOR UNDERCUT

Station	Uncl. Exc.	Undercut	Embt	Station	Uncl. Exc.	Undercut	Embt
Y4	(cu. yd.)	(cu. yd.)	(cu. yd.)	L	(cu. yd.)	(cu. yd.)	(cu. yd.)
10+50.00	0		0	38+50.00	476		379
11+00.00	148		1854	39+00.00	1476		0
11+50.00	148		340	39+50.00	1943		0
12+00.00	3		521	40+00.00	1411		7
12+50.00	3		317	40+50.00	468		377
13+00.00	0		8				
Station	Uncl. Exc.	Undercut	Embt	Station	Uncl. Exc.	Undercut	Embt
Dr5	(cu. yd.)	(cu. yd.)	(cu. yd.)	Dr3	(cu. yd.)	(cu. yd.)	(cu. yd.)
10+40.00	0		0	12+60.00	0		0
10+50.00	11		0	13+00.00	0		0
10+91.43	57		3	13+50.00	6		109
11+43.79	48		5	14+00.00	117		225
12+11.00	86		3	14+50.00	117		963
				14+97.04	117		963
Station	Uncl. Exc.	Undercut	Embt				
Dr4	(cu. yd.)	(cu. yd.)	(cu. yd.)				
10+12.00	0		0				
10+50.00	0		550				
11+00.00	13		611				
11+50.00	13		296				
12+00.00	5		58				
12+08.00	1		2				
Station	Uncl. Exc.	Undercut	Embt				
L	(cu. yd.)	(cu. yd.)	(cu. yd.)				
30+64.06	0		0				
31+00.00	3		0				
31+50.00	5		36				
32+00.00	1		104				
32+50.00	0		142				
33+00.00	0		113				
33+39.60	0		62				
Station	Uncl. Exc.	Undercut	Embt				
Y3	(cu. yd.)	(cu. yd.)	(cu. yd.)				
14+00.00	0		0				
14+50.00	0		295				
15+00.00	0		798				
15+50.00	22		573				
16+00.00	69		11				
16+50.00	198		0				
Station	Uncl. Exc.	Undercut	Embt				
L	(cu. yd.)	(cu. yd.)	(cu. yd.)				
37+00.00	0		0				
37+50.00	0		2394				
38+00.00	0		1706				