PROJECT NO.	SHEET NO.	TOTAL NO.
2027CPT.13.04.20111	29	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	BEGIN MP	END MP	1220000000-E INCIDENTAL STONE BASE	1245000000-E SHOULDER RECONSTRUCTION	1260000000-E AGGREGATE SHOULDER BORROW	1297000000-E MILLING ASPHALT PAVEMENT, 1-1/2" DEPTH	1308000000-E MILLING ASPHALT PAVEMENT, 0" TO 1-1/2"	1308000000-E MILLING ASPHALT PAVEMENT, 0" TO 1-1/4"	1330000000-E INCIDENTAL MILLING	1519000000-E ASPHALT CONC SURFACE COURSE, TYPE S9.5B	1520000000-E LEVELING COURSE, TYPE S9.5B	1575000000-E ASPHALT BINDER FOR PLANT MIX	1704000000-E PATCHING EXISTING PAVEMENT	1881000000-E SINUSOIDAL MILLED RUMBLE STRIPS 8" (EDGELINE)	1881000000-E SINUSOIDAL MILLED RUMBLE STRIPS 18" (CENTERLINE)	2612500000-N REMOVE AND REPLACE CONCRETE CURB RAMPS	2738000000-E GENERIC PAVING ITEM, REMOVE AND REPLACE 4" CONCRETE SIDEWALK	2752000000-E GENERIC PAVING ITEM, REMOVE AND REPLACE 2'-6" CONCRETE CURB & GUTTER	2830000000-N ADJUSTMENT OF MANHOLES	2845000000-N ADJUSTMENT OF METER BOXES OR VALVE BOXES	7444000000-E INDUCTIVE LOOP SAWCUT	7456100000-E LEAD-IN CABLE (14-2)
								MI	FT			TON	SMI	TON	SY	SY	SY	SY	TON	TONS	TON	TON	LF	LF	EA	SY	LF	EA	EA	LF	LF
2027CPT.13.04.20111	BUNCOMBE	28	SR 3231 (REYNOLDS SCHOOL ROAD)	FROM SR 3121 (ROSE HILL ROAD) TO END OF STATE MAINTENANCE	4	2	2WU	0.79	18.50	0.00	0.79	54	1.58	205					662		50	142							7		
		29	SR 3268 (REYNOLDA DRIVE)	FROM SR 3231 (REYNOLDS SCHOOL ROAD) TO CUL DE SAC	4	2	2WU	0.22	21.00	0.00	0.22	5	0.44	57				635	248		17	11									
		30	SR 3277 (FOREST RUN DRIVE)	FROM SR 3121 (PINNERS COVE ROAD) TO CUL DE SAC	6	2	2WU	0.24	24.00	0.01	0.25					844		159	312		24	68									
		31	SR 3279 (REYNOLDS MIDDLE SCHOOL)	FROM SR 3279 (CHARLES A LYTLE LANE) TO HIGH SCHOOL ROAD INTERSECTION	5, 7	2	2WU	0.01	18.00	0.12	0.13		0.34	45		175		300	372		25	11									
		32	SR 3279 (CHARLES A LYTLE LANE)	FROM US 74 ALTERNATE PAVEMENT JOINT TO END OF MAINTENANCE	2, 8	2	2WU	0.11	22.00	0.02	0.13		0.22	28		35		325	126		11	52									
		33	SR 3282 (BREEZEWAY DRIVE)	FROM SR 3256 (TUCKAWAY DRIVE) TO END OF STATE MAINTENANCE	2, 6	2	2WU	0.14	20.00	0.00	0.14	5	0.28	36		166		225	173		13	36									
		34	SR 3290 (FOX RIDGE DRIVE)	FROM SR 3128 (EMMAS GROVE ROAD) TO CUL DE SAC	4	2	2WU	0.33	18.00	0.01	0.34	5	0.66	86				129	300		21	35									
		35	SR 3300 (WHITE PINE CIRCLE)	FROM SR 3221 (WHITE PINE DRIVE) TO SR 3221 (WHITE PINE DRIVE)	4	2	2WU	0.86	20.00	0.01	0.87	5	1.72	224				250	757		53	72									
		36	SR 3301 (WHITE PINE WAY)	FROM SR 3300 (WHITE PINE CIRCLE) TO SR 3300 (WHITE PINE CIRCLE)	4	2	2WU	0.13	20.00	0.00	0.13	5	0.26	34					115		8	11									
		37	SR 3302 (BALDWIN COURT)	FROM SR 3189 (BALDWIN ROAD) TO SR 3315 (MEADOWS CIRCLE)	4	2	2WU	0.17	19.00	0.01	0.18	20	0.34	45				190	171		13	36									
		38	SR 3305 (WOODHAVEN DRIVE)	FROM SR 3187 (PENSACOLA AVENUE) TO END OF STATE MAINTENANCE	2	2	2WU	0.11	20.00	0.00	0.11	5	0.38	49					160		11	11									
		39	SR 3318 (SPRING COVE COURT)	FROM BEGIN OF STATE MAINTENANCE TO END OF STATE MAINTENANCE	9	2	2WU	0.06	20.00	0.00	0.06	5					1,192	115	212		14	11									
		40	SR 3326 (WESTON HEIGHTS DRIVE)	FROM SR 3150 (CONCORD ROAD) TO CUL DE SAC	9	2	2WU	0.46	20.00	0.01	0.47	5					3,239	125	429		32	85									
		41	SR 3327 (MEADOW WOOD TRAIL)	FROM SR 3131 (LYTLE ROAD) TO CUL DE SAC	2	2	2WU	0.34	20.00	0.00	0.34	5	0.68	88				479	378		27	53								1		
		42	SR 3335 (MEADOW BROOK DRIVE)	FROM SR 3327 (MEADOW WOOD TRAIL) TO SR 3327 (MEADOW WOOD TRAIL)	4	2	2WU	0.46	18.50	0.00	0.46	5	0.92	120					384		28	62								3		
		43	SR 3336 (WESTON PLACE)	FROM SR 3326 (WESTON HEIGHTS DRIVE) TO CUL DE SAC	9	2	2WU	0.04	20.00	0.00	0.04	5					724		70		5	15									
		44	SR 3342 (SPRINGFIELD WAY)	FROM SR 3189 (BALDWIN ROAD) TO CUL DE SAC	9	2	2WU	0.10	18.00	0.00	0.10	5					704	125	100		7	12								1		
		45	SR 3345 (WESTON WAY)	FROM SR 3326 (WESTON HEIGHTS DRIVE) TO CUL DE SAC	9	2	2WU	0.05	20.00	0.00	0.05	5					352		69		6	22									
		46	SR 3347 (EMERALD COURT)	FROM SR 3189 (BALDWIN ROAD) TO CUL DE SAC	4	2	2WU	0.07	19.00	0.01	0.08	5	0.16	21				115	66		5	11									
		47	SR 3348 (KIT COURT)	FROM SR 3290 (FOX RIDGE DRIVE) TO CUL DE SAC	4	2	2WU	0.17	18.00	0.00	0.17	5	0.34	44					158		11	20									
		48	SR 3354 (CANE CREEK CIRCLE)	FROM SR 3136 (CANE CREEK ROAD) TO SR 3355 (CANE CREEK CIRCLE)	4	2	2WU	0.25	18.50	0.01	0.26	5	0.50	65				155	201		14	23									
		49	SR 3355 (CANE CREEK CIRCLE)	FROM SR 3354 (CANE CREEK CIRCLE) TO CUL DE SAC	4	2	2WU	0.28	18.00	0.00	0.28	5	0.54	70					241		17	38									
		50	SR 3356 (KNOLL DRIVE)	FROM SR 3138 (UPPER BRUSH CREEK ROAD) TO CUL DE SAC	4	2	2WU	0.15	19.00	0.00	0.15	5	0.30	39				167	156		11	20									
		51	SR 3357 (SOUTH KNOLL COURT)	FROM SR 3356 (KNOLL DRIVE) TO CUL DE SAC	4	2	2WU	0.05	18.00	0.00	0.05	5	0.10	13					80		6	11									
		52	SR 3358 (MOUNTAIN VIEW LANE)	FROM SR 3335 (MEADOW BROOK DRIVE) TO CUL DE SAC	4	2	2WU	0.13	20.00	0.00	0.13	5	0.26	34					142		11	29								2		
		53	SR 3374 (SPRING LAKE DRIVE)	FROM SR 3136 (CANE CREEK ROAD) TO CUL DE SAC	4	2	2WU	0.36	18.00	0.01	0.37	10	0.72	94				225	312		24	86									
		54	SR 3375 (KNOLLWOOD DRIVE)	FROM SR 3374 (SPRING LAKE DRIVE) TO CUL DE SAC	4	2	2WU	0.05	18.00	0.00	0.05	5	0.10	13					56		4	14									
		55	SR 3376 (GUN FLINT TRAIL)	FROM SR 3374 (SPRING LAKE DRIVE) TO CUL DE SAC	4	2	2WU	0.17	18.00	0.00	0.17	6	0.34	45					168		12	15									
		56	SR 3503 (TC ROBERSON HIGH SCHOOL)	FROM SPRINGSIDE ROAD (CITY) TO SPRINGSIDE ROAD (CITY)	5, 7	2	2WU	0.01	30.00	1.48	1.49		0.54	70		695		575	686		45	15									
		57	SR 3503 (OVERLOOK ROAD)	FROM US 25 (HENDERSONVILLE ROAD) TO NC 146 (LONG SHOALS ROAD)	3	2	2WU	1.86	24.00	0.02	1.88	6			28,777				2,590		170	30	755	755	9	10	15	5	6	1,320	500
		58	SR 3503 (OVERLOOK ROAD EXTENSION)	FROM NC 146 (LONG SHOALS ROAD) TO END OF MAINTENANCE	3	2	2WU	0.05	24.00	1.91	1.96	5			740				70		5	11								408	250
TOTAL FOR PROJ NO. 2027CPT.13.04.20111								**35.89**				**803**	**55.55**	**7,254**	**38,339**	**2,643**	**6,211**	**21,728**	**34,356**	**320**	**2,505**	**5,233**	**755**	**755**	**9**	**10**	**15**	**42**	**40**	**2,160**	**824**
GRAND TOTAL								**35.89**				**803**	**55.55**	**7,254**	**38,339**	**2,643**	**6,211**	**21,728**	**34,356**	**320**	**2,505**	**5,233**	**755**	**755**	**9**	**10**	**15**	**42**	**40**	**2,160**	**824**