Docusign Envelope ID: 26802295-3CD8-8E50-80CF-5CD34BF3DEF2

TIP PROJECT: U-3422B

CONTRACT: C205231 TI

# STATE OF NORTH CAROLINA
# DEPARTMENT OF TRANSPORTATION

HDR Engineering, Inc. of the Carolinas
555 Fayetteville St, Suite 900 Raleigh, N.C. 27601
N.C.B.E.L.S. License Number: F-0116

| TIP NO. | SHEET NO. |
|---|---|
| U-3422B | SIGN-1 |

APPROVED: Michael T. Rzepka

DATE: 11/3/2026

SEAL

NORTH CAROLINA PROFESSIONAL SEAL 15876 ENGINEER MICHAEL T. RZEPKA

**DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED**

# SIGNING PLAN
# CUMBERLAND COUNTY

## LOCATION: SR 1003 (Camden Road) from just West of SR 1112 (Rockfish Rd) To (SR 1596) Hope Mills Road

## ROADWAY STANDARD DRAWING

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2024 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

| STD. NO. | TITLE |
|---|---|
| 904.10 | ORIENTATION OF GROUND MOUNTED SIGNS |
| 904.50 IN=LIEU OF 904D5001 & 2 | MOUNTING OF TYPE 'D', 'E' AND 'F' SIGNS ON 'U' CHANNEL POSTS |
| 910.20 | SCHOOL MARKED AND UNMARKED CROSSWALKS / SPEED REDUCTION REQUIREMENTS |
| 910.30 | SIGNING SIGNALIZED AND UNSIGNALIZED SUPERSTREET |

## GENERAL NOTES

. SIGNS FURNISHED BY STATE
. CONFIRM IN WRITING AT LEAST 4 MONTHS IN ADVANCE, THE ACTUAL DATE THE DEPARTMENT FURNISHED SIGNS WILL BE REQUIRED.
. ALL TYPE 'D' SIGNS SHALL BE MOUNTED ON TWO U-CHANNEL POSTS UNLESS OTHERWISE INDICATED ON THE PLANS.
. IF REMOVAL OR RELOCATION OF SIGNS ON PRIVATE STREET (NON-STATE MAINTAINED) IS REQUIRED DUE TO CONSTRUCTION, THE CONTRACTOR SHALL INFORM THE ENGINEER. THE WORK WILL BE COMPLETED BY OTHERS.
. WHEN NOT STATIONED OR DIMENSIONED ON PLANS, ALL 'E' AND 'F' SIGNS SHALL BE FIELD LOCATED BY THE ENGINEER
. ALL EXISTING SIGNS ON "U" CHANNEL POST WITHIN THE PROJECT LIMITS SHALL BE REMOVED AND DISPOSED OF UNLESS OTHERWISE NOTED ON PLANS.
. WHEN EXISTING SIGNS ARE REMOVED AND INSTALLED ON NEW SUPPORTS, THE RE-ERECTION SHALL IMMEDIATELY FOLLOW THE REMOVAL.
. THE BACKGROUND FOR TYPE E & F SIGNS SHALL BE TYPE C REFLECTIVE SHEETING.
. SEE ROADWAY PLANS FOR GUARD/GUIDE RAIL DETAILS.

## SUMMARY OF QUANTITIES

| ITEM NO. | | ITEM DESCRIPTION | QUANTITY | UNIT |
|---|---|---|---|---|
| DESC. NO. | SECT. NO. | | | |
| 4072000000 | 903 | SUPPORTS, 3 LB STEEL U-CHANNEL | 2401 | L.F. |
| 4096000000 | 904 | SIGN ERECTION, TYPE D | 2 | EA. |
| 4102000000 | 904 | SIGN ERECTION, TYPE E | 168 | EA. |
| 4116100000 | 904 | SIGN ERECTION, RELOCATE SIGN TYPE D | 2 | EA. |
| 4155000000 | 907 | DISPOSAL OF SIGN SYSTEM, U-CHANNEL | 60 | EA. |
| 4192000000 | 907 | DISPOSAL OF SUPPORT, U-CHANNEL | 4 | EA. |

## INDEX


| SHEET NO. | DESCRIPTION |
|---|---|
| SIGN-1 | TITLE SHEET |
| SIGN-1A & 1B | MOUNTING OF TYPE 'D', 'E' AND 'F' SIGNS ON 'U' CHANNEL POSTS |
| SIGN-2 | E SHEET |
| SIGN-3 | SIGN DESIGNS |
| SIGN-4-17 | SIGN DETAIL SHEETS |


## PROJECT NOTES

1. DISPOSAL OF SIGN SYSTEM, U-CHANNEL
2. RELOCATE SIGN, TYPE D

**PLAN SUBMITTED TO: N.C.D.O.T. SIGNING AND DELINEATION UNIT**

| | |
|---|---|
| MITCH EATON, PE | SIGNING & DELINEATION REGIONAL ENGINEER |
| MATT TRACEY, PE | SIGNING & DELINEATION PROJECT DESIGN ENGINEER |

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

**PLAN PREPARED BY: HDR Engineering, Inc. of the Carolinas**

| | |
|---|---|
| MIKE RZEPKA, PE | PROJECT ENGINEER |
| RICHARD DRAYTON | TRAFFIC DESIGN ENGINEER |