ADA SUMMARY OF QUANTITIES - TOTALS

WBS	2027CPT.05.05.20321
Number:	2027CPT.05.05.20322
County:	Durham

Sheet No.
19

WBS Number	County	Municipality	Resurfacing Route	4447000000-E (LF) Pedestrian Channelizing Devices	4600000000-N (EA) Generic Traffic Control Item - Pedestrian Transport Service (Per Trip)	4600000000-N (EA) Generic Traffic Control Item - Audible Warning Devices	0156000000-E (SY) Removal of Existing Asphalt Pavement	1704000000-E (TON) Patching Existing Pavement	2549000000-E (LF) 2'-6" Concrete Curb & Gutter	2752000000-E (LF) Remove And Replace 2'-6" Concrete Curb & Gutter	0257000000-E (LF) Remove 2'-6" Concrete Curb & Gutter	2591000000-E (SY) 4" Concrete Sidewalk	2738000000-E (SY) Remove And Replace 4" Concrete Sidewalk	0241000000-E (SY) Remove 4" Concrete Sidewalk	2830000000-N (EA) Adjustment of Manholes	2845000000-N (EA) Adjustment of Meter Boxes or Valve Boxes	2655000000-E (SY) 5" Monolithic Concrete Island (Keyed In)	2738000000-E (SY) Remove And Replace 5" Monolithic Concrete Islands (Keyed In)	0241000000-E (SY) Remove 5" Monolithic Concrete Islands (Keyed In)	2612500000-N (EA) Remove and Replace Concrete Curb Ramps	2605000000-N (EA) Concrete Curb Ramps	0262000000-N (EA) Remove Concrete Curb Ramps
2027CPT.05.05.20321	Durham	Durham	MLK Pkwy From NC 751 To SR 2220	40	10	2	8	0	0	128	10	27	72	59	0	4	0	0	0	32	1	0
2027CPT.05.05.20321	Durham	Outside Municipality	Cornwallis Rd. From SR 2028 To Width Change	24	10	1	6	5	30	72	0	15	9	0	0	1	16	0	0	18	0	3
2027CPT.05.05.20321	Durham	Durham Outside Municipality	Cornwallis Rd. From Width Change To SR 1959	8	0	0	34	1	15	0	0	0	0	0	0	0	30	0	0	0	0	3
2027CPT.05.05.20321	Durham	Durham Outside Municipality	Miami Blvd From US 70 To SR 2028	88	20	3	112	20	32	310	20	102	147	0	1	1	80	10	146	75	3	4
2027CPT.05.05.20322	Durham	Durham	Crystal Lake Rd From END MAINT To NC 157	8	1	0	0	0	0	8	0	0	3	0	0	0	0	0	0	2	0	0
2027CPT.05.05.20322	Durham	Durham	Colony Rd. From SR 1303 To Begin C&G	4	1	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1	0	0
2027CPT.05.05.20322	Durham	Durham Outside Municipality	Stone Rd. From SR 1955 To Pavement Joint @ C&G	12	1	1	0	1	0	12	0	0	6	9	0	0	0	0	0	3	0	0
2027CPT.05.05.20322	Durham	Durham	Bandock Rd From SR 2042 To SR 2044	4	1	0	0	0	0	4	0	0	0	0	0	0	0	0	0	1	0	0
GRAND TOTAL				**188**	**44**	**7**	**160**	**27**	**77**	**534**	**30**	**144**	**237**	**68**	**1**	**6**	**126**	**10**	**146**	**132**	**4**	**10**

Notes: (1) Construct in accordance with Section 848. Detectable warnings shall be of one of the following materials: engineered plastics, rubber, or composite tile. Additionally, warnings shall be applied directly to the curb ramps by incorporating into the concrete of the curb ramps unless otherwise approved by the Engineer. Surface mounted rubber mats, brick, steel and stamped concrete pavers will not be accepted. (2) In accordance with PROWAG Sections R304.2.1 and R304.3.1, curb ramp running slope is to be constructed to a maximum of 8.33%. Where the curb ramp length must exceed 15 feet to achieve an 8.33% running slope, the curb ramp length shall extend at least 15 feet and may have a running slope greater than 8.33%.