4/20/20

REVISIONS

PROJECT REFERENCE NO.	SHEET NO.
R-5711	RW02D-1
Location and Surveys	

PROPOSED ALIGNMENT CONTROL SHEET

L

TYPE	STATION	NORTH	EAST
POT	10+00.00	705644.8114	1448611.8655
PC	19+88.98	706528.7770	1448168.3681
PT	24+24.41	706937.6883	1448021.8483
PC	27+22.68	707228.5615	1447955.8524
PT	30+05.04	707492.9327	1447858.9127
PC	33+03.11	707757.3490	1447721.3215
PRC	36+31.83	708045.8135	1447563.7446
PT	38+73.43	708257.8260	1447447.9304
POT	41+56.30	708508.7609	1447317.3543

Y1

TYPE	STATION	NORTH	EAST
POT	10+00.00	706289.7903	1447276.0540
PC	12+82.32	706277.2599	1447558.0995
PT	14+58.42	706287.9244	1447733.5525
POT	15+60.17	706304.7174	1447833.8986

Y2

TYPE	STATION	NORTH	EAST
POT	10+00.00	705607.9617	1447802.0378
PC	16+46.47	706253.6413	1447834.0584
PT	19+33.57	706528.0174	1447765.0429
PC	21+03.57	706673.6177	1447677.2902
PT	28+43.56	707327.6681	1447823.8787
POT	29+45.00	707383.8877	1447908.3119

Y3

TYPE	STATION	NORTH	EAST
POT	10+00.00	707383.8877	1447908.3119
PC	10+72.14	707423.8708	1447968.3603
PT	12+56.35	707502.7592	1448134.1209
POT	22+60.34	707800.3777	1449092.9844

Y4

TYPE	STATION	NORTH	EAST
POT	10+00.00	706559.2022	1448576.4366
PC	12+52.05	706777.3344	1448450.1515
PT	15+05.95	707006.1509	1448340.7163
POT	20+42.67	707507.0418	1448147.9185

DRW1

TYPE	STATION	NORTH	EAST
POT	10+00.00	706678.6167	1447831.2909
PC	10+31.32	706679.4980	1447799.9784
PT	10+59.85	706672.3414	1447772.7620
POT	11+40.96	706630.4729	1447703.2934

NOTES:

1. PROJECT CONTROL WAS ESTABLISHED USING GNSS, THE GLOBAL NAVIGATION SATELLITE SYSTEM.

2. THE PROPOSED ALIGNMENT CONTROL DATA FOR THIS PROJECT HAS BEEN COMPILED FROM VARIOUS SOURCES. IF FURTHER INFORMATINO REGARDING PROJECT CONTROL IS NEEDED, PLEASE CONTACT THE LOCATION AND SURVEYS UNIT.

20-APR-2020 13:06
C:\Projects\R-5711_FlowerhouseRd_near_US21-I77\US12-20-017_RW_rev\r5711_ls_rw02d-1.dgn
jleffreys AT LS-31619