PROJECT NO.	SHEET NO.	TOTAL NO.
2027CPT.08.02.10531, 2027CPT.08.02.20531	17	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	LENGTH	WIDTH	BEGIN MP	END MP	1220000000-E INCIDENTAL STONE BASE	1245000000-E SHOULDER RECONSTRUCTION	1260000000-E AGGREGATE SHOULDER BORROW	1297000000-E 1.5" MILLING	1330000000-E INCIDENTAL MILLING	1491000000-E BASE COURSE, B25.0C	1519000000-E SURFACE COURSE, S9.5B	1523000000-E SURFACE COURSE, S9.5C	1575000000-E ASPHALT BINDER FOR PLANT MIX	1704000000-E PATCHING EXISTING PAVEMENT	1775500000-E ASPHALT SURFACE TREATMENT, MATCOAT, 67 STONE	1838000000-E EMULSION FOR ASPHALT SURFACE TREATMENT	1838500000-N VACUUM TRUCK	1891000000-E GENERIC PAVING ITEM - (SCRUB SEAL)	2143000000-E BLOTTING SAND	2830000000-N ADJUST MANHOLES	2845000000-N ADJUST METER OR VALVE BOX	5255000000-N PORTABLE LIGHTING	7444000000-E INDUCTIVE LOOP SAWCUT
									MI	FT			TONS	SMI	TON	SY	SY	TONS	TONS	TONS	TONS	TONS	SY	GAL	WK	SY	TON	EA	EA	LS	LF
2027CPT.08.02.10531	Lee	1	US-1 BUS	FROM SR 1002 (CHARLOTTE AVE) TO SR 1488 +0.55 MILES	1,2	2	2WU	NO	1.967	34	12.113	14.080				41,196	550			3,506	232	527						30	42		552
TOTAL FOR MAP NO. 1									**1.967**							**41,196**	**550**			**3,506**	**232**	**527**						**30**	**42**		**552**
2027CPT.08.02.10531	Lee	2	US-1 BUS	FROM C&G AT US 421 BYP TO SR 1420 (AMOS BRIDGES RD)	3	2	2WU	NO	0.896	28	14.080	14.976		1.79	250.88		356			1,341	80	15							4		
TOTAL FOR MAP NO. 2									**0.896**					**1.79**	**250.88**		**356**			**1,341**	**80**	**15**							**4**		
2027CPT.08.02.10531	Lee	3	US-421 BUS	FROM WASHINGTON AVE. TO PAVEMENT JOINT SOUTH OF W CHRISHOLM ST.	4	2		NO	0.830	48	3.970	4.800				24,500	2,720			2,300	136	15						40	24		4,000
TOTAL FOR MAP NO. 3									**0.830**							**24,500**	**2,720**			**2,300**	**136**	**15**						**40**	**24**	*	**4,000**
2027CPT.08.02.10531	Lee	4	NC-78	FROM SR 1152 + 0..08 MI (FIRETOWER RD PAVEMENT JOINT) TO SR 1001 (LEMON SPRINGS RD))	1,4	2		NO	1.740	38	1.910	3.650				40,730	2,900			3,665	216							4	16		750
TOTAL FOR MAP NO. 4									**1.740**							**40,730**	**2,900**			**3,665**	**216**							**4**	**16**		**750**
TOTAL FOR PROJ NO. 2027CPT.08.02.10531									**5.433**					**1.79**	**250.88**	**106,426**	**6,526**			**10,812**	**664**	**557**						**74**	**86**	**1**	**5,302**
2027CPT.08.02.20531	Lee	5	SR-1100 / SPRING LN	FROM SR 1325 (COOL SPRINGS RD) TO 0.02 MI EAST OF SR 1328 (WILKINS DR)	6	2	2WU	NO	1.190	24	0.000	1.190		2.30	322.20		400		1,590		104	15	16,893.30	6,757	1.00		20		2		864
TOTAL FOR MAP NO. 5									**1.190**					**2.30**	**322.20**		**400**		**1,590**		**104**	**15**	**16,893.30**	**6,757**	**1.00**		**20**		**2**		**864**
2027CPT.08.02.20531	Lee	6	SR-1100 / SPRING LN/W. WEATHERSPOON ST	FROM BRIDGE AT US 1 TO US 421 BUS	5	2	2WU	NO	0.723	36	1.520	2.243				15,270	2,038		1,480		110	290						12	40		2,508
TOTAL FOR MAP NO. 6									**0.723**							**15,270**	**2,038**		**1,480**		**110**	**290**						**12**	**40**		**2,508**
2027CPT.08.02.20531	Lee	7	SR-1305 / HENLEY RD	FROM SR 1303 (CENTER CHURCH RD) TO SR 1303 (CENTER CHURCH RD)	7	2	2WU	NO	4.148	23	0.000	4.148	40	8.30	1,162.00		350		5,031		354	565									
TOTAL FOR MAP NO. 7									**4.148**				**40**	**8.30**	**1,162.00**		**350**		**5,031**		**354**	**565**									
2027CPT.08.02.20531	Lee	8	SR-1335 / BRIDGES RD	FROM SR 1318 (STEEL BRIDGE ROAD) TO SR 1332 (S FRANKLIN DR)	8	2	2WU	NO	0.860	18.5	0.000	0.860	20	1.72	245.00		150		800		53	20		2,940		9,800.00	15				
TOTAL FOR MAP NO. 8									**0.860**				**20**	**1.72**	**245.00**		**150**		**800**		**53**	**20**		**2,940**		**9,800.00**	**15**				
2027CPT.08.02.20531	Lee	9	SR-1319 / PICKARD RD	SR 1318 (STEEL BRIDGE ROAD) TO NC 42	9	2	2WU	NO	3.386	22	0.000	3.386	40	6.73	942.20		280	2,251	3,982		381	433									
TOTAL FOR MAP NO. 9									**3.386**				**40**	**6.73**	**942.20**		**280**	**2,251**	**3,982**		**381**	**433**									
2027CPT.08.02.20531	Lee	10	SR-1588 / VALLEY VIEW DR	SR 1002 (LOWER MONCURE RD) TO SR 1508 (LICK CREEK RD)	6	2	2WU	NO	0.380	20	0.000	0.380	10	0.76	106.40		230		405		34	150	4,680.00	1,872			10				
TOTAL FOR MAP NO. 10									**0.380**				**10**	**0.76**	**106.40**		**230**		**405**		**34**	**150**	**4,680.00**	**1,872**			**10**				
2027CPT.08.02.20531	Lee	11	SR-1422 / OSGOOD RD	FROM SR 1423 (FARRELL ROAD) TO SR 1415 (COLON RD)	7	2	2WU	NO	1.413	18.5	0.000	1.413	20	2.83	395.64		110		1,382		107	368									
TOTAL FOR MAP NO. 11									**1.413**				**20**	**2.83**	**395.64**		**110**		**1,382**		**107**	**368**									
2027CPT.08.02.20531	Lee	12	SR-1433 / WOMBLE RD	FROM SR 1423 (FARRELL RD) TO SR 1466 (DEEP RIVER RD)	6	2	2WU	NO	0.670	20	0.000	0.670	10	1.34	187.60		140		713		51	100	8,000.00	3,200			15				
TOTAL FOR MAP NO. 12									**0.670**				**10**	**1.34**	**187.60**		**140**		**713**		**51**	**100**	**8,000.00**	**3,200**			**15**				
TOTAL FOR PROJ NO. 2027CPT.08.02.20531									**12.770**				**140**	**23.98**	**3,361.04**	**15,270**	**3,698**	**2,251**	**15,383**		**1,194**	**1,941**	**29,573.30**	**14,769**	**1.00**	**9,800.00**	**60**	**12**	**42**		**3,372**
GRAND TOTAL									**18.203**				**140**	**25.77**	**3,611.92**	**121,696**	**10,224**	**2,251**	**15,383**	**10,812**	**1,858**	**2,498**	**29,573.30**	**14,769**	**1.00**	**9,800.00**	**60**	**86**	**128**	**1**	**8,674**