PROJECT NO.	SHEET NO.	TOTAL NO.
2027CPT.08.02.10531, 2027CPT.08.02.20531	18	

THERMOPLASTIC AND PAINT QUANTITIES

												4413000000-E	4457000000-N	4510000000-N	4688000000-E		4695000000-E	4700000000-E		4709000000-E	4720000000-E			4725000000-E						4815000000-E		4820000000-E	4825000000-E		4835000000-E	4840000000-N	4845000000-N						4890000000-E	4890000000-E	4895000000-N		4900000000-N	
PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	BEGIN MP	END MP	WORK ZONE ADVANCE/ GENERAL WARNING SIGNING	TEMPORARY TRAFFIC CONTROL	LAW ENFORCEMENT	6" X 90 M WHITE THERMO	6" X 90 M YELLOW THERMO	8" X 90 M WHITE THERMO	12" X 90 M YELLOW THERMO	12" X 90 M WHITE THERMO	24" X 90 M WHITE THERMO	THERMO MSG SCHOOL 90 M	THERMO MSG STOP 90 M	THERMO MSG AHEAD 90 M	THERMO LT ARROW 90 M	THERMO RT ARROW 90 M	THERMO STR & RT ARROW 90 M	THERMO STR ARROW 90 M	THERMO LT STR RT ARROW 90 M	THERMO STR & LT ARROW 90 M	6" WHITE PAINT	6" YELLOW PAINT	8" WHITE PAINT	12" YELLOW PAINT	12" WHITE PAINT	24" WHITE PAINT	PAINT MSG SCHOOL	PAINT LT ARROW	PAINT RT ARROW	PAINT STR & RT ARROW	PAINT STR ARROW	PAINT LT STR RT ARROW	PAINT STR & LT ARROW	GENERIC PAVEMENT MARKING ITEM - 24" YIELD LINE PAINT	GENERIC PAVEMENT MARKING ITEM - 24" YIELD LINE THERMO 90 MILS	GENERIC PAVEMENT MARKING ITEM POLYCARBONATE H-SHAPED MARKERS C&R	GENERIC PAVEMENT MARKING ITEM POLYCARBONATE H-SHAPED MARKERS Y&Y	PERMANENT RAISED MARKERS (YELLOW & YELLOW)	PERMANENT RAISED PAVEMENT MARKERS (CRYSTAL & RED)
								MI	FT			SF	LS	HR	LF	LF	LF	LF	LF	LF	EA	EA	EA	EA	EA	EA	EA	EA	EA	LF	LF	LF	LF	LF	LF	EA	EA	EA	EA	EA	EA	EA	LF	LF	EA	EA	EA	EA
2027CPT.08.02.10531	Lee	1	US-1 BUS	FROM SR 1002 (CHARLOTTE AVE) TO SR 1488 +0.55 MILES	1,2	2	2WU	1.967	34	12.113	14.08	220		80	12,415	19,856		209		140				29	1	5	2			12,995	20,436		209		140		29	1	5	2					38	202		
TOTAL FOR MAP NO. 1								**1.967**				**220**		**80**	**12,415**	**19,856**		**209**		**140**				**29**	**1**	**5**	**2**			**12,995**	**20,436**		**209**		**140**		**29**	**1**	**5**	**2**					**38**	**202**		
2027CPT.08.02.10531	Lee	2	US-1 BUS	FROM C&G AT US 421 BYP TO SR 1420 (AMOS BRIDGES RD)	3	2	2WU	0.896	28	14.08	14.976	100			8,284	9,918		178						7																					20	88		
TOTAL FOR MAP NO. 2								**0.896**				**100**			**8,284**	**9,918**		**178**						**7**																					**20**	**88**		
2027CPT.08.02.10531	Lee	3	US-421 BUS	FROM WASHINGTON AVE. TO PAVEMENT JOINT SOUTH OF W CHRISHOLM ST.	4	2		0.83	48	3.97	4.8	90	*		2,475	9,400		60		375				12		16	10	2	4	2,475	9,400		60		375		12		16	10	2	4			212	115		
TOTAL FOR MAP NO. 3								**0.83**				**90**			**2,475**	**9,400**		**60**		**375**				**12**		**16**	**10**	**2**	**4**	**2,475**	**9,400**		**60**		**375**		**12**		**16**	**10**	**2**	**4**			**212**	**115**		
2027CPT.08.02.10531	Lee	4	NC-78	FROM SR 1152 + 0..08 MI (FIRETOWER RD PAVEMENT JOINT) TO SR 1001 (LEMON SPRINGS RD))	1,4	2		1.74	38	1.91	3.65	200		80	19,300	23,500	160	255	175	90	6			46	3	8	3			19,300	23,500	160	255	175	140	6	46	3		3			20	20	115	355		
TOTAL FOR MAP NO. 4								**1.74**				**200**		**80**	**19,300**	**23,500**	**160**	**255**	**175**	**90**	**6**			**46**	**3**	**8**	**3**			**19,300**	**23,500**	**160**	**255**	**175**	**140**	**6**	**46**	**3**		**3**			**20**	**20**	**115**	**355**		
TOTAL FOR PROJ NO. 2027CPT.08.02.10531								**5.433**				**610**	*****	**160**	**42,474**	**62,674**	**160**	**702**	**175**	**605**	**6**			**94**	**4**	**29**	**15**	**2**	**4**	**34,770**	**53,336**	**160**	**524**	**175**	**655**	**6**	**87**	**4**	**21**	**15**	**2**	**4**	**20**	**20**	**385**	**760**		
															105,148			**877**			**6**			**148**						**88,106**			**699**				**133**								**1,145**			
2027CPT.08.02.20531	Lee	5	SR-1100 / SPRING LN	FROM SR 1325 (COOL SPRINGS RD) TO 0.02 MI EAST OF SR 1328 (WILKINS DR)	6	2	2WU	1.19	24	0	1.19	135		40	12,280	9,690				34										12,280	9,690				34												86	
TOTAL FOR MAP NO. 5								**1.19**				**135**		**40**	**12,280**	**9,690**				**34**										**12,280**	**9,690**				**34**												**86**	
2027CPT.08.02.20531	Lee	6	SR-1100 / SPRING LN/W. WEATHERSPOON ST	FROM BRIDGE AT US 1 TO US 421 BUS	5	2	2WU	0.723	36	1.52	2.243	255		80	4,978	7,326	130	133		138				7	2	5			1	6,508	9,678	130	169		138		9	2	5	2		1	50	50			81	45
TOTAL FOR MAP NO. 6								**0.723**				**255**		**80**	**4,978**	**7,326**	**130**	**133**		**138**				**7**	**2**	**5**			**1**	**6,508**	**9,678**	**130**	**169**		**138**		**9**	**2**	**5**	**2**		**1**	**50**	**50**			**81**	**45**
2027CPT.08.02.20531	Lee	7	SR-1305 / HENLEY RD	FROM SR 1303 (CENTER CHURCH RD) TO SR 1303 (CENTER CHURCH RD)	7	2	2WU	4.148	23	0	4.148	495			43,802	42,142						4	5							43,802	42,142																	
TOTAL FOR MAP NO. 7								**4.148**				**495**			**43,802**	**42,142**						**4**	**5**							**43,802**	**42,142**																	
2027CPT.08.02.20531	Lee	8	SR-1335 / BRIDGES RD	FROM SR 1318 (STEEL BRIDGE ROAD) TO SR 1332 (S FRANKLIN	8	2	2WU	0.86	18.5	0	0.86	100	*		9,254	7,750														9,254	7,750																	
TOTAL FOR MAP NO. 8								**0.86**				**100**			**9,254**	**7,750**														**9,254**	**7,750**																	
2027CPT.08.02.20531	Lee	9	SR-1319 / PICKARD RD	SR 1318 (STEEL BRIDGE ROAD) TO NC 42	9	2	2WU	3.386	22	0	3.386	380			35,534	30,306														35,534	30,306																	
TOTAL FOR MAP NO. 9								**3.386**				**380**			**35,534**	**30,306**														**35,534**	**30,306**																	
2027CPT.08.02.20531	Lee	10	SR-1588 / VALLEY VIEW DR	SR 1002 (LOWER MONCURE RD) TO SR 1508 (LICK CREEK RD)	6	2	2WU	0.38	20	0	0.38	43			4,000	4,000														4,000	4,000																	
TOTAL FOR MAP NO. 10								**0.38**				**43**			**4,000**	**4,000**														**4,000**	**4,000**																	
2027CPT.08.02.20531	Lee	11	SR-1422 / OSGOOD RD	FROM SR 1423 (FARRELL ROAD) TO SR 1415 (COLON RD)	7	2	2WU	1.413	18.5	0	1.413	160			14,604	12,534														14,604	12,534																	
TOTAL FOR MAP NO. 11								**1.413**				**160**			**14,604**	**12,534**														**14,604**	**12,534**																	
2027CPT.08.02.20531	Lee	12	SR-1433 / WOMBLE RD	FROM SR 1423 (FARRELL RD) TO SR 1466 (DEEP RIVER RD)	6	2	2WU	0.67	20	0	0.67	75			6,758	4,448														6,758	4,448																	
TOTAL FOR MAP NO. 12								**0.67**				**75**			**6,758**	**4,448**														**6,758**	**4,448**																	
TOTAL FOR PROJ NO. 2027CPT.08.02.20531								**12.77**				**1,643**	*****	**120**	**131,210**	**118,196**	**130**	**133**		**172**		**4**	**5**	**7**	**2**	**5**			**1**	**132,740**	**120,548**	**130**	**169**		**172**		**9**	**2**	**5**	**2**		**1**	**50**	**50**			**167**	**45**
															249,406			**133**			**9**			**15**						**253,288**			**169**				**19**										**212**	
GRAND TOTAL								**18.203**				**2,253**	**1.000**	**280**	**173,684**	**180,870**	**290**	**835**	**175**	**777**	**6**	**4**	**5**	**101**	**6**	**34**	**15**	**2**	**5**	**167,510**	**173,884**	**290**	**693**	**175**	**827**	**6**	**96**	**6**	**26**	**17**	**2**	**5**	**70**	**70**	**385**	**760**	**167**	**45**
															354,554			**1,010**			**15**			**163**						**341,394**			**868**				**152**								**1,145**		**212**	