ADA SUMMARY OF QUANTITIES - ARCO CORPORATE DR FROM SR-3109 TO PAVEMENT JOINT

Municipality:	**Raleigh**
WBS Number:	2027CPT.05.08.10921, ETC.
County:	**Wake**

Sheet No.
26

Ramp ID	Inset Map Number	Route 1	Route 2	0156000000-E (SY) Removal of Existing Asphalt Pavement	1704000000-E (TON) Patching Existing Pavement	2549000000-E (LF) 2'-6" Concrete Curb & Gutter	2752000000-E (LF) Remove And Replace 2'-6" Concrete Curb & Gutter	2591000000-E (SY) 4" Concrete Sidewalk	2738000000-E (SY) Remove And Replace 4" Concrete Sidewalk	2738000000-E (SY) Remove 4" Concrete Sidewalk	2845000000-N (EA) Adjustment of Meter Boxes or Valve Boxes	2655000000-E (SY) 5" Monolithic Concrete Island (Keyed In)	2738000000-E (SY) Remove And Replace 5" Monolithic Concrete Islands (Keyed In)	2612300000-N (EA) Retrofit Existing Concrete Curb Ramps	2612500000-N (EA) Remove and Replace Concrete Curb Ramps	2759000000-N (EA) Remove Concrete Curb Ramps	Improvement Type
12914	5	SR-3102 (Arco Corporate Dr)	Shopping Center (7980 Arco Corporate Dr)												1		Type 3 Modified - 848D0609
12915	5	SR-3102 (Arco Corporate Dr)	Shopping Center (7980 Arco Corporate Dr)												1		Type 3 Modified - 848D0609
12912	6	SR-3102 (Arco Corporate Dr)	Shopping Center (7990 Arco Corporate Dr)												1		Type 3 Modified - 848D0609
12913	6	SR-3102 (Arco Corporate Dr)	Shopping Center (7990 Arco Corporate Dr)												1		Type 3 Modified - 848D0609
-	-	-	-	-	5*	-	68*	-	30*	-	-	-	-	-	-	-	
Sub-Total				**0**	**5**	**0**	**68**	**0**	**30**	**0**	**0**	**0**	**0**	**0**	**4**	**0**	
-	-	-	-	-	5*	-	68*	-	30*	-	-	-	-	-	-	-	
Sub-Total				**0**	**5**	**0**	**68**	**0**	**30**	**0**	**0**	**0**	**0**	**0**	**4**	**0**	
Sub-Total for Arco Corporate Dr From SR-3109 To Pavement Joint				**0**	**5**	**16**	**68**	**7**	**30**	**0**	**1**	**0**	**0**	**1**	**17**	**2**	

*Contingency line item amount provided for additional adjustments outside of curb ramp pay limits, as needed.

**While ramp is compliant upon initial inspection, it is to be improved in order to create a more resilient curb ramp.

Notes: (1) ADA quantity totals are provided on the project 'ADA SUMMARY OF QUANTITIES - TOTALS' page. (2) Construct in accordance with Section 848. Detectable warnings shall be of one of the following materials: engineered plastics, rubber, or composite tile. Additionally, warnings shall be applied directly to the curb ramps by incorporating into the concrete of the curb ramps unless otherwise approved by the Engineer. Surface mounted rubber mats, brick, steel and stamped concrete pavers will not be accepted. (3) In accordance with PROWAG Sections R304.2.1 and R304.3.1, curb ramp running slope is to be constructed to a maximum of 8.33%. Where the curb ramp length must exceed 15 feet to achieve an 8.33% running slope, the curb ramp length shall extend at least 15 feet and may have a running slope greater than 8.33%.