ADA SUMMARY OF QUANTITIES - TOTALS

WBS Number:	2027CPT.05.08.10921, ETC.
County:	Wake

Sheet No.
28

WBS Number	County	Municipality	Resurfacing Route	4447000000-E (LF) Pedestrian Channelizing Devices	4600000000-N (EA) Generic Traffic Control Item - Pedestrian Transport Service (Per Trip)	4600000000-N (EA) Generic Traffic Control Item - Audible Warning Devices	0156000000-E (SY) Removal of Existing Asphalt Pavement	1704000000-E (TON) Patching Existing Pavement	2549000000-E (LF) 2'-6" Concrete Curb & Gutter	2752000000-E (LF) Remove And Replace 2'-6" Concrete Curb & Gutter	2591000000-E (SY) 4" Concrete Sidewalk	2738000000-E (SY) Remove And Replace 4" Concrete Sidewalk	2738000000-E (SY) Remove 4" Concrete Sidewalk	2845000000-N (EA) Adjustment of Meter Boxes or Valve Boxes	2655000000-E (SY) 5" Monolithic Concrete Island (Keyed In)	2738000000-E (SY) Remove And Replace 5" Monolithic Concrete Islands (Keyed In)	2612300000-N (EA) Retrofit Existing Concrete Curb Ramps	2612500000-N (EA) Remove and Replace Concrete Curb Ramps	2759000000-N (EA) Remove Concrete Curb Ramps
2027CPT.05.08.10921	Wake	Wake Forest	NC 98 BUS (Durham Rd) From NC 98 To Pvmt Jt E of US1	30	5	2	31	4	0	60	0	15	10	1	0	0	0	15	0
2027CPT.05.08.20921	Wake	Raleigh Durham Outside Municipality	T W Alexander Dr From/To Durham County Line To/From SR 6010	60	10	2	62	14	76	196	27	73	12	2	8	12	0	49	6
2027CPT.05.08.20921	Wake	Raleigh	Arco Corporate Dr From SR-3109 To Pavement Joint	30	5	2	0	5	16	68	7	30	0	1	0	0	1	17	2
2027CPT.05.08.20921	Wake	Raleigh Outside Municipality	Gresham Lake Rd From SR 2012 To US 1	30	5	2	8	5	106	74	11	51	0	2	0	0	0	17	5
GRAND TOTAL				**150**	**25**	**8**	**101**	**28**	**198**	**398**	**45**	**169**	**22**	**6**	**8**	**12**	**1**	**98**	**13**

Notes: (1) Construct in accordance with Section 848. Detectable warnings shall be of one of the following materials: engineered plastics, rubber, or composite tile. Additionally, warnings shall be applied directly to the curb ramps by incorporating into the concrete of the curb ramps unless otherwise approved by the Engineer. Surface mounted rubber mats, brick, steel and stamped concrete pavers will not be accepted. (2) In accordance with PROWAG Sections R304.2.1 and R304.3.1, curb ramp running slope is to be constructed to a maximum of 8.33%. Where the curb ramp length must exceed 15 feet to achieve an 8.33% running slope, the curb ramp length shall extend at least 15 feet and may have a running slope greater than 8.33%.