| PROJECT NO. | SHEET NO. | TOTAL NO. |
|---|---|---|
| 2027CPT.05.08.10921, ETC. | 29 | |
| | | |

# SUMMARY OF QUANTITIES

| | | | | | | | | | 0156000000-E | 1220000000-E | 1245000000-E | 1260000000-E | 1297000000-E | 1330000000-E | 1519000000-E | 1523000000-E | 1575000000-E | 1704000000-E | 1841000000-E | 2549000000-E | 2591000000-E | 2612300000-N | 2612500000-N | 2655000000-E | 2738000000-E | | | 2752000000-E | 2759000000-N | 2845000000-N | 4600000000-N | | 7444000000-E |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| PROJECT NO | COUNTY | MAP NO | ROUTE | DESCRIPTION | TYP NO | LENGTH | WIDTH | REMOVAL OF EXISTING ASPHALT PAVEMENT | INCIDENTAL STONE BASE | SHOULDER RECONSTRUCTION | AGGREGATE SHOULDER BORROW | 1½" MILLING | INCIDENTAL MILLING | SURFACE COURSE, S9.5B | SURFACE COURSE, S9.5C | ASPHALT BINDER FOR PLANT MIX | PATCHING EXISTING PAVEMENT | MILLED RUMBLE STRIPS (ASPHALT CONCRETE) | 2'-6" CONCRETE CURB & GUTTER | 4" CONCRETE SIDEWALK | RETROFIT EXISTING CONCRETE CURB RAMPS | REMOVE AND REPLACE CONCRETE CURB RAMPS | 5" MONOLITHIC CONCRETE ISLANDS | REMOVE AND REPLACE 4" CONCRETE SIDEWALK | REMOVE 4" CONCRETE SIDEWALK | REMOVE AND REPLACE 5" MONOLITHIC CONCRETE ISLANDS | REMOVE AND REPLACE 2'-6" CONCRETE CURB & GUTTER | REMOVE CONCRETE CURB RAMPS | ADJUSTMENT OF METER BOXES OR VALVE BOXES | GENERIC TRAFFIC CONTROL ITEM PEDESTRIAN TRANSPORT SERVICE (PER TRIP) | GENERIC TRAFFIC CONTROL ITEM AUDIBLE WARNING DEVICES | INDUCTIVE LOOP SAWCUT |
| | | | | | | MI | FT | SY | TONS | SMI | TON | SY | SY | TONS | TONS | TON | TONS | LF | LF | SY | EA | EA | SY | SY | SY | SY | LF | EA | EA | EA | EA | LF |
| 2027CPT.05.08.10921 | Wake | 1 | NC-98 BUS E / OLD FALLS OF NEUSE RD/DURHAM RD | FROM NC 98 TO END DIVIDED HWY | 1 | 0.129 | 24 | | | | | 5,111 | 49 | 469 | | 31 | 6 | | | | | | | | | | | | | | | |
| | | 2 | NC-98 E / DURHAM RD/DR CALVIN JONES HWY | FROM VERMILION CT TO BRIDGE JOINT | 2 | 1.744 | 28 | | | | | 39,367 | 738 | | 3,706 | 222 | 70 | 17,616 | | | | | | | | | | | | | | | 1,200 |
| | | 3 | NC-98 BUS E / DURHAM RD | FROM END DIVIDED HWY TO PVMT JT E OF US1 | 3 | 1.062 | 60 | 31.0 | | | | 38,949 | 410 | 3,572 | | 234 | 44 | | | | | | 15.0 | | 15 | 10 | | 60 | | 5 | 5 | 2 | 2,040 |
| | | 4 | NC-98 W / DR CALVIN JONES HWY/DURHAM RD | FROM BRIDGE JOINT TO END DIVIDED HWY | 2 | 1.598 | 35 | | | | | 33,909 | 656 | | 3,194 | 192 | 69 | 15,974 | | | | | | | | | | | | | | | 1,176 |
| | | 5 | NC-98 BUS W / DURHAM RD | FROM BEGIN DIVIDED HWY TO NC-98 | 4 | 0.140 | 24 | | | | | 2,542 | 57 | 236 | | 16 | 6 | | | | | | | | | | | | | 1 | | | 882 |
| **TOTAL FOR PROJ NO. 2027CPT.05.08.10921** | | | | | | **4.673** | | **31.0** | | | | **119,878** | **1,910** | **4,277** | **6,900** | **695** | **195** | **33,590** | | | | **15.0** | | **15** | **10** | | **60** | | **6** | **5** | **2** | **5,298** |
| 2027CPT.05.08.20921 | Wake | 6 | SR-3067 / T W ALEXANDER DR/T.W. ALEXANDER DR | FROM DURHAM COUNTY LINE TO SR 6010 | 5 | 1.784 | 23 | 62.0 | | | | 40,986 | 770 | 3,790 | | 250 | 86 | | 76 | 27 | | 49.0 | 8 | 73 | 12 | 12 | 196 | 6 | 22 | 10 | 2 | 1,068 |
| | | 7 | SR-3102 / ARCO CORPORATE DR | FROM SR-3109 TO PAVEMENT JOINT | 3 | 0.425 | 24 | | | | | 8,782 | 164 | 812 | | 60 | 142 | | 16 | 7 | 1 | 17.0 | | 30 | | | 68 | 2 | 5 | 5 | 2 | |
| | | 8 | SR-2013 / GRESHAM LAKE RD | FROM SR 2012 TO US 1 | 6 | 1.671 | 36 | 8.0 | 45 | 1.77 | 164 | 39,547 | 721 | 3,655 | | 241 | 76 | | 106 | 11 | | 17.0 | | 51 | | | 74 | 5 | 7 | 5 | 2 | 1,344 |
| | | 9 | SR-3067 / T.W. ALEXANDER DR/T W ALEXANDER DR | FROM SR 6010 TO DURHAM COUNTY LINE | 5 | 1.733 | 36 | | | | | 37,724 | 746 | 3,492 | | 231 | 82 | | | | | | | | | | | | 15 | | | 1,200 |
| **TOTAL FOR PROJ NO. 2027CPT.05.08.20921** | | | | | | **5.613** | | **70.0** | **45** | **1.77** | **164** | **127,039** | **2,401** | **11,749** | | **782** | **386** | | **198** | **45** | **1** | **83.0** | **8** | **154** | **12** | **12** | **338** | **13** | **49** | **20** | **6** | **3,612** |
| 2027CPT.05.08.20922 | Wake | 10 | SR-4672 / NORWOOD OAKS DR | FROM SR 1834 TO CUL-DE-SAC | 7 | 0.197 | 20 | | | | | | 82 | 144 | | 10 | 8 | | | | | | | | | | | | | | | |
| **TOTAL FOR PROJ NO. 2027CPT.05.08.20922** | | | | | | **0.197** | | | | | | | **82** | **144** | | **10** | **8** | | | | | | | | | | | | | | | |
| **GRAND TOTAL** | | | | | | **10.483** | | **101.0** | **45** | **1.77** | **164** | **246,917** | **4,393** | **16,170** | **6,900** | **1,487** | **589** | **33,590** | **198** | **45** | **1** | **98.0** | **8** | **169** | **22** | **12** | **398** | **13** | **55** | **25** | **8** | **8,910** |