

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

ROY COOPER GOVERNOR JAMES H. TROGDON, III SECRETARY

March 7, 2018

U.S. Army Corps of Engineers Raleigh Regulatory Field Office Attn: Mr. James Lastinger 3331 Heritage Trade Drive, Suite 105 Wake Forest, NC 27587

Subject:

Application for Section 404 Regional General Permit 198200031 and Section 401 Water Quality Certification for Interstate 40 Pavement Rehabilitation and Construction of Additional Lanes from West of NC 801 to East of SR 1101 in Davie and Forsyth Counties, Federal Aid Project No. NHIMF-40-3(112)180; TIP Number I-0911A, Division 9.

Debit \$570 from WBS Element 34147.3.4.

Dear Mr. Lastinger:

The North Carolina Department of Transportation (NCDOT), in accordance with the Federal Highway Administration (FHWA), proposes to widen I-40 from west of NC 801 in Davie County to east of SR 1101 (Harper Road) in Forsyth County. The proposed impacts to jurisdictional areas include 0.25 acre of permanent wetland impacts, 893 linear feet (If) of permanent stream impacts, 19 If of stream bank stabilization, and 1.03 acre (288 If) of temporary stream impacts.

Please find enclosed copies of the Pre-Construction Notification (PCN), North Carolina Division of Mitigation Services (DMS) mitigation acceptance letter (dated March 1, 2018), permit drawing review meeting minutes (4B and 4C), Stormwater Management Plan, permit drawings, and design plans. The Environmental Assessment was completed June 2011. The Finding of No Significant Impact was completed June 2014. This document is available at the NCDOT website: https://xfer.services.ncdot.gov/pdea/EnvironmentalDocs/Documents/.

A Natural Resources Technical Report (NRTR) dated August 2013, and NRTR Addendum dated December 2017 was prepared for this project. A summary of the findings of this report are provided in Table 1.

Table 1 – Federally protected species listed for Davie (D) and Forsyth (F) Counties

Scientific Name	Common Name	Federal Status ¹	Habitat Present	Biological Conclusion
Glyptemys muhlenbergii (F)	Bog turtle	T(S/A)	No	Not Required
Myotis septentrionalis (F, D)	Northern long-eared bat	T	Yes	2
Rhus michauxii (D)	Michaux's sumac	E	Yes	No Effect
Cardamine micranthera (F)	Small-anthered bittercress	E	No	No Effect

^{1 -} T(S/A) - Threatened due to similarity of appearance, E - Endangered, T - Threatened,

This project was analyzed in the 2011 EA and the 2014 FONSI for potential effects to archaeological and historic architectural resources with a determination of "no effect" for both.

Bridge Causeways

Causeways will be required to construct the project. As detailed in the accompanying permit drawings (Permit Drawings 15-24 of 33), causeway configurations will change during the various stages of construction. Turbidity curtains will be installed around the river edges of causeways. As part of the efforts to minimize surface water impacts, a series of 54" conveyance pipes will be placed under the causeways to maintain river flow. They will be placed on the river bottom in an attempt to keep them below the river surface to minimize risk to recreationists.

At no point will more than 49% of the river cross section be occupied by causeways. The times when the highest percentage of channel will be occupied is during the two stages of demolition (Permit Drawings 23 and 24 of 33). Each demolition stage is expected to take less than a month.

Permits Requested

<u>Section 404:</u> Application is hereby made for a Section 404 Regional General Permit No. 198200031 as required for the above-described activities.

Section 401: Application is hereby made for the associated 401 Water Quality Certification from the NC Division of Water Resources. In compliance with Section 143-215.3D (e) of the NCAC, we will provide \$570.00 to act as payment for processing the Section 401 permit application.

Thank you for your assistance with this project. If you have any questions or need additional information, please contact Erin Cheely at either ekcheely@ncdot.gov or (919) 707-6108. A copy of this permit application and its distribution list will also be posted on the NCDOT website at https://connect.ncdot.gov/resources/Environmental/Pages.

Sincerely,

Carla Tomus For Philip S. Harris, III, P.E., C.P.M.

Environmental Analysis Unit Head

cc: NCDOT Permit Application Standard Distribution List

^{2 -} Northern long-eared bat is consistent with the 4(d) rule.





Pre-Construction Notification (PCN) Form

For Nationwide Permits and Regional General Permits (along with corresponding Water Quality Certifications)

January 31, 2018 Ver 2.3

Please note: fields marked with a red asterisk * below are required. You will not be able to submit the form until all mandatory questions are answered.

Also, if at any point you wish to print a copy of the E-PCN, all you need to d	o is right-click on the document and you can print a copy of the form.
Below is a link to the online help file.	
https://edocs.deq.nc.gov/WaterResources/0/edoc/624704/PCN%20Help%	0File%202018-1-30.pdf
A. Processing Information	
County (or Counties) where the project is located:*	
Davie	
Forsyth	
Is this project a public transportation project?★(?) • Yes • No	
Is this a NCDOT Project?* • Yes • No	
(NCDOT only) T.I.P. or state project number: I-0911A	
WBS # 34147.3.4 (for NCDOT use only)	
 1a. Type(s) of approval sought from the Corps: * ✓ Section 404 Permit (wetlands, streams and waters, Clean Water Act) ☐ Section 10 Permit (navigable waters, tidal waters, Rivers and Harbors Act) 	ct)
1b. What type(s) of permit(s) do you wish to seek authorization? ★ □ Nationwide Permit (NWP) ☑ Regional General Permit (RGP)	
Regional General Permit (RGP) Number: 198200031 - NCDOT B	ridges, Widening Projects 2015
RGP Number Other:	
List all RGP numbers you are applying for not on the drop down list.	
1c. Type(s) of approval sought from the DWR:* check all that apply	
✓ 401 Water Quality Certification - Regular✓ Non-404 Jurisdictional General Permit	☐ 401 Water Quality Certification - Express ☐ Riparian Buffer Authorization

1d. Is this notification solely for the record because written appr	roval is not required?
For the record only for DWR 401 Certification:	C Yes € No
For the record only for Corps Permit:	C Yes € No
1e. Is payment into a mitigation bank or in-lieu fee program prop If so, attach the acceptance letter from mitigation bank or in-lieu fee program. © Yes © No	osed for mitigation of impacts?
Acceptance Letter Attachment Click the upload button or drag and drop files here to attach document I-0911A Revised DMS Acceptance.pdf FILETYPEMUST BEPDF	67.6KB
1f. Is the project located in any of NC's twenty coastal counties? O Yes O No	*
1h. Is the project located in a designated trout watershed?* ○ Yes ○ No	
Link to trout information: http://www.saw.usace.army.mil/Missions/Regula	atory-Permit-Program/Agency-Coordination/Trout.aspx
B. Applicant Information	
1a. Who is the Primary Contact?* NCDOT	
1b. Primary Contact Email: * ekcheely@ncdot.gov	
1c. Primary Contact Phone: * (xxx)xxx-xxxx (919)707-6108	
1d. Who is applying for the permit? ✓ Owner ☐ Applicant (other than owner) ☐ Agent/Consultant (Check all that apply)	
2. Owner Information	
2a. Name(s) on recorded deed:	
2b. Deed book and page no.:	
2c. Responsible party: (for Corporations)	
2d. Address Street Address	
Address Line 2 City	State / Province / Region
Postal / Zip Code	Country
2e. Telephone Number: (xxx)xxx-xxxx	
2f. Fax Number:	
(xxx)xxx-xxxx	

2g. Email Address:*
pharris@ncdot.gov

C. Project Information and Prior Project History

1. Project Information

1a. Name of project:*

I-40 Pavement Rehabilitation and Widening from West of NC 801 to East of SR 1101 (Harper Rd)

1b. Subdivision name:

(if appropriate)

1c. Nearest municipality / town:*

Bermuda Run and Clemmons

1d. Driving directions *

If it is a new project and can not easily be found in a GPS mapping system. Please provide directions.

https://www.google.com/maps/dir//Twins+Way,+Advance,+NC+27006/@36.0158864,-

80.418802,17z/data=!4m8!4m7!1m0!1m5!1m1!1s0x8853b859fc0daaa1:0x9f2f6cccfa159232!2m2!1d-80.4198062!2d36.0162224

2. Project Identification

2a. Property Identification Number:

(tax PIN or parcel ID)

Multiple, see attached permit drawings

2b. Property size:

(in acres)

71.1

2c. Project Address

Street Address

Address Line 2

City

State / Province / Region

Postal / Zip Code

Country

2d. Site coordinates in decimal degrees

Please collect site coordinates in decimal degrees. Use between 4-6 digits (unless you are using a survey-grade GPS device) after the decimal place as appropriate, based on how the location was determined. (For example, most mobile phones with GPS provide locational precision in decimal degrees to map coordinates to 5 or 6 digits after the decimal place.)

Latitude:*

Longitude:*

36.016479

-80.418436

ex: 34.208504

-77.796371

3. Surface Waters

3a. Name of the nearest body of water to proposed project:*

Yadkin River, Smith Creek; Johnson Creek

3b. Water Resources Classification of nearest receiving water:*

WS-IV (Yadkin, Johnson Creek), C (Smith Creek)

3c. What river basin(s) is your project located in?*

Yadkin-PeeDee

River Basin Lookup

4. Project Description

4a. Describe the existing conditions on the site and the general land use in the vicinity of the project at the time of this application:

The project study area is comprised of mostly maintained roadway with hardwood forest along the stream banks, nearby residential and commercial areas, and a soccer park. The study area is within the towns of Clemmons and Bermuda Run. In addition to the Yadkin River and Smith Creek, there are unnamed tributaries (UTs) to those streams and also wetlands in the project area. There are also several ponds.

4b. Attach an 8 1/2 X 11 excerpt from the most recent version of the USGS topographic map indicating the location of the project site. (for DWR)

Click the upload button or drag and drop files here to attach document

I0911A_USGS_Topo.pdf

4.16MB

1.67MB

File type must be pdf

4c. Attach an 8 1/2 X 11 excerpt from the most recent version of the published County NRCS Soil Survey map depicting the project site. (for DWR)

Olick the upload button or drag and drop files here to attach document

I0911A Soils.pdf

File type must be pdf

4d. List the total estimated acreage of all existing wetlands on the property:

1.05

4e. List the total estimated linear feet of all existing streams on the property:

(intermittent and perennial)

4,500

4f. Explain the purpose of the proposed project:*

The purpose of the proposed project is to increase the traffic carrying capacity and enhance transportation safety along I-40 within the project limits. Capacity analysis indicates that the existing 4-lane divided facility operated at Level of Service (LOS) D in 2009 and will operate at LOS F in 2035 under the no build conditions. The 2035 Build scenario capacity analysis results indicate that this segment of I-40 is expected to operate at a LOS E. In addition, as part of transportation safety requirements, the existing bridges over the Yadkin River were inspected and determined to be structurally deficient and must be replaced due to age and wear.

4g. Describe the overall project in detail, including indirect imapacts and the type of equipment to be used:*

I-40 will be widened to a six-lane facility from west of NC 801 in Davie County to east of SR 1101 (Harper Road/Tanglewood Business Park Road) in Forsyth County for a project length of 3.78 miles. The project includes the replacement of Bridges No. 85 and 86, which will require in-water causeways and staged construction (see cover letter for causeway discussion and permit drawings for details). The road will remain open to traffic during construction. Erosion and sedimentation control measures will be installed. For in-water work other than the bridge replacements, water will be diverted around the construction area. Water will gravity flow through a 24" pipe around the work area during construction by installed impervious dikes upstream and downstream of existing pipes. Special stilling basins will be utilized on an as needed basis to pump water trapped between the impervious dikes if a storm event overtops the dikes. Typical equipment that will be used includes cranes, track hoes, dump trucks, paving equipment, pumps, various hand tools, and concrete buckets to place concrete.

4h. Please upload project drawings for the proposed project.

Click the upload button or drag and drop files here to attach document

I-0911A Final Permit Drawings.pdf 13.45MB
I-0911A Final Roadway Plans.pdf 7.69MB

File type must be pdf

5. Jurisdictional Determinations

5a. Have the wetlands or streams been d	elineated on the property or p	proposed impact areas?*	
⊙ Yes	C No	C Unkr	nown
Comments:			
A JD package was submitted to the USACE (J 2008 and again on June 24, 2013 after a reconducted with Amy Euliss (when she was with Additional reources were delineated in 2017 at the USACE (James Lastinger) and Dave Wan Both determined a site visit would not be need.	delineation. A site visit was h NCDWR) on July 31, 2013. and this information was sent to ucha (NCDWR) on 11/27/17.		
5b. If the Corps made a jurisdictional dete	ermination, what type of deter	mination was made?*	
C Preliminary C Appr	oved	Unknown	© N/A
Corps AID Number:			
Example: SAW-2017-99999			
5c. If 5a is yes, who delineated the jurisd	ictional areas?		
Name (if known):		Alexander Smith & Sc Michael Turchy	cott Davis / Erin Cheely &
Agency/Consultant Company:		Axiom Environmental	/ NCDOT
Other:			
5d. If yes, list the dates of the Corps juris	dictional determinations or St	ate determinations and att	tach documentation.
5d1. Jurisdictional determination upload			
Click the upload button or drag and drop files here to attach	document		
File type must be PDF			
6. Project History			
6a. Have permits or certifications been re	equested or obtained for this	project (including all prior	phases) in the past?*
C Yes	No	C Unkr	nown
7. Future Project Plans			
7a. Is this a phased project?*			
O Yes • No			
Are any other NWP(s), regional general p proposed project or related activity? This Army authorization but don't require pre-	s includes other separate and		
D. Proposed Impacts In	ventory		
1. Impacts Summary			
1a. Where are the impacts associated wit	h your project? (check all that	t apply):	
✓ Wetlands	▼ Streams-tributaries ▼ Streams	☐ Buffe	ers
☐ Open Waters	☐ Pond Construction		
2. Wetland Impacts			
If there are wetland impacts proposed on the	site, then complete this question	for each wetland area impacte	ed.

2a. Site # - Reason for impact *	2b. Impact type *	2c. Type of wetland *	2d. Wetland name	*2e. Forested*	2f. Type of Jurisdicition *	2g. Impact area *
5 - Roadway Fill Map label (e.g. Road Crossing 1 - Oulvert, dew atering, etc)	Permanent (P) or Temporary (T)	Headwater Forest	J	Yes	Corps (404, 10) or DWR (401, other)	0.010 (acres)
7A - Roadway Fill Map label (e.g. Road Crossing 1 - Oulvert, dew atering, etc)	Permanent (P) or Temporary (T)	Seep	SP	Yes	Corps (404, 10) or DWR (401, other)	0.230 (acres)
9 - Roadway Fill Map label (e.g. Road Crossing 1 - Oulvert, dew atering, etc)	Permanent (P) or Temporary (T)	Bottomland Hardwood Forest	A	Yes	Corps (404, 10) or DWR (401, other)	0.008 (acres)
10 - 60" WSP Installation Map label (e.g. Road Crossing 1 - Oulvert, dew atering, etc)	P Permanent (P) or Temporary (T)	Non-Tidal Freshwater Marsh	WAE	No	Corps (404, 10) or DWR (401, other)	0.008 (acres)

2g. Total Temporary Wetland Impact

0.000

2g. Total Permanent Wetland Impact

0.256

2g. Total Wetland Impact

0.256

2h. Comments:

Of the 0.25 acre of permanent wetland impacts, there will be <0.01 acre of mechanized clearing of wetlands at Site 9 and <0.01 acre of mechanized clearing of wetlands at Site 10.

3. Stream Impacts

If there are perennial or intermittent stream impacts (including temporary impacts) proposed on the site, then complete this question for all stream sites impacted.

3a. Site # - Reason for impact *	3b.Impact type *	3c. Type of impact *	3d. Stream name *	3e. Stream Type *	3f. Type of Jurisdiction *	3g. Stream width *	3h. Impact length *
1 Map label (e.g. Road Crossing 1)	Permanent (P) or Temporary (T)	Fill	UT to Smith Creek (SC)	Intermittent Perennial (PER) or intermittent (INT)	Both	3 Average (feet)	41 (linear feet)
2 Map label (e.g. Road Crossing 1)	P Permanent (P) or Temporary (T)	Fill	UT to Yadkin River (CB)	Perennial Perennial (PER) or intermittent (INT)	Both	5 Average (feet)	324 (linear feet)
2 Map label (e.g. Road Crossing 1)	T Permanent (P) or Temporary (T)	Dewatering	UT to Yadkin River (CB)	Perennial Perennial (PER) or intermittent (INT)	Both	5 Average (feet)	14 (linear feet)
2 Map label (e.g. Road Crossing 1)	P Permanent (P) or Temporary (T)	Fill	UT to Yadkin River (CB)	Intermittent Perennial (PER) or intermittent (INT)	Both	4 Average (feet)	50 (linear feet)
2 Map label (e.g. Road Crossing 1)	T Permanent (P) or Temporary (T)	Dewatering	UT to Yadkin River (CB)	Intermittent Perennial (PER) or intermittent (INT)	Both	4 Average (feet)	16 (linear feet)
3 Map label (e.g. Road Crossing 1)	Permanent (P) or Temporary (T)	Fill	UT to Yadkin River (CBZ)	Intermittent Perennial (PER) or intermittent (INT)	Both	3 Average (feet)	84 (linear feet)
4 Map label (e.g. Road Crossing 1)	Permanent (P) or Temporary (T)	Fill	UT to Yadkin River (JS)	Intermittent Perennial (PER) or intermittent (INT)	Both	2 Average (feet)	57 (linear feet)
5 Map label (e.g. Road Crossing 1)	Permanent (P) or Temporary (T)	Fill	UT to Yadkin River (SAA)	Intermittent Perennial (PER) or intermittent (INT)	Both	1 Average (feet)	19 (linear feet)

3a. Site # - Reason for impact *	3b.Impact type *	3c. Type of impact *	3d. Stream name *	3e. Stream Type *	3f. Type of Jurisdiction *	3g. Stream width *	3h. Impact length *
6 Map label (e.g. Road Crossing 1)	Permanent (P) or Temporary (T)	Fill	UT to Yadkin River (FH)	Intermittent Perennial (PER) or intermittent (INT)	Both	3 Average (feet)	57 (linear feet)
7A Map label (e.g. Road Crossing 1)	P Permanent (P) or Temporary (T)	Bank Stabilization	UT to Yadkin River (SP)	Perennial Perennial (PER) or intermittent (INT)	Both	6 Average (feet)	9 (linear feet)
7A Map label (e.g. Road Crossing 1)	T Permanent (P) or Temporary (T)	Dewatering	UT to Yadkin River (SP)	Perennial Perennial (PER) or intermittent (INT)	Both	6 Average (feet)	21 (linear feet)
7B Map label (e.g. Road Crossing 1)	Permanent (P) or Temporary (T)	Bank Stabilization	UT to Yadkin River (SP)	Perennial Perennial (PER) or intermittent (INT)	Both	6 Average (feet)	6 (linear feet)
7B Map label (e.g. Road Crossing 1)	T Permanent (P) or Temporary (T)	Dewatering	UT to Yadkin River (SP)	Perennial Perennial (PER) or intermittent (INT)	Both	6 Average (feet)	21 (linear feet)
7C Map label (e.g. Road Crossing 1)	Permanent (P) or Temporary (T)	Bank Stabilization	UT to Yadkin River (SP)	Perennial Perennial (PER) or intermittent (INT)	Both	6 Average (feet)	4 (linear feet)
7C Map label (e.g. Road Crossing 1)	T Permanent (P) or Temporary (T)	Dewatering	UT to Yadkin River (SP)	Perennial Perennial (PER) or intermittent (INT)	Both	6 Average (feet)	20 (linear feet)
8 Map label (e.g. Road Crossing 1)	T Permanent (P) or Temporary (T)	Workpad/Causew ay	Yadkin River	Perennial Perennial (PER) or intermittent (INT)	Both	300 Average (feet)	144 (linear feet)
9 Map label (e.g. Road Crossing 1)	P Permanent (P) or Temporary (T)	Fill	UT to Yadkin River (A)	Perennial Perennial (PER) or intermittent (INT)	Both	5 Average (feet)	244 (linear feet)
9 Map label (e.g. Road Crossing 1)	T Permanent (P) or Temporary (T)	Dewatering	UT to Yadkin River (A)	Perennial Perennial (PER) or intermittent (INT)	Both	5 Average (feet)	31 (linear feet)
10 Map label (e.g. Road Crossing 1)	P Permanent (P) or Temporary (T)	Fill	UT to Johnon Creek (SAC)	Perennial Perennial (PER) or intermittent (INT)	Both	4 Average (feet)	17 (linear feet)
10 Map label (e.g. Road Crossing 1)	T Permanent (P) or Temporary (T)	Dewatering	UT to Johnson Creek (SAC)	Perennial Perennial (PER) or intermittent (INT)	Both	4 Average (feet)	21 (linear feet)

^{**} All Perennial or Intermittent streams must be verified by DWR or delegated local government.

3i. Total jurisdictional ditch impact in square feet:

0

3i. Total permanent stream impacts:

912

3i. Total temporary stream impacts:

288

3i. Total stream and tributary impacts:

1200

3j. Comments:

Of the 912 linear feet of permanent impacts, 19 linear feet are from bank stabilization. Additionally, Site 8 has 14 proposed bridge piers with a diameter of 4.5' for a total area of 227.7 square feet.

For Permit Site 2, stream CB is intermittent on the south side of I-40 (upstream of RCP inlet and perennial on the north side (downstream of the RCP outlet).

E. Impact Justification and Mitigation

1. Avoidance and Minimization		
1a. Specifically describe measures taken to avoid or The proposed project is to widen I-40 over 3.78 miles. As a River will be replaced, culverts will be extended, and some near the historic property near the project and have been an easement on the historic property. Noise barriers will be impacts to jurisdictional features, 2:1 fill slopes will be utilized work causeways are detailed in the cover letter.	a result of this expansion, the bride wetlands will be filled. Retaining w moved closer to the travel lanes s e utilized near residential areas. In	ge over the Yadkin walls will be utilized so as to require less of n order to minimize
1b. Specifically describe measures taken to avoid or Erosion and sedimentation BMPs will be installed prior to be to prevent sedimentation of downstream aquatic resources. Management Practices for the protection of surface waters adjacent to waters of the US and coordination (including a Environmental Supervisor.	onstruction. Water will be diverted s. Impacts will be minimized by stricts, restrictions against the staging of	d around the work area ct enforcement of Best of equipment in or
2. Compensatory Mitigation for Impacts to	Waters of the U.S. or V	Waters of the State
2a. Does the project require Compensatory Mitigation • Yes • No	n for impacts to Waters of the	U.S. or Waters of the State?
2c. If yes, mitigation is required by (check all that app ☑ DWR ☑ Corps	oly):	
2d. If yes, which mitigation option(s) will be used for ☐ Mitigation bank	this project? nent to in-lieu fee program	☐ Permittee Responsible Mitigation
4. Complete if Making a Payment to In	-lieu Fee Program	
4a. Approval letter from in-lieu fee program is attach ▼ Yes	ed.	
4b. Stream mitigation requested: (linear feet) 893		
4c. If using stream mitigation, what is the stream tem warm	perature:	
NC Stream Temperature Classification Maps can be found	under the Mitigation Concepts ta	ab on the Wilmington District's RIBITS website.
4d. Buffer mitigation requested (DWR only): (square feet)		
4e. Riparian wetland mitigation requested: (acres) 0.25		
4f. Non-riparian wetland mitigation requested: (acres)		
4g. Coastal (tidal) wetland mitigation requested:		

(acres)

4h. Comments

feet) of temporary impacts. These i	ation for the 19 linear feet of bank stabilization or the <1.03 ac (288 linear npacts do not require permanent fill in the stream bed and, therefore, under do not constitute Loss of Waters of the U.S. and are not subject to
6. Buffer mitigation (Sta	te Regulated Riparian Buffer Rules) - required by DWR
6a. Will the project result in an i	npact within a protected riparian buffer that requires buffer mitigation? If yes, you must fill out this entire ore information.
© Yes	⊙ No
F. Stormwater Ma	nagement and Diffuse Flow Plan (required by DWR)
*	* Recent changes to the stormwater rules have required updates to this section .***
1. Diffuse Flow Plan	
1a. Does the project include or Rules?	s it adjacent to protected riparian buffers identified within one of the NC Riparian Buffer Protection
C Yes	⊙ No
For a list of options to meet the diff	se flow requirements, click here.
If no, explain why:	
2. Stormwater Manage	nent Plan
2a. Is this a NCDOT project subj	ct to compliance with NCDOT's Individual NPDES permit NCS000250?*
G. Supplementary	Information
Environmental Docu	nentation
1a. Does the project involve an \odot Yes	expenditure of public (federal/state/local) funds or the use of public (federal/state) land?* © No
	above, does the project require preparation of an environmental document pursuant to the State (North Carolina) Environmental Policy Act (NEPA/SEPA)? *
	above, has the document review been finalized by the State Clearing House? (If so, attach a copy of the
• Yes	C No
NEPA or SEPA Final Approval Le	
Click the upload button or drag and drop files	
10911A_FONSI.pdf FILETYPEMUST BEPDF	86.1MB
2. Violations (DWR Re	quirement)
	R Water Quality Certification Rules (15A NCAC 2H .0500), Isolated Wetland Rules (15A NCAC 2H .1300), or Standards or Riparian Buffer Rules (15A NCAC 2B .0200)?
C Yes	⊙ No

2b. Is this an after-the-fact permit application?* C Yes © No
3. Cumulative Impacts (DWR Requirement)
3a. Will this project (based on past and reasonably anticipated future impacts) result in additional development, which could impact nearby downstream water quality? *
C Yes © No
3b. If you answered "no," provide a short narrative description. An Indirect and Cumulative Effects Assessment (ICE) was done for this project in the August 2013 EA and was updated in the June 2014 FONSI. This report details the potential ecological effects that may result from the proposed project and other past, present, and reasonably foreseeable future development activities in the region. Based upon the ICE analysis done in the EA, much of the project area is urban and suburban in character, and most of the area already has an established road network. The project's individual effects on land use and natural resources are minor. The potential indirect effect identified in the EA, including increased commercial and industrial development, are minor. As indirect and direct impacts associated with this project are avoided or mitigated per the NEPA process, the potential for adverse cumulative impacts to the human environment, such as increased noise levels, view changes, and impacts to historic resources is eliminated or lessened to levels not considered to be significant. Potential for adverse cumulative impacts to the natural environment, such as impacts to streams, wetlands, floodplains, threatened and endangered species, and degradation to water quality is eliminated or lessened as well. Within the region, there are watershed requirements in place for protecting water quality, and indirect and direct impacts associated with this project will be avoided or mitigated per the NEPA process.
4. Sewage Disposal (DWR Requirement)
4a. Is sewage disposal required by DWR for this project?* ○ Yes ○ No ○ N/A
5. Endangered Species and Designated Critical Habitat (Corps Requirement)
5a. Will this project occur in or near an area with federally protected species or habitat?*
© Yes C No
5b. Have you checked with the USFWS concerning Endangered Species Act impacts?* © Yes C No
5c. If yes, indicate the USFWS Field Office you have contacted. Asheville
5d. Is another Federal agency involved?*
C Yes © No C Unknown
5e. Is this a DOT project located within Division's 1-8?* ○ Yes ○ No
5f. Will you cut any trees in order to conduct the work in waters of the U.S.? ★ ⊙ Yes ⊙ No
5g. Does this project involve bridge maintenance or removal?* ⊙ Yes ⊙ No
5g(1). If yes, have you inspected the bridge for signs of bat use such as staining, guano, bats, etc.? Representative photos of signs of bat use can be found in the NLEB SLOPES, Appendix F, pages 3-7. O Yes © No
Link to the NLEB SLOPES document: http://saw-reg.usace.army.mil/NLEB/1-30-17-signed_NLEB-SLOPES&apps.pdf
If you answered "Yes" to 5g(1), did you discover any signs of bat use?*

C Yes C No C Unknown
*** If yes, please show the location of the bridge on the permit drawings/project plans.
5h. Does this project involve the construction/installation of a wind turbine(s)?** ○ Yes ○ No
5i. Does this project involve (1) blasting, and/or (2) other percussive activities that will be conducted by machines, such as jackhammers, mechanized pile drivers, etc.?* C Yes © No
5j. What data sources did you use to determine whether your site would impact Endangered Species or Designated Critical Habitat?* The 2013 Environmental Assessment and the 2014 Finding of No Significant Impact covered the impacts to federally listed species. Updated surveys for Michaux's sumac were conducted in 2017, and no individuals of this species were identified within the project area. The northern long-eared bat is consistent with 4(d) requirements (a memo to this effect was forwarded to Marella Buncick of USFWS on April 26, 2017). No habitat exists for the remaining two listed species (bog turtle and small-anthered bittercress).
Percussive activities (including impact pile driving with crane and pile hammer, and existing bridge demolition with hydraulic hammers/hoe-rams) will only occur at the I-40 crossing of the Yadkin River and in the adjacent flood plain.
There will be 24.6 acres of tree clearing for the proposed project.
6. Essential Fish Habitat (Corps Requirement)
6a. Will this project occur in or near an area designated as an Essential Fish Habitat?* O Yes O No
6b. What data sources did you use to determine whether your site would impact an Essential Fish Habitat?* This project takes place in Davie and Forsyth Counties, which are not near any coastal or tidal habitat that would support EFH (i.e. salt marshes, oyster reefs, etc.).
7. Historic or Prehistoric Cultural Resources (Corps Requirement)
Link to the State Historic Preservation Office Historic Properties Map (does not include archaeological data: http://gis.ncdcr.gov/hpoweb/
7a. Will this project occur in or near an area that the state, federal or tribal governments have designated as having historic or cultural preservation status (e.g., National Historic Trust designation or properties significant in North Carolina history and archaeology)? * • Yes • No
7b. What data sources did you use to determine whether your site would impact historic or archeological resources?* The historical and cultural resources were discussed in the 2013 EA, and coordination with the respective agencies is currenty underway. The work under this permit will mimize impacts to historical and cultural resources. See documentation in FONSI provided for item G.1c.
7c. Historic or Prehistoric Information Upload Click the upload button or drag and drop files here to attach document File must be PDF
8. Flood Zone Designation (Corps Requirement)
Link to the FEMA Floodplain Maps: https://msc.fema.gov/portal/search
8a. Will this project occur in a FEMA-designated 100-year floodplain?*
8b. If yes, explain how project meets FEMA requirements: MOA

8c. What source(s) did you use to make the floodplain determination?*

NC Floodplain Mapping Program

Miscellaneous

Miscellaneous attachments not previously requested.

Olick the upload button or drag and drop files here to attach document

I-0911A CP4B and CP4C Minutes.pdf

118.99KB

cover letter.pdf

1.69MB

File must be PDF or KMZ

Signature

*

 ${\color{red} \overline{\hspace*{-0.05cm} \hspace*{-0.05cm} \hspace*{-0cm} \hspace*{-0c$

- I have given true, accurate, and complete information on this form;
- I agree that submission of this PCN form is a "transaction" subject to Chapter 66, Article 40 of the NC General Statutes (the "Uniform Electronic Transactions Act");
- I agree to conduct this transaction by electronic means pursuant to Chapter 66, Article 40 of the NC General Statutes (the "Uniform Electronic Transactions Act");
- I understand that an electronic signature has the same legal effect and can be enforced in the same way as a written signature; AND
- I intend to electronically sign and submit the PCN form.

Full Name:*

Carla Dagnino

Signature

Carla Dagriro

Date

3/7/2018



March 1, 2018

Mr. Philip S. Harris, III, P.E., CPM Project Development and Environmental Analysis Unit North Carolina Department of Transportation 1598 Mail Service Center Raleigh, North Carolina 27699-1598

Dear Mr. Harris:

Subject: Mitigation Acceptance Letter:

I-0911A, I-40 Widening and Rehabilitation from 0.30 miles West of NC 801 in Davie County to 0.30 miles West of SR 1101 (Harper Road / Tanglewood Park Business Road) in Forsyth County, Forsyth and Davie Counties

The purpose of this letter is to notify you that the Division of Mitigation Services (DMS) will provide the compensatory stream and riparian wetland mitigation for the subject project. Based on the information supplied by you on February 28, 2018, the impacts are located in CU 03040101 of the Yadkin River basin in the Central Piedmont (CP) Eco-Region, and are as follows:

Yadkin		Stream			Wetlands	Buffer (Sq. Ft.)		
03040101 CP	Cold	Cool	Warm	Riparian	Non- Riparian	Coastal Marsh	Zone 1	Zone 2
Impacts (feet/acres)	0	0	893.0	0.25	0	0	0	0

^{*}Some of the stream and/or wetland impacts may be proposed to be mitigated at a 1:1 mitigation ratio. See permit application for details.

This mitigation acceptance letter replaces the mitigation acceptance letter issued on April 18, 2017. The impacts and associated mitigation needs were under projected by the NCDOT in the 2017 impact data. DMS will commit to implement sufficient compensatory stream and riparian wetland mitigation credits to offset the impacts associated with this project as determined by the regulatory agencies using the delivery timeline listed in Section F.3.c.iii of the In-Lieu Fee Instrument dated July 28, 2010. If the above referenced impact amounts are revised, then this mitigation acceptance letter will no longer be valid and a new mitigation acceptance letter will be required from DMS.

If you have any questions or need additional information, please contact Beth Harmon at 919-707-8420.

Sincerely,

James B. Stanfill

Credit Management Supervisor

cc: Mr. Monte Matthews, USACE - Raleigh Regulatory Field Office

Ms. Amy Chapman, NCDWR

File: I-0911A Revised



I-0911A 4B Interagency Concurrence Point Meeting Minutes



Date: November 15, 2017

Location: NCDOT Structures Conference Room

Time: 1:00 PM

Minutes Authored By: Matthew Cook Attendees: James Lastinger – USACE

James Lastinger – USACE Marla Chambers – NCWRC
Bill Elam – NCDOT Hydraulics Erin Cheely – NCDOT ECAP

Grain Lag NCDOT Hydraulica Tim McFodden NCDOT Do

Craig Lee – NCDOT Hydraulics Tim McFadden – NCDOT Design Build Carla Dagnino – NCDOT EAU Malcolm Watson – NCDOT Design Build

Jason Mroz – Flatiron Nancy Scott – Three Oaks

Brent Huskey – RK&K Matt Lamy – RK&K

Matthew Cook - RK&K

Via Telephone:

Amy Euliss – NCDOT Div.9 Dave Wanucha - NCDWR
Marella Buncick – USFWS Janet Harris – NCDOT Div. 9

The 30% Hydraulic Review was held in order to reach agreement on concurrence point 4B for the I-0911A I-40 widening project in Davie and Forsyth Counties. The following items were discussed and conclusions reached:

Bill Elam began the meeting and introductions were made. He then turned the meeting over to the Design Build (DB) Team.

Matthew Cook introduced the DB Team for the project. RK&K is the prime designer. The project is being constructed by the Flatiron / Blythe Development Joint Venture. The DB Team was awarded the job in July 2017. The project is on I-40 approximately 14 miles west of Winston Salem. It runs one mile west of NC 801 to one half mile east of Harper Rd. It is 3.78 mi in length with 0.21 mi of bridge over the Yadkin River. The Yadkin River crossing is the only major hydraulic structure being affected by the project. A 4B meeting was previously held for this project May 2015. Due to the project going through the Design Build process two years later, another 4B meeting is needed to account for the design changes proposed by the DB Team and as mandated in the Design Build Request for Proposals.

Mr. Cook then began to go through the 4B planset.

Plan sheet 4 (Stream Smith Creek, wetland WAA): No impacts. There is an existing 8'x8' RCBC under I-40 that will not be affected by the project. Mr. Cook stated that –L- 10+00-14+50 was not included in the original environmental study corridor. Erin Cheely stated that she planned on visiting the project this Friday, November 17 to investigate. All appropriate measures will be taken to ensure the project is in compliance with environmental documentation.

Plan sheet 5 (Streams Smith Creek and SAB, wetlands WAB and WAC): No impacts. There is an existing 9'x9' RCBC under I-40 that will not be affected by the project. Marla Chambers asked how wide Smith Creek running through the RCBC was. Mr. Cook said it was using both barrels. Ms. Chambers asked if a sill could be added to one sill of the RCBC to restrict flow to one barrel (the upstream 8'x8' RCBC on plan sheet 4 only used one barrel). Mr. Cook said that they did not plan on working in the area of the stream or RCBC and that by adding a sill construction equipment would be needed in the area. This would potentially destroy the natural stream buffer. Dave Wanucha asked if there was a storm basin to the right of the RCBC entrance (-L- 35+00 LT). Mr. Cook said that that was a ditch to continue flow that was partially blocked by the proposed roadway fill slope. The equipment needed to install the ditch was minor compared to the equipment needed to install a concrete sill. Ms. Chambers asked if the ditch provided treatment for the stormwater prior to entering the RCBC. Mr. Cook said that the new ditch would not since it was riprap lined, not grass lined. Craig Lee pointed out that the portion of existing ditch between the new ditch and the RCBC could potentially provide treatment. Mr. Wanucha asked why the RCBC was extended in the plans at the May 2015 4B meeting but not extended now. Mr. Lee stated that the original design in 2015 extended a fill slope further out to the left requiring an RCBC extension. The DB Team's design did not require it.





Plan sheet 6 (Stream SC): Stream SC begins at the outlet to the existing 36" RCP at -L- 46+50 RT. It is impacted by the proposed fill slope. The existing pipe will be extended with a 66" RCP that will also include the drainage from the interchange. There is extensive scour that has occurred at the pipe outlet and along the roadside ditch that feeds the stream at the pipe outlet. Mr. Cook stated that a riprapped energy dissipator basin was designed at the outlet of the pipe to attenuate the flow and minimize the velocity before entering the existing stream downstream of the project. This will be Site 1. Amy Euliss asked if the agencies were OK with not burying the pipe since it is not jurisdictional upstream. Everyone was OK with not burying it. Ms. Euliss asked that the plans show a note on pipes that were on jurisdictional streams that we not buried. Mr. Cook stated they would add it. Ms. Euliss asked that the "on banks only" note be removed from the pipes outlet at -L- 37+50 RT since it was not jurisdictional. Mr. Cook stated they had already done so. He also stated that the additional riprap at that pipe outlet was due to the high velocity leaving the pipe. The New York method was used to determine the riprap required. Mr. Wanucha asked what the New York method was and if it was approved by NCDOT. Mr. Cook said it was a design method that helped determine additional riprap required given the stream and velocity at each site. Mr. Elam stated that NCDOT required additional outlet protection at sites that had velocities greater than 15 ft/s, and this was a good compromise between a standard riprap pad and a riprapped energy dissipator basin.

Mr. Cook said that the existing crosspipes that were to be retained on the project were recently videoed to determine their condition. NCDOT Division also recently gave recommendations at each of these locations concerning retaining the pipes, fixing them, or removing them in order to install new pipes. This location required cleaning out the existing 36" RCP and either lining it or replacing it. The 4C plans will reflect the design decision.

Plan sheet 7 (Streams CB and CBZ): Stream CB runs south to north through the project and is currently conveyed in a 42" RCP at –L-68+00. It is impacted by the proposed fill slope. An additional 36" pipe will be installed parallel to the pipe. There is extensive scour that has occurred at the pipe outlet. Mr. Cook said that the outlet channel is more than 20' incised and unstable with three sections of 42" RCP broken off in the channel. He stated that a riprapped energy dissipator basin was designed at the outlet of the pipe to attenuate the flow and minimize the velocity before entering the existing stream downstream of the project. The pipe would also be extended using junction boxes to allow the stream to enter the downstream channel without a bend. This will be Site 2. Ms. Euliss recommended not burying the pipe which everyone agreed with since the pipe length would be very long with junction boxes and also since the upstream portion of CB is intermittent. Ms. Chambers asked if mitigation could be achieved at this site. Ms. Euliss said that it was unlikely given the fact it is along the toe of the I-40 slope. Mr. Elam said that there really wasn't much room here given the highway and the surrounding land use as well as the steep contours. Ms. Cheely added that there was no biology upstream in the initial investigations. Mr. Wanucha asked if this feeds a pond. Mr. Cook said that it does further downstream. Video inspection of the existing 42" RCP led NCDOT Division to ask that the existing 42" RCP be replaced. The 4C plans will reflect the design decision.

Stream CBZ runs parallel to I-40 at -L- 67+50 RT and ties to stream CB prior to entering the upstream end of the crosspipe. It is impacted by the proposed fill slope and will be a total take. This will be Site 3

Plan sheet 8 (Streams JS and SAA, wetland J): Stream JS runs south to north through the project and is currently conveyed in a 24" RCP at –L- 84+50. It is impacted by the proposed fill slope. It will be plugged and filled and a new 42" pipe installed. Junction boxes will be used to place the new pipe in line with the receiving pipe under Pinewood Ln. A new 42" pipe will installed to receive the 42" pipe under I-40 since the existing pipe under Pinewood Ln. is only a 24" RCP. This will be Site 4. Mr. Cook stated that although the current design showed a new 42" pipe extending to the pond, the DB Team is exploring the option to stop the pipe short of the pond and use a riprap lined ditch to take the drainage to the pond. This would limit impacts to the pond. The DB Team can also commit to not impacting the pond with temporary impacts either. Mr. Cook stated that this area at Pinewood Ln. is outside the study corridor and will be investigated by Ms. Cheely. The pond was located using survey equipment by RK&K August 2017. Ms. Euliss asked if the stream began at the point shown on the plans or continued beyond the study corridor. Ms. Cheely stated that the call was made to begin the JS inside the corridor. Ms. Euliss asked that the beginning of the jurisdictional call be noted on the plans. She also stated that this pipe would not need to be buried which everyone agreed to.

Stream SAA runs parallel to I-40 at -L- 84+50 RT and ties to the stream JS prior to entering the upstream end of the crosspipe. It is impacted by the proposed fill slope and will be a total take. Wetland J at -L- 84+5 RT is also impacted by the proposed fill slope and will be a total take. This will be Site 5.

Plan sheet 9 (Stream FH, wetland FH, Pond P2): Stream FH runs south to north through the project and is currently conveyed in a 42" RCP at –L- 99+50. The upstream end is not impacted by the project. The downstream end is impacted by the proposed fill slope and will be extended. An existing 24" RCP downstream of the 42" RCP will be removed. The DB Team also proposed shortening the proposed 42" RCP and conveying the drainage to the pond with a standard base ditch. This would limit impacts to the pond, and the DB Team can also commit to not impacting the pond with temporary impacts either. This will be site 6. Ms. Euliss asked that the linestyle around the pond be changed to jurisdictional. She also suggested not burying the pipe which was agreed upon. Video inspection of the existing 42" RCP led NCDOT Division to ask that it be replaced. The 4C plans will reflect the design decision. This will cause impacts to the upstream side of the crossing.



Plan sheet 11 (Streams SP and 1A, wetlands SP and AC): Wetland SP at –L- 119+50 – 123+50 RT will be impacted by the proposed fill slope. A small portion of the wetland could remain outside of the fill slope. The drainage downstation leaves a 36" RCP. The design currently takes that drainage in a ditch through wetland SP to tie to stream SP. The decision was made for the following reasons: 1) the outlet location for the proposed 36" RCP did not exhibit defined channel characteristics which could cause scour and instability; 2) the remaining functionality of the wetland would be compromised by losing the majority of its area due to the fill slope; 3) the drainage for the entire area would tie better to stream SP using a ditch. This will be Site 7. Ms. Euliss asked that bank stabilization be used on stream SP. Ms. Chambers asked if treatment could be achieved in the ditch. Mr. Cook said that as it is currently designed with riprap, it could not. However, the DB Team will investigate steepening the beginning of the ditch and flattening the end of the ditch to try to remove the riprap and provide a grass liner suitable for some treatment.

Stream 1A and wetland AC at -L- 123+50 RT will not be impacted.

Plan sheet 12 (Streams SP and Yadkin River): Stream SP at –L- 129+25 will be impacted at two locations due to ditch tie-ins from the proposed drainage. The ditches impacting stream SP were used in lieu of preformed scour holes due to stability concerns. Ms. Chambers asked if the ditches could be used for stormwater treatment. Mr. Cook said they could try to do so. Ms. Cheely suggested numbering the stream SP impacts on this sheet Site 7A since they are part of the same stream on the previous sheet. Mr. Cook said that stream SP will have crane mats placed over it during construction for project access, but they will not create stream impacts.

The Yadkin River will be Site 8. The 1104' new bridge will have 8 spans over the FEMA regulated river. Mr. Cook pointed out that the original project commitments stated that there would be "no impacts to the Yadkin River". Mr. Cook said this was impossible given the new bridge piers. Ms. Euliss said that this needed to be noted in the Construction Consultation while addressing the areas of the project outside the study corridor. Mr. Cook pointed out that the bridge will have deck drains due to hydraulic spread in to the travel lane. Deck drains will be present over the Yadkin River on the new bridge during construction but will be plugged once construction is completed. Mr. Elam pointed out that this is an improvement over the existing bridge since it currently has deck drains over the river. Ms. Euliss asked that this be included in the permit application. Marella Buncick asked if riprap would be placed on the ground under the deck drains. Mr. Cook said it would not be since the area is used for soccer fields / parking. Also, the height of the bridge above existing ground should allow the water to disperse through the air.

During construction of the bridge, the DB Team is proposing a phased construction sequence that will require causeways to be placed in the river at different times. Mr. Cook showed the phasing plan as well as the anticipated causeways that would be used during construction. The causeways would extend from both sides of the river out to the new bridge bents. 54" pipes will be installed in the causeways to help with river passage. Ms. Euliss asked if the causeways would extend to cover more than half the river width. Jason Mroz said that they might during the period of time that additional causeway length is needed to remove the existing piers. However that time frame should not be more than one week long and the weather would be checked prior to this operation to ensure no major storms. Ms. Buncick asked about the stability of the Yadkin River banks after the causeway removal. Mr. Cook said that they could leave the banks lined with riprap. He also showed a video of the Yadkin River crossing and its banks in its current state. Ms. Euliss said not to line the banks at this time. Ms. Buncick suggested maintaining construction access roads well during construction to prevent sediment loss. She also suggested using jersey barrier with sheeting on top as an alternative means for river passage under the causeway. She asked about slurry created during the dilled shaft pier construction. Mr. Mroz said they would take the slurry behind them away from the river to a stabilized area.

Plan sheet 13 (Streams A and UT-SA, wetlands A and WAD): Stream A runs north to south through the project and is conveyed in a 42" RCP at –L- 147+00 to be retained with an 54" pipe extension to accommodate the roadway system drainage. It is impacted by the proposed fill slope on the upstream end and by construction of a new drainage system on the downstream end. There is extensive scour that has occurred at the pipe outlet and along the roadside ditch that feeds the stream at the pipe outlet. Mr. Cook stated that a riprapped energy dissipator basin was designed at the outlet of the pipe to attenuate the flow and minimize the velocity before entering the existing stream downstream of the project. Wetland A will also be impacted by toe protection that will be installed along the fill slope. It should still receive overland flow. This will be Site 9. Ms. Chambers asked if the DB Team could angle the pipe more to prevent taking it through such a long length of pipe including junction boxes. Mr. Elam stated that NCDOT preferred not to have pipes skewed under the roadway facility at angles greater than 30 degrees. She said she was concerned about fish passage. Mr. Cook said that there is not any passage currently since the scour is so great at the outlet end that the pipe is perched a couple feet and portions of the pipe broken off in the stream. Ms. Chambers asked if we could gain stormwater treatment anywhere in this area. Mr. Cook stated that the contours were too steep. Video inspection of the existing 42" RCP led NCDOT Division to ask that it be replaced. The 4C plans will reflect the design decision. Everyone agreed that a new pipe would not need to be buried.

The system outletting at –L- 142+50 RT has been removed from the design. There will be no impacts to stream A where it was supposed to outlet. Wetland WAD has no impacts. Stream UT-SA has no impacts.



Plan sheet 15: No impacts and no jurisdictional features. The outlet at –L- 172+00 LT is outside the study corridor and will be reviewed by Ms. Cheely. –L- 195+00-196+00 is outside the study corridor and will also be reviewed.

Plan sheet 16: No impacts and no jurisdictional features. This sheet is outside the study corridor and will be reviewed by Ms. Cheely.

After completing the review of the plans, Mr. Cook asked if anyone was interested in a field visit to see the sites and project. No one felt it necessary to review the project in person.

The meeting adjourned.

R:\Hydraulics\DOCUMENTS\Permits\I-0911A 4B Minutes.docx



I-0911A 4C Interagency Concurrence Point Meeting Minutes



Date: January 18, 2018

Location: NCDOT Structures Conference Room

Time: 3:00 PM

Minutes Authored By: Matthew Cook Attendees: Bill Elam – NCDOT Hydraulics

Bill Elam – NCDOT Hydraulics

Jason Mroz – Flatiron

Matthew Cook – RK&K

Brent Huskey – RK&K

Via Telephone:

Monte Matthews – USACE Dave Wanucha - NCDWR
Amy Euliss – NCDOT Div.9 Carla Dagnino – NCDOT EAL

Tim McFadden – NCDOT Design Build Malcolm Watson – NCDOT Design Build

Marla Chambers – NCWRC

Tierre Peterson – NCDOT Structures

Nancy Scott - Three Oaks

Carla Dagnino – NCDOT EAU

Malcolm Watson – NCDOT Design Build

Rodney Hatton – NCDOT Div. 9

Mike Wood – Three Oaks

An interagency concurrence point meeting was held in order to reach agreement on concurrence point 4C for the I-0911A I-40 widening project in Davie and Forsyth Counties. The following items were discussed and conclusions reached:

Bill Elam began the meeting and introductions were made. He then turned the meeting over to the Design Build (DB) Team.

Matthew Cook introduced the DB Team for the project. RK&K is the prime designer. The project is being constructed by the Flatiron / Blythe Development Joint Venture. The DB Team was awarded the job in July 2017. The project is on I-40 approximately 14 miles west of Winston Salem. It runs one mile west of NC 801 to one half mile east of Harper Rd. It is 3.78 mi in length with 0.21 mi of bridge over the Yadkin River. The Yadkin River crossing is the only major hydraulic structure being affected by the project. The 4B meeting was held for this project November 15, 2017.

Mr. Cook then began to go through the 4C Permit drawings.

Permit drawing 3 of 33

Site 1, Stream SC: Stream SC begins at the outlet to the existing 36" RCP at –L- 46+50 RT. It is impacted by the proposed fill slope. The existing pipe will be cleaned out, slip lined, and extended with a 66" RCP that will also include the drainage from the interchange. There is extensive scour that has occurred at the pipe outlet and along the roadside ditch that feeds the stream at the pipe outlet. Mr. Cook stated that a riprapped energy dissipator basin was designed at the outlet of the pipe to attenuate the flow and reduce the velocity (from V10 23.3ft/s to 5.9ft/s) before entering the existing stream downstream of the project. The proposed pipe extension will not be buried. The permanent stream impact will continue to the permanent drainage easement limit to allow for a smoother transition from the basin to the existing stream and also to allow for future NCDOT Division maintenance.

Permit drawing 5 of 33

Site 2, Streams CB: Stream CB runs south to north through the project and is currently conveyed in a 42" RCP at –L- 68+00. It is impacted by the proposed fill slope. A new 48" welded steel pipe will be installed by bore and jack methods parallel to the existing pipe. The existing pipe will be plugged and filled with flowable fill. There is extensive scour that has occurred at the pipe outlet. Mr. Cook said that the outlet channel is more than 20' incised and unstable with three sections of 42" RCP broken off in the channel. He stated that a riprapped energy dissipator basin was designed at the outlet of the pipe to attenuate the flow and reduce the velocity (from V10 19.0ft/s to 5.5ft/s) before entering the existing stream downstream of the project. The pipe would also be extended using junction boxes to allow the stream to enter the downstream channel without a bend. The proposed 48" pipe will not be buried. The permanent stream impact will continue to the ditch construction limit beyond the basin to allow for a smoother transition from the basin to the existing stream and also to allow for future NCDOT Division maintenance. Dave Wanucha asked that the steam's transition location from intermittent to perennial be listed in the permit application.





Site 3, Stream CBZ: Stream CBZ runs parallel to I-40 at –L- 67+50 RT and ties to stream CB prior to entering the upstream end of the crosspipe. It is impacted by the proposed fill slope and will be a total take.

Permit drawing 7 of 33

Site 4, Stream JS: Stream JS runs south to north through the project and is currently conveyed in a 24" RCP at –L- 84+50. It is impacted by the proposed fill slope. A new 48" welded steel pipe will be installed by bore and jack methods parallel to the existing pipe. The existing pipe will be plugged and filled with flowable fill. Junction boxes will be used to place the new pipe in line with the receiving pipe under Pinewood Ln. A new 48" RCP will be installed under Pinewood Ln. just downstream of the proposed 48" under I-40 since the existing pipe under Pinewood Ln. is only a 24" RCP. The 24" pipe under Pinewood Ln. will continue to receive drainage via catch basins on Pinewood Ln. but will no longer receive I-40 drainage. At the outlet of the proposed 48" RCP under Pinewood Ln., a ditch will be constructed to convey the drainage to the adjacent pond. There will be no jurisdictional impacts to the pond. Amy Euliss asked if we could extend the temporary drainage easement at the ditch / pond tie-in for a turbidity curtain to be used. Mr. Cook said they could add it. Marla Chambers asked if Stream JS continued between the existing 24" outlet pipe and the pond. Mr. Cook said that their files did not show a stream there. Carla Dagnino stated she would check in to whether there was a jurisdictional feature between the outlet pipe and pond. Monte Matthews asked if the pond was being listed as a stormwater device. Mr. Cook said it was not.

Site 5, Stream SAA, Wetland J: Stream SAA runs parallel to I-40 at –L- 84+50 RT and ties to the stream JS prior to entering the upstream end of the crosspipe. It is impacted by the proposed fill slope and will be a total take. Wetland J at –L- 84+5 RT is also impacted by the proposed fill slope and will be a total take.

Permit drawing 10 of 33

Site 6, Stream FH: Stream FH runs south to north through the project and is currently conveyed in a 42" RCP at –L- 99+50. The upstream end is impacted by the proposed channel to redirect flow to the proposed pipe. The downstream end is impacted by the proposed fill slope. A new 54" welded steel pipe will be installed by bore and jack methods parallel to the existing pipe. The existing pipe will be plugged and filled with flowable fill. The proposed 54" pipe will not be buried. An existing 24" RCP downstream of the existing 42" RCP will be removed. A ditch will be constructed to convey the drainage from the proposed 54" pipe to the adjacent pond. There will be no jurisdictional impacts to the pond. Ms. Chambers asked if Stream FH continued between the existing 24" outlet pipe and the pond. Mr. Cook said that their files did not show a stream there.

Permit drawing 12 of 33

Site 7A, Stream SP, Wetlands SP: Wetland SP at -L- 119+50 – 123+50 RT will be impacted by the proposed fill slope and lateral base ditch. Mr. Cook said that the lateral base ditch was modified (versus the design shown at the 4B meeting) to achieve some swale filtration prior to entering stream SP. Stream SP is impacted by the lateral base ditch tie-in at -L- 123+50 LT. Mr. Cook stated that they would add a permanent stream impact as bank stabilization where the riprap transition occurred.

Permit drawing 15 of 33

Sites 7B and 7C, Stream SP: Stream SP at -L- 129+00 will be impacted at two locations (Site 7B LT and Site 7C RT) due to ditch tie-ins from the proposed drainage. The ditches impacting stream SP were used in lieu of preformed scour holes due to stability concerns. Bank stabilization will occur where lateral V ditches tie-in to stream SP. Mr. Cook said that stream SP will have crane mats placed over it during construction under the proposed bridge for project access, but they will not create stream impacts.

Site 8, Yadkin River:

The 1104′ new bridge will have 8 spans over the FEMA regulated river. Mr. Cook pointed out that the original project commitments stated that there would be "no impacts to the Yadkin River". Mr. Cook said this was impossible given the new bridge piers, and will be noted in the permit application. Mr. Cook pointed out that the bridge will have deck drains due to hydraulic spread in to the travel lane. Deck drains will be present over the Yadkin River on the new bridge during construction but will be plugged once construction is completed which is an improvement over the existing bridge since it currently has deck drains over the river.

During construction of the bridge, the DB Team is proposing a phased construction sequence that will require causeways to be placed in the river at different times. Mr. Cook showed the phasing plan as well as the anticipated causeways that would be used during construction. The causeways would extend from both sides of the river to 10' beyond the new bridge bents and 40' beyond the outside of the proposed bridge LT and RT. The height of the causeways would be 2' above normal water surface and would extend to the river bottom with 1:1 slopes. 54" pipes will be installed in the causeways to help with river passage. Mr. Cook said that during construction the river would never be blocked more than 50% by causeways. Ms. Chambers asked that a note stating this be added to the permit impact summary. Ms. Chambers also asked how long the causeways will be in place. Jason Mroz stated approximately 8 – 10 months per phase for a total of 28 months. The existing pier removal causeways will be in place approximately 1 month each. Mr. Matthews asked that the downstream banks be monitored during construction for any issues that might occur due to the causeways. Ms. Euliss asked that turbidity curtains be included around the downstream ends of the causeways during their installation and removal. Mr. Cook said they could do this, and a note would be placed on the erosion control plans. He said they would not be advisable the entire time the causeways were in place because they would block the flow conveyed by the temporary 54" pipes.



Permit drawing 25 of 33

Site 9, Streams A, Wetland A: Stream A runs north to south through the project and is currently conveyed in a 42" RCP at –L- 147+00. It is impacted by the proposed fill slope upstream. A new 42" welded steel pipe will be installed by bore and jack methods parallel to the existing pipe. The existing pipe will be plugged and filled with flowable fill. There is extensive scour that has occurred at the pipe outlet and along the roadside ditch that feeds the stream at the pipe outlet. Mr. Cook stated that a riprapped energy dissipator basin was designed at the outlet of the pipe to attenuate the flow and reduce the velocity (from V10 22.0ft/s to 6.0ft/s) before entering the existing stream downstream of the project. The proposed 42"pipe will not be buried. The permanent stream impact will continue to the permanent drainage easement limit to allow for a smoother transition from the basin to the existing stream and also to allow for future NCDOT Division maintenance. A portion of stream A will also be impacted at -L- 143+60 RT due to plugging an existing 18" CMP and filling it with flowable fill. The temporary impact is to allow for construction to occur. Ms. Chambers asked that if concrete is used that it be isolated and measures used to prevent any surface water contamination.

Wetland A will also be impacted by mechanized clearing along the fill slope. Ms. Chambers asked if this should be a total take given the extent of the wetland impact. Mike Wood stated that this is a seep wetland and he expected the area would stay wet. He thought the partial impact was the best way to show the impact.

Permit drawing 28 and 30 of 33

Site 10: This stream and wetland at -L- 196+00 were added during Erin Cheely's (NCDOT ECAP) field visit for jurisdictional areas outside the corridor. The stream runs north to south through the project and is currently conveyed in a 60" RCP. A new 60" welded steel pipe will be installed by bore and jack methods parallel to the existing pipe. The existing pipe will be plugged and filled with flowable fill. The proposed 60" pipe will not be buried. Craig Lee asked that the proposed riprap pad at the proposed outlet be shown to scale.

Ms. Dagnino asked if the project would fit within the parameters of a GP-31. Mr. Matthews said he would check in to it. Mr. Wanucha said he did not have a preference.

The meeting adjourned.

R:\Hydraulics\DOCUMENTS\Permits\I-0911A 4C Minutes.docx





Highway Stormwater Program STORMWATER MANAGEMENT PLAN



(Version 2.07; Released October 2016)

FOR NCDOT PROJECTS

WBS Element:	34147.3.4	TIP No.:	I-0911A		County(ies):	Davie Forsyth			Pag	e 1	of	4	
					General Project	Information							
WBS Element:		34147.3.4		TIP Number:	I-0911A		Project	Type:	Roadway Widening	Date:	1/4/2018		
NCDOT Contact:		Craig Lee, PE				Contractor / Desig							
	Address:	NC Department of	f Transportation				Address:	900 Ridgefi	ield Drive				
		1020 Birch Ridge	Dr					Suite 350					
		Raleigh, NC 2761	0					Raleigh, NO	C 27609				
	Phone:	919-707-6708					Phone:	919-878-95	560				
	Email:	cjlee@ncdot.gov					Email:	mcook@rkl	k.com				
City/Town:			Bermu	da Run		County(ies):	Dav	vie	Forsyth				
River Basin(s):		Yadkin-P	ee Dee			CAMA County?	No)	No				
Wetlands within Pro	ject Limits?	Yes											
					Project Des								
Project Length (lin. r	miles or feet):	3.7	8	Surrounding	Land Use:	Residential and Cor	mmercial						
				Proposed Proje	ect				Existing Site				
Project Built-Upon A			67.0		ac.			58.0	ac.				
Typical Cross Section	on Description:	6 lane dvided high							ith a grass median: 10' outside		(2) 12' travel la	ines,	
		median shoulders spans the Yadkin	, ()	nes, 14' outside s	snoulders. 122 w	ide bridge that	4 median sno	bulder. Duai	bridges that spans the Yadkin	River.			
		spans the Taukin	Kivei.										
Annual Avg Daily Tra	offic (wob/br/dov):	5	_			0007	- · · ·		50.000		00.45		
General Project Nari		Design/Future		4,800 0 from 4 Janes to		2037	Existing:	orovomonto	58,600 and the rehabilitation of the du	Ye			
(Description of Minir									ng the construction of the prop				
Quality Impacts)	inzution of Water								ge will discharge through deck				
		only during the ter	mporary condtion	for traffic phasin	g but will not disc	harge into the river in	n the permane	nt condition.	Concrete will be precasted or	ffiste when p	ossible to		
									@ 155', 3 spans @ 150', 1 sp				
									our Holes are used as Best Ma				
									er enters jurisdictional streams jurisdictional streams.	. There are	three sites wh	ere	
		lifere are propose	a preformed sco	ui rioles to provid	ie enegery dissipa	מווטוז מווע וווווונומנוטוז ג	before the water	i cilicis lile	jurisuictional streams.				
					Waterbody Inf	ormation							
Surface Water Body	(1):		Yadkir	River		NCDWR Stream In	idex No.:		12-(86.7)				
NCDWR Surface Wa	tor Classification fo	r Water Body		Primary Classif	fication:	Water Supply I	V (WS-IV)						
NODWK Garrace Wa	ter olassification to	Water Body		Supplemental (Classification:								
Other Stream Classi	fication:	Nor	ne										
Impairments:		Nor	ne										
Aquatic T&E Species	s?	No	Comments:										
NRTR Stream ID:		Yadkin River						Buffer Rule	es in Effect:		N/A		
Project Includes Brid	dge Spanning Water	r Body?		Deck Drains Di	scharge Over Βι	ıffer?	N/A	Dissipator	Pads Provided in Buffer?		N/A		
Deck Drains Dischar	rge Over Water Bod	y?	Yes										



Highway Stormwater Program STORMWATER MANAGEMENT PLAN

FOR NCDOT PROJECTS

WBS Element:	34147.3.4	TIP No.:	I-0911A	County(ies):	Page	2	of	4			
				Additional Waterboo	dy Information						
Surface Water Body	/ (2):		Smith	Creek	NCDWR Stream In	dex No.:		12-93-1			
NCDWR Surface Wa	ater Classification fo	r Water Rody		Primary Classification:	Class C						
NODIVIN GUITACC W	ater Glassification to	Water Body		Supplemental Classification:	None						
Other Stream Class	ification:	Nor	ne								
Impairments:		Nor	ne								
Aquatic T&E Specie	es?	No	Comments:								
NRTR Stream ID:				Buffer Rules in Effect:		N/A					
Project Includes Bri	idge Spanning Water	Body?	No	Deck Drains Discharge Over Bu	ffer?	N/A	Dissipator Pads Provided	in Buffer?	N/A		
Deck Drains Discha	rge Over Water Body	y?	No								
Surface Water Body	/ (3):		Johnson	n Creek	NCDWR Stream In	dex No.:	12-91				
NCDWR Surface Wa	ator Classification fo	r Water Body		Primary Classification:	Water Supply I'	V (WS-IV)					
NODIVIN GUITACC W	DWR Surface Water Classification for Water Body			Supplemental Classification:	None						
Other Stream Class	ification:	Nor	ne								
Impairments:		Nor	ne								
Aquatic T&E Specie	es?	No	Comments:								
NRTR Stream ID:	·	UT to Johnson Cr	eek (not in NRTI	R)	Buffer Rules in Effect:			N/A			
Project Includes Bri	idge Spanning Water	Body?	No	Deck Drains Discharge Over Buffer? N/A			Dissipator Pads Provided in Buffer? N/A				
Deck Drains Discha	rge Over Water Body	y?	No	(If yes, provide justification in	(If yes, describe in the General Project Narrative; if no, justify in the						
(If yes, provi	ide justification in the	General Project Na	arrative)			General Project Narrative)					



Highway Stormwater Program

(Version 2.07; Released October 2016)

STORMWATER MANAGEMENT PLAN

FOR NCDOT PROJECTS WBS Element: 34147.3.4 TIP No.: I-0911A County(ies): Davie Forsyth Page of

							Swales								
Sheet No.	Station & Coordinates (Road and Non Road Projects)	Surface Water Body	Base Width (ft)	Front Slope (H:1)	Back Slope (H:1)	Drainage Area (ac)	Recommended Treatm't Length (ft)	Actual Length (ft)	Longitudinal Slope (%)	Q2 (cfs)	V2 (fps)	Q10 (cfs)	V10 (fps)	Rock Checks Used	BMP Associated w/ Buffer Rules?
7	-L- STA. 49+17 LT		4.0	3.0	3.0	4.9	493	372	1.98%	14.6	3.1	18.9	3.3	No	No
11	-L- STA. 123+50 LT		4.0	3.0	3.0	19.5	1945	199	1.20%	57.6	3.7	74.5	4.0	No	No
12	-L- STA. 128+97 LT		0.0	3.0	3.0	0.1	12	51	4.04%	0.4	1.7	0.5	1.9	No	No
12	-L- STA. 129+16 RT		0.0	3.0	3.0	0.4	36	207	5.29%	1.1	2.4	1.4	2.6	No	No

Additional Comments



Highway Stormwater Program





(Version 2.07: Released October 2016)


STORMWATER MANAGEMENT PLAN
FOR NCDOT PROJECTS

(Version 2.0	(Version 2.07; Released October 2016) FOR NCDOT PROJECTS												
	WBS Element:		TIP No.:		Page 4	of 4							
	Preformed Scour Holes and Energy Dissipators												
Sheet No.	Station & Coordinates (Road and Non Road Projects)	Surface Water Body	Energy Dissipator	Riprap Type	Drainage Area (ac)	Conveyance Structure	Pipe/Structure Dimensions (in)	Q10 (cfs)	V10 (fps)	BMP Associated w/ Buffer Rules?			
4	-L- STA. 49+17 LT		PSH	Class 'B'	0.4	Pipe	15	2.2	0.5	No			
11	-L- STA. 121+50 RT		PSH	Class 'B'	2.8	Pipe	18	9.5	1.0	No			
12	-L- STA. 139+49 RT		PSH	Class 'B'	1.7	Pipe	18	8.2	0.9	No			
				Additional Co	ommonte								


Additional Comments









-L- STA. 10+46 TO STA. 11+00 RT
-L- STA. 10+48 TO STA. 11+00 LT
-L- STA. 41+00 TO STA. 43+50 LT
-L- STA. 43+50 LT
-L- STA. 45+00 TO STA. 43+50 LT
-L- STA. 45+00 TO STA. 49+50 RT
-L- STA. 43+00 TO STA. 59+00 RT
-L- STA. 43+00 TO STA. 59+00 RT
-L- STA. 134-00 TO STA. 163+50 LT
-L- STA. 156+00 TO STA. 163+50 LT
-L- STA. 156+00 TO STA. 163+50 LT
-L- STA. 157+00 TO STA. 169+50 LT
-L- STA. 157+00 TO STA. 178+50 RT
-YIRPD- STA. 14+21 TO STA. 178+50 LT
-YIRPD- STA. 14+21 TO STA. 17+50 LT




-YRPB- STA. 14+04 TO STA. 17+50 LT -YRPB- STA. 17+50 TO STA. 18+00 LT; CLASS I -YRPC- STA. 10+16 TO STA. 16+80 RT; VARYING V.C




-L- STA. 38+00 TO STA. 39+74 RT
-L- STA. 45+79 TO STA. 46+50 RT
-L- STA. 55+50 TO STA. 37+50 LT
-L- STA. 60+00 TO STA. 62+00 LT
-L- STA. 60+00 TO STA. 62+00 LT
-STA. 127+09 TO STA. 129+16 RT; 3:1 SLOPES
-L- STA. 128+46 TO STA. 128+97 LT; 3:1 SLOPES
-L- STA. 138+67 TO STA. 140+50 LT
-L- STA. 141+50 TO STA. 140+00 LT
-STA. 141+50 TO STA. 144+50 LT
-YIRPS-STA. 18+50 TO STA. 142+50 LT
-YIRPS-STA. 18+50 TO STA. 122+50 RT



-L- STA, 39+60 TO STA, 41+00 LT
-L- STA, 49+17 TO STA, 52+89 LT, 3:1 SLOPES
-L- STA, 84+80 TO STA, 85+50 LT, 2' BERM
-L- STA, 85+50 TO STA, 87+00 LT
-L- STA, 84+60 TO STA, 87+28 RT
-L- STA, 84+83 TO STA, 89+00 LT
-L- STA, 94+00 TO STA, 69-66 LT
-L- STA, 94+00 TO STA, 79+50 RT
-L- STA, 100+50 TO STA, 102+46 LT





-L- STA. 145+50 TO STA. 148+00 LT -YRPB- STA. 17+50 TO STA. 19+00 LT -YRPB- STA. 19+50 TO STA. 20+78 LT -YIRPD- STA. 17+00 TO STA. 19+00 RT



PERMIT DRAWING SHEET 2 OF 33












d= 2.0 Ft.


DETAIL


TOE PROTECTION (Not to Scale)



































PLANS PREPARED BY : RUMMEL KLEPPER & KAHL LIP


900 RIDGEFIELD DRIVE SUITE 350 RALEIGH, NORTH CAROLINA 27609–3960 NC LICENSE NO. F-0112 • (919) 878–9560






















































































			Wi	ETLAND AI	ND SURAC	E WATER IM	IPACTS S	UMMARY				
				WE	TLAND IMPA	CTS			//PACTS	ACTS		
Site	Station	Structure	Permanent Fill In	Temp. Fill In	Excavation in	Mechanized Clearing	Hand Clearing in	Permanent SW	Temp. SW	Existing Channel Impacts	Existing Channel Impacts	Natural Stream
No.	(From/To)	Size / Type	Wetlands (ac)	Wetlands (ac)	Wetlands (ac)			impacts (ac)	impacts (ac)	Permanent (ft)	Temp. (ft)	Design (ft)
1	-L- 46+35 TO 46+58 RT	ROADWAY FILL						< 0.01		41		
2	-L- 66+89 TO 71+75 LT & RT	ROADWAY FILL						0.04	< 0.01	374	30	
3	-L- 67+30 TO 68+07 RT	ROADWAY FILL						< 0.01		84		
4	-L- 84+03 TO 84+72 LT & RT	ROADWAY FILL						< 0.01		57		
5	-L- 84+11 TO 84+62 RT ROADWAY FILL		0.01					< 0.01		19		
6	-L- 99+44 TO 99+71 LT & RT	ROADWAY FILL & DITCH						< 0.01		57		
7A	-L- 119+64 TO 123+66 LT	BANK STABILIZATION	0.23					< 0.01	< 0.01	9	21	
7B	-L- 128+75 TO 129+03 LT	BANK STABILIZATION						< 0.01	< 0.01	6	21	
7C	-L- 129+14 TO 129+20 RT	BANK STABILIZATION						< 0.01	< 0.01	4	20	
8	-L- 134+87 TO 137+72	BRIDGE							1.01		144	
9	-L- 145+53 TO 149+33 LT & RT	ROADWAY FILL				< 0.01		0.03	< 0.01	244	31	
10	-L- 195+27 TO 196+20 LT & RT	60" WS	< 0.01			< 0.01		< 0.01	< 0.01	17	21	
TOTALS*:			0.24			0.01		0.09	1.03	912	288	0

^{*}Rounded totals are sum of actual impacts


NOTES:

Site 8 has 14 proposed bridge piers with a diameter of 4.5' for a total area of 222.7 sf Yadkin River to never be blocked more that 50% at any time during construction.

NC DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
February 2018
DAVIE & FORSYTH
I-0911A

SHEET 33 OF 33

Revised 2016 09 09



BOUNDARIES AND PROPERTY:

STATE OF NORTH CAROLINA, DIVISION OF HIGHWAYS

CONVENTIONAL PLAN SHEET SYMBOLS

Note: Not to Scale

*S.U.E. = Subsurface Utility Engineering

WATER:

State Line ————————————————————————————————————					Water Manhole	- W
County Line	D 4 M D 0 4 D 0				Water Meter	- 0
Township Line ————————————————————————————————————	RAILROADS:		Orchard —		Water Valve	- ⊗
City Line ————————————————————————————————————	Standard Gauge —————	CSX TRANSPORTATION		\$ \$ \$ \$	Water Hydrant	- ♣
Reservation Line ————————————————————————————————————	RR Signal Milepost	€ MILEPOST 35	vinleyara	Vineyard	U/G Water Line LOS B (S.U.E*)	w
Property Line ————————————————————————————————————	Switch ————	SWITCH	EXISTING STRUCTURES:		U/G Water Line LOS C (S.U.E*)	
Existing Iron Pin	RR Abandoned		MAJOR:		U/G Water Line LOS D (S.U.E*)	
Property Corner ———————————————————————————————————	RR Dismantled		Bridge, Tunnel or Box Culvert ————	CONC		A/G Water
Property Monument	RIGHT OF WAY:		Bridge Wing Wall, Head Wall and End Wall –	CONC WW (Above Ground Water Line	
Parcel/Sequence Number — (23)	Baseline Control Point	•	MINOR:		TV:	
	Existing Right of Way Marker	\triangle	Head and End Wall	CONC HW	TV Pedestal	
Existing Terrice Line	Existing Right of Way Line		Pipe Culvert —————		TV Tower	- 🛇
Proposed Woven Wire Fence	Proposed Right of Way Line		Footbridge	·	U/G TV Cable Hand Hole	- H _H
Proposed Chain Link Fence	Proposed Right of Way Line with		Drainage Box: Catch Basin, DI or JB	СВ	U/G TV Cable LOS B (S.U.E.*)	тv
Proposed Barbed Wire Fence ———	Iron Pin and Cap Marker	- (k)	Payed Ditch Gutter		U/G TV Cable LOS C (S.U.E.*)	тv
Existing Wetland Boundary	Proposed Right of Way Line with	\mathcal{R}	Storm Sewer Manhole ————	(S)	U/G TV Cable LOS D (S.U.E.*)	тv—
Proposed Wetland Boundary ————————————————————————————————————	Concrete or Granite R/W Marker			(5)	U/G Fiber Optic Cable LOS B (S.U.E.*)	
Existing Endangered Animal Boundary ————————————————————————————————————	Proposed Control of Access Line with Concrete C/A Marker	(A)	Storm Sewer	s	U/G Fiber Optic Cable LOS C (S.U.E.*)	
Existing Endangered Plant Boundary ————————————————————————————————————		(\bar{\bar{\bar{\bar{\bar{\bar{\bar{	UTILITIES:		U/G Fiber Optic Cable LOS D (S.U.E.*)	
Existing Historic Property Boundary	Proposed Control of Access	\d>	POWER:			
Known Contamination Area: Soil ————————————————————————————————————	'	&	Existing Power Pole	•	GAS:	
Potential Contamination Area: Soil ————————————————————————————————————	Existing Easement Line	L	Proposed Power Pole —	\forall	Gas Valve	- ♦
Known Contamination Area: Water ————————————————————————————————————	Proposed Temporary Construction Easement -		Existing Joint Use Pole		Gas Meter	▽
Potential Contamination Area: Water ————————————————————————————————————	Proposed Temporary Drainage Easement——		Proposed Joint Use Pole		U/G Gas Line LOS B (S.U.E.*)	
Contaminated Site: Known or Potential — 💢 🏋	Proposed Permanent Drainage Easement ——	PDE	Power Manhole —	©	U/G Gas Line LOS C (S.U.E.*)	
	Proposed Permanent Drainage / Utility Easement	DUE	Power Line Tower	♥	U/G Gas Line LOS D (S.U.E.*)	
BUILDINGS AND OTHER CULTURE:	Proposed Permanent Utility Easement ———	PUE			Above Ground Gas Line	A/G Gas
Gas Pump Vent or U/G Tank Cap — O	Proposed Temporary Utility Easement ———	TUE	Power Transformer	\square	SANITARY SEWER:	
Sign — Ö	Proposed Aerial Utility Easement ————	AUE	U/G Power Cable Hand Hole			
Well —	Proposed Permanent Easement with		H-Frame Pole	•—•	Sanitary Sewer Manhole	
Small Mine —	Iron Pin and Cap Marker		U/G Power Line LOS B (S.U.E.*)		Sanitary Sewer Cleanout	-
Foundation	ROADS AND RELATED FEATURE	ZS:	U/G Power Line LOS C (S.U.E.*)		U/G Sanitary Sewer Line ————————————————————————————————————	
Area Outline —	Existing Edge of Pavement		U/G Power Line LOS D (S.U.E.*)	P	Above Ground Sanitary Sewer —————	A/G Sanitary Sewer
Cemetery †	Existing Curb		TELEPHONE:		SS Forced Main Line LOS B (S.U.E.*) ———	FSS
Building	Existing Corb	<u>C</u>			SS Forced Main Line LOS C (S.U.E.*)———	
School	Proposed Slope Stakes Fill	<u>F</u>	Existing Telephone Pole —————	-•-	SS Forced Main Line LOS D (S.U.E.*)———	FSS
Church —			Proposed Telephone Pole	-0-		
Dam —	Proposed Curb Ramp	CR	Telephone Manhole	\bigcirc	MISCELLANEOUS:	
HYDROLOGY:	Existing Metal Guardrail —————		Telephone Pedestal	T	Utility Pole ————————————————————————————————————	- •
Stream or Body of Water	Proposed Guardrail —————		Telephone Cell Tower ——————	, Ā ,	Utility Pole with Base ——————	
Hydro, Pool or Reservoir	Existing Cable Guiderail		U/G Telephone Cable Hand Hole	H _H	Utility Located Object ——————	- <u></u>
	Proposed Cable Guiderail		U/G Telephone Cable LOS B (S.U.E.*)		Utility Traffic Signal Box ———————————————————————————————————	- S
Jurisdictional Stream	Equality Symbol	lacktriangle	U/G Telephone Cable LOS C (S.U.E.*)		Utility Unknown U/G Line LOS B (S.U.E.*)	
	Pavement Removal		U/G Telephone Cable LOS D (S.U.E.*)		U/G Tank; Water, Gas, Oil —	_
Buffer Zone 2 ———————————————————————————————————	VEGETATION:		U/G Telephone Conduit LOS B (S.U.E.*)		Underground Storage Tank, Approx. Loc. —	
Flow Arrow	Single Tree	£	U/G Telephone Conduit LOS C (S.U.E.*)		A/G Tank; Water, Gas, Oil	
Disappearing Stream	Single Shrub	\$			Geoenvironmental Boring	
Spring	Hedge —		U/G Telephone Conduit LOS D (S.U.E.*)		U/G Test Hole LOS A (S.U.E.*)	· ·
Wetland \underset	Woods Line	-::-::-:::-:::-:::-:::-:::-:::-:::-:::-:::-::::	U/G Fiber Optics Cable LOS B (S.U.E.*)			•
Proposed Lateral, Tail, Head Ditch ————————————————————————————————————			U/G Fiber Optics Cable LOS C (S.U.E.*)		Abandoned According to Utility Records —	
False Sump — >			U/G Fiber Optics Cable LOS D (S.U.E.*)——	T FO	End of Information ————————————————————————————————————	E.O.I.


PAVEMENT SCHEDULE

C1	PROP. APPROX. 1.5" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 168 LBS. PER SQ. YD.	E4	PROP. APPROX. 3.0" ASPHALT CONCRETE BASE COURSE, TYPE B25.0C, AT AN AVERAGE RATE OF 342 LBS. PER SQ. YD.
C2	PROP. APPROX. 2" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 224 LBS. PER SQ. YD.	E5	PROP. APPROX. 8.0" ASPHALT CONCRETE BASE COURSE, TYPE B25.0C, AT AN AVERAGE RATE OF 456 LBS. PER SQ. YD. IN EACH OF TWO LAYERS.
C3	PROP. APPROX. 3" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 168 LBS. PER SQ. YD. IN EACH OF TWO LAYERS.	E6	PROP. VAR. DEPTH ASPHALT CONCRETE BASE COURSE, TYPE B25.0C, AT AN AVERAGE RATE OF 114 LBS. PER SQ. YD. PER 1" DEPTH. TO BE PLACED IN LAYERS NOT LESS THAN 4.0" IN DEPTH OR GREATER THAN 5.5" IN DEPTH.
C4	PROP. VAR. DEPTH ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 168 LBS. PER SQ. YD. PER 1.5" DEPTH. TO BE PLACED IN LAYERS NOT TO EXCEED 2" IN DEPTH.	J1	PROP. 6" AGGREGATE BASE COURSE
C5	PROP. APPROX. 3" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5C, AT AN AVERAGE RATE OF 168 LBS. PER SQ. YD. IN EACH OF TWO LAYERS.	J2	PROP. 8" AGGREGATE BASE COURSE
C6	PROP. VAR. DEPTH ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5C, AT AN AVERAGE RATE OF 168 LBS. PER SQ. YD. PER 1.5" DEPTH. TO BE PLACED IN LAYERS NOT TO EXCEED 2" IN DEPTH.	K1	BASE TO BE TREATED WITH LIME TO A DEPTH OF 8" AT A RATE OF 36 LBS. PER SQ. YD.
D1	PROP. APPROX. 2.5" ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE I19.0B, AT AN AVERAGE RATE OF 285 LBS. PER SQ. YD.	K2	CLASS IV SUBGRADE STABILIZATION
D2	PROP. APPROX. 3" ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE I19.0B, AT AN AVERAGE RATE OF 342 LBS. PER SQ. YD.	Р	PRIME COAT
D3	PROP. APPROX. 4" ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE I19.0B, AT AN AVERAGE RATE OF 456 LBS. PER SQ. YD.	R1	2'-6" CONCRETE CURB AND GUTTER
D4	PROP. VAR. DEPTH ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE I19.0B, AT AN AVERAGE RATE OF 114 LBS. PER SQ. YD. PER 1" DEPTH. TO BE PLACED IN LAYERS NOT LESS THAN 2.5" IN DEPTH OR GREATER THAN 4.0" IN DEPTH.	R2	DOUBLE FACED CONCRETE BARRIER (TYPE T, T1, T2)
D5	PROP. APPROX. 3" ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE I19.0C, AT AN AVERAGE RATE OF 342 LBS. PER SQ. YD.	R3	PRECAST SINGLE-FACED BARRIER
D6	PROP. APPROX. 5" ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE I19.0C, AT AN AVERAGE RATE OF 285 LBS. PER SQ. YD. IN EACH OF TWO LAYERS.	Т	EARTH MATERIAL
D7	PROP. VAR. DEPTH ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE I19.0C, AT AN AVERAGE RATE OF 114 LBS. PER SQ. YD. PER 1" DEPTH. TO BE PLACED IN LAYERS NOT LESS THAN 2.5" IN DEPTH OR GREATER THAN 4.0" IN DEPTH.	U	EXISTING PAVEMENT
E1	PROP. APPROX. 5.5" ASPHALT CONCRETE BASE COURSE, TYPE B25.0B, AT AN AVERAGE RATE OF 627 LBS. PER SQ. YD.	V	MILLING ASPHALT OFF OF EXISTING CONCRETE
E2	PROP. APPROX. 8.0" ASPHALT CONCRETE BASE COURSE, TYPE B25.0B, AT AN AVERAGE RATE OF 456 LBS. PER SQ. YD. IN EACH OF TWO LAYERS.	w	VARIABLE DEPTH ASHPALT PAVEMENT (SEE WEDGING DETAILS)
E3	PROP. VAR. DEPTH ASPHALT CONCRETE BASE COURSE, TYPE B25.0B, AT AN AVERAGE RATE OF 114 LBS. PER SQ. YD. PER 1" DEPTH. TO BE PLACED IN LAYERS NOT LESS THAN 4.0" IN DEPTH OR GREATER THAN 5.5" IN DEPTH.		
		-	


PROJECT REFERENCE NO).	SHEET NO.						
1-0911A		2A-I						
ROADWAY DESIGN ENGINEER	P,	AVEMENT DESIGN ENGINEER						
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED								
ONELUG ALL GIGHA		J COMIN EL I ED						

€ SURVEY (D2)* 3" MIN.1 MIN.

DETAIL SHOWING METHOD OF WEDGING
FOR -Y1RPB-, -Y1RPC-, -YRPA-*, -YRPB-*, -YRPC-*, -YRPD-*, -Y1RPA-, -Y1RPB-




DETAIL SHOWING METHOD OF WEDGING





DETAIL SHOWING METHOD OF WEDGING FOR -L-


NOTE: PAVEMENT EDGE SLOPES ARE 1:1 UNLESS SHOWN OTHERWISE. FOR CROSSOVER AREAS, SEE PLANS.

PLANS PREPARED BY 900 RIDGEFIELD DRIVE SUITE 350
RALEIGH, NORTH CAROLINA 27609–3960
NC LICENSE NO. F–0112 • (919) 878–9560










USE TYPICAL SECTION NO. 4

-YRPA- STA. 10+00.00 TO STA. 14+45.00 -YRPC- STA. 10+00.00 TO STA. 20+87.06 -YSPB- STA. 10+00.00 TO STA. 11+17.00

NOTE: USE _L_ PAVEMENT TO BACK OF GORE

REVERSE LANE TYPICAL & LANE DIRECTION FOR -YSPB-

** USE 0' FOR -YSPB-



USE TYPICAL SECTION NO. 5

-YRPA- STA. 16+60.00 TO STA. 20+10.00 -YRPD- STA. 12+13.12 TO STA. 21+30.00 -Y1RPC- STA. 26+10.00 TO STA. 26+47.00

NOTES: TRANSITION FROM TYPICAL SECTIONS NO. 4 TO NO. 5 IN THE FOLLOWING LOCATIONS: -YRPA- STA. 14+35.00 TO STA. 16+60.00

TRANSITION FROM TYPICAL SECTIONS NO. 8 TO NO. 5 IN THE FOLLOWING LOCATIONS: -Y1RPC- STA. 24+60.00 TO STA. 26+10.00

REVERSE TYPICAL & LANE DIRECTION FOR -YRPD-.

USE _L_ PAVEMENT TO BACK OF GORE.


**INSIDE LANE ALONG -YRPA- IS STRIPED OUT

USE TYPICAL SECTION NO. 6 -YRPB- STA. 10+00.00 TO STA. 19+76.45

NOTE: USE -L- PAVEMENT TO BACK OF GORE.

PLANS PREPARED BY 900 RIDGEFIELD DRIVE SUITE 350 RALEIGH, NORTH CAROLINA 27609–3960 NC LICENSE NO. F-0112 • (919) 878-9560

SEE PLANS FOR LOCATION OF AUXILARY LANES, AND TAPERS. *4:1 INSIDE INTERCHANGE.




TYPICAL SECTION NO. 9

NOTES SEE PLANS FOR LOCATION OF AUXILARY LANES, AND TAPERS. *4:1 INSIDE INTERCHANGE.

GROUND

900 RIDGEFIELD DRIVE SUITE 350 RALEIGH, NORTH CAROLINA 27609–3960 NC LICENSE NO. F-0112 • (919) 878-9560

P.A	PAVEMENT SCHEDULE								
СЗ	3" S9.5B								
C5	3" S9.5C								
D1	2.5" I19.0B								
D2	3" I19.0B								
D5	3" I19.0C								
E4	3" B25.0C								
E6	VAR. B25.0C								
J1	6" ABC								
J2	8" ABC								
K1	LIME SUB. SLAB								
K2	CLASS IV STAB.								
Р	PRIME COAT								
Т	EARTH MATERIAL								
U	EXIST. PAVEMENT								
W	WEDGING								
T	EARTH MATERIAL EXIST. PAVEMENT								



DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

SHEET NO.

PROJECT REFERENCE NO.


ROADWAY DESIGN ENGINEER

<u>USE TYPICAL SECTION NO. 10</u>


-PED- STA. 12+38.43 TO STA. 13+30.63 (BEGIN BRIDGE)
-PED- STA. 15+12.96 (END BRIDGE) TO STA. 15+20.11

TYPICAL SECTION NO. 10

GUARDRAIL WIDENING DETAILS



EXPRESSWAY GUTTER DETAILS




NOTES


SEE PLANS FOR LOCATION OF AUXILARY LANES, AND TAPERS. *4:1 INSIDE INTERCHANGE.


PLANS PREPARED BY 900 RIDGEFIELD DRIVE SUITE 350
RALEIGH, NORTH CAROLINA 27609–3960
NC LICENSE NO. F–0112 • (919) 878–9560

PA	AVEMENT SCHEDULE
C2	2" S9.5B
C5	3" S9.5C
D3	4" I19.0B
D5	3" I19.0C
D6	5" I19.0C
E1	5.5" B25.0B
E4	3" B25.0C
J2	8" ABC
K2	CLASS IV STAB.
R2	CONCRETE BARRIER
R3	PRECAST BARRIER
Т	EARTH MATERIAL
U	EXIST. PAVEMENT
W	WEDGING

TEMPORARY PAVEMENT DETAILS







TYPICAL SECTION NO. 11

ROADWAY DESIGN PAVEMENT DESIGN ENGINEER

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

SHEET NO.

PROJECT REFERENCE NO.

<u>USE TYPICAL SECTION NO. 11</u>
-DET_1- STA. 14+91.38 TO STA. 17+07.26
-DET_2- STA. 16+64.34 TO STA. 19+52.62

:\Roadway\Proj\IØ911A_Rdy_typ.dgr uahl

NOTES
SEE PLANS FOR LOCATION OF AUXILARY LANES, AND TAPERS.

*4:1 INSIDE INTERCHANGE.

PLANS PREPARED BY:

RUMMEL, KLEPPER & KAHL, LLP
900 RIDGEFIELD DRIVE SUITE 350
RALEIGH, NORTH CARGUINA 27609–3960
NC LICENSE NO. F-0112 • (919) 878–9560

C5	3" S9.5C	K1	LIME SUB. STAB.	U	EXIST. PAVEMENT
D5	3" I19.0C	K2	CLASS IV STAB.	٧	MILLING
E4	3" B25.0C	R2	CONCRETE BARRIER	W	WEDGING
J2	8" ABC	Т	EARTH MATERIAL		

PROJECT REFERENCE NO. SHEET NO.
1-0911A 2A-7
ROADWAY DESIGN ENGINEER PAVEMENT DESIGN ENGINEER ENGINEER

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

SHOULDER DRAIN DETAILS

	SHOULDER DRAIN DETAILS	
	€ -L- (I-40) VARIES 17.75′ TO 30′	U
	17' 14' FDPS 0.04 12" X 12" SHOULDER DRAIN WITH #57 STONE AND 4" PERFORATED PIPE WRAPPED WITH FABRIC -L- MEDIAN SHOULDER DRAIN DETAIL -L- STA. 11+00.00 TO 23+00.00	
	Q -L- (I-40) 13' 13' D C5 E4 0.04 12" X 12" SHOULDER DRAIN WITH #57 STONE AND 4" PERFORATED PIPE WRAPPED WITH FABRIC L- STA. 23+00.00 TO 92+00.00 -L- STA. 147+30.00 TO 188+70.00 Q -L- (I-40) 12' 13' 12' R2 GRADE POINT 0.02 0.04 0.04 0.04 0.02 D5 K1) E4 J2 V S J2 E4 C5 POINT 0.02 V S J2 E4 C5 POINT 0.02 D5	1
	EXISTING LEFT LANE PAVEMENT 12" X 12" SHOULDER DRAIN WITH #57 STONE AND 4" PERFORATED PIPE WRAPPED WITH FABRIC -L- MEDIAN SHOULDER DRAIN DETAIL	
	-L- STA. 92+00.00 TO 128+06.00 -L- STA. 139+09.50 TO 147+30.00	
adway irroj ila ila inay- appagn	18' 14' 17' W/GR 12" X 12" SHOULDER DRAIN WITH #57 STONE AND 4" PERFORATED PIPE WRAPPED WITH FABRIC ONCINAL	+
ay vr rc	ORIGINAL → 6"	
Š Č	<u>-L- OUTSIDE SHOULDER DRAIN DETAIL</u>	

Line	Begin Station	End Station	Location	Outlet Station	Drainage Structure	Line	Begin Station	End Station	Location	Outlet Station	Drainage Structure	Line	Begin Station	End Station	Location	Outlet Station	Drainage Structure
				11+86.16	0401					39+75.00	0603					145+51.00	1315
				14+60.00	СР					42+75.00	СР	ì				147+69.00	1312
				16+50.00	0411					45+79.06	0620					149+17.00	1309
				19+90.00	0412]				49+17.00	0755					151+48.00	1308
				22+50.00	0414					51+95.00	0753	ĺ				154+00.00	CP
				23+43.21 0511 54+95.00 0740			157+00.00	1411									
				26+00.00	СР					58+08.57	0737	Į.				160+00.00	CP
				29+00.00	СР					61+15.09	0762					162+65.00	1401
				32+00.00	CP					64+50.51	0722	-L-	139+09.50	194+90.00	LT	165+66.00	CP
				34+85.01	0507					67+34.00	0707		133103.30	154750.00		169+00.00	1551
				37+90.00	СР					70+30.00	СР					172+00.00	1539
				40+90.00	СР					74+99.00	СР					175+40.00	1530
				43+71.18	0615				8	77+40.00	0801					178+60.00	1521
				46+70.00	СР					80+99.09	0809					181+60.00	CP
				49+70.00	СР	-L-	10+50.00	128+06.00	RT	84+00.00	СР					184+50.00	1514
				52+70.00	СР					87+00.00	СР					187+74.91	1505
				55+50.00	0745					90+00.00	СР					192+00.00	СР
				57+70.00	0743					93+00.00	CP					194+90.00	CP
				60+00.00	0742					95+41.29	0910	Į.				139+48.78	1215
				63+00.00	0726					99+00.00	СР				140+50.00	1325	
	020 200		6 LT	66+50.00	0717	4				102+39.09	1001				RT	144+00.00	CP
-L-	10+50	128+06		68+61.57	0708					105+40.00	СР	1				147+30.00	1307
				71+14.43	0709	-				108+52.09	1009	120,000				151+50.00	1303
				74+00.00	0763					111+50.00	СР					154+50.00	CP
				77+00.00	CP					115+00.00	1102					157+00.00	1409
				79+00.00	CP	0807 0821 0817				118+18.01	1112					160+00.00	1425
				81+20.00	10000000					121+50.00	1114					162+87.00	1406
				84+06.00					5	124+60.00	CP		120.00.50	104.00.00		165+12.00	1422
				87+00.00					-	127+75.91	1204	-L-	139+09.50	194+90.00	KI	167+00.00	1421
				88+96.00	0903				8	11+99.22	0403	ł				170+00.00	1535
				91+95.00	CP					16+50.00	0410	ļ				172+00.00	1534
				94+95.00	CP				8	23+48.84	0502					176+00.00	1526
				97+95.00	CP				2	28+99.00	0504					179+00.00	1517
				100+95.00	CP 1006		10+50.00	95+89.00	1450	34+85.09	0509	l.				180+50.00	CP 1E00
				102+46.00	1006 CP					39+98.50	0601					183+50.00	1509
				105+46.00						45+66.35 49+92.54	0607 0701	ř				184+50.00	1508 EV DI
				108+50.00 111+50.00	1013 CP	-L-			MED	55+15.51	0738					187+50.00 191+01.00	EX. DI
				115+00.00	1105					60+43.22	0730					194+90.00	EX. CB CP
					100000000000000000000000000000000000000				1		0730	-	120,00 50	147+30.00	MED LT EXIST	139+74.91	
				117+70.00	1116 1120				1	64+36.74 77+67.00	0804	-L- -L-	139+09.50 139+09.50	147+30.00	MED RT EXIST	139+74.91	1210 1210
				121+50.00					1			-L-	139+09.30	147+30.00	IVIED KT EXIST		_
				124+50.00	CP 1206					82+67.00 88+95.64	0813 0902					147+28.00	1305 1301
				127+65.00	-						-	4				151+50.00	
				12+13.49	0405			_		95+89.00	0913					156+65.00	1414
				15+15.00	CP CP				1	102+40.00	1004	ļ				159+50.00	1429
				18+15.00		1	05160.00	130,00,00	EV MEDIT	108+63.54	1012	-L-	147+30.00	188+70.00	MED	162+40.00	1407
9	10,50.00	120+06-00	PT	19+95.00	0407	-L-	95+89.00	128+06.00	EX. MED LT		1104	-6-	14/+30.00	100+/0.00	IVIED	166+75.00	1418
-L-	10+50.00	128+06 CO	RT	23+00.00	CP CP				1	118+86.91	1108					172+00.00	1537
				26+00.00	EX. DI	_				121+51.00	1118					175+61.00	1529
				32+00.00	CP	,	120,00 50	104,00.00	17	139+48.36	1213					178+80.00	1520
				34+97.00	CP CP	-L-	139+09.50	194+90.00	LT	141+00.00	1323					183+00.00	1511
	Š.			37+00.00	LP					144+55.00	1317				1	STROKE THE TROOPS	mm.gA325

NOTE: (CP) CONCRETE PAD OUTLET



2/19/2018 R:\Roadwau\Pro |\I0911A_Rdu_tup 862D03 STATE OF

NORTH CAROLINA
DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
RALEIGH, N.C. STATE OF

NORTH CAROLINA
DIVISION OF HIGHWAYS
RALEIGH, N.C. 862D03 GUARDRAIL ANCHOR UNIT TYPE B-77 FOR PARRIER FOR F-SHAPE BARRIER GUARDRAIL ANCHOR UNIT TYPE B-77 GUARDRAIL ANCHOR UNIT STRUCTURE ANCHOR UNIT ENGLISH DETAIL DRAWING FOR ENGLISH DETAIL DRAWING FOR SECTION DETAIL C RUBRAIL BLOCKOUT DETAIL A x 8.2 RUBRAIL ELEVATION SECTION GUARDRAIL ANCHOR UNIT ELEVATION ANCHOR UNIT RUBRAIL OFFSET BLOCK SEE DETIAL C AND NOTE 2 PLAN SLOPED RUBRAIL SECTION TYPE HOLE B B-77 BLOCKOUT DETAIL B PLATE RUBRAIL 13 X 7'-6" CONTRACT STANDARDS AND DEVELOPMENT UNIT Office 919-707-6950 FAX 919-250-4119 STATE OF NORTH CAROLINA DEPT. OF TRANSPORTATION DIVISION OF HIGHWAYS RALEIGH, N.C. 862D03 ENGLISH DETAIL DRAWING FOR ENGLISH DETAIL DRAWING FOR STATE OF NORTH CAROLINA 862D03 SEE TITLE BLOCK STRUCTURE ANCHOR UNIT STRUCTURE ANCHOR UNIT DEPT. OF TRANSPORTATION DIVISION OF HIGHWAYS GUARDRAIL ANCHOR UNIT TYPE B-77 GUARDRAIL ANCHOR UNIT TYPE B-77 FOR F-SHAPE BARRIER RALEIGH, N.C. FOR F-SHAPE BARRIER


DATE: 06-22-12 DATE: DATE: ORIGINAL BY: J HOWERTON
MODIFIED BY:
CHECKED BY:
FILE SPEC.:

PROJECT REFERENCE NO.

SHEET NO.


yes of Liner = Closs B Ng Nop

-L STA, 34+00 TO STA, 35+50 LT
-L STA, 39+00 TO STA, 39+60 LT
-L STA, 48+50 TO STA, 49+17 LT
-L STA, 48+50 TO STA, 49+17 LT
-L STA, 69+50 TO STA, 74+00 LT
-L STA, 80+50 TO STA, 84+50 LT
-L STA, 80+50 TO STA, 84+50 LT; 2 BERM
-L STA, 80+50 TO STA, 84+60 LT; 2 BERM
-L STA, 80+50 TO STA, 84+60 LT; 2 BERM
-L STA, 80+50 TO STA, 84+60 LT; 2 SERM
-L STA, 80+50 TO STA, 85+50 RT
-YRPA-STA, 11+00 TO STA, 15+70 RT
-YRPA-STA, 11+00 TO STA, 15+70 RT
-YRPD-STA, 13+18 TO STA, 14+24 LT






-L- STA. 10+46 TO STA. 11+00 RT
-L- STA. 10+48 TO STA. 11+00 LT
-L- STA. 41+00 TO STA. 43+50 LT
-L- STA. 43+50 LT
-L- STA. 45+50 TO STA. 49+50 RT
-L- STA. 45+50 TO STA. 59+00 RT
-L- STA. 61+00 TO STA. 59+00 RT
-L- STA. 61+00 TO STA. 59+50 LT
-L- STA. 134-50 TO STA. 153+55 LT
-L- STA. 156+00 TO STA. 153+55 RT
-L- STA. 156+50 TO STA. 153+55 RT
-L- STA. 156+00 TO STA. 159+50 RT
-L- STA. 157+00 TO STA. 159-50 RT
-L- STA. 157+00 TO STA. 159-50 RT
-TIRPA- STA. 15+38 TO STA. 178+50 RT
-TIRPA- STA. 14+21 TO STA. 17+50 LT
-YIRPB- STA. 14+21 TO STA. 17+50 LT




-YRPB- STA. 14+04 TO STA. 17+50 LT -YRPB- STA. 17+50 TO STA. 18+00 LT; CLASS I -YRPC- STA. 10+16 TO STA. 16+80 RT; VARYING V.C.




-L- STA. 38+00 TO STA. 39+74 RT
-L- STA. 45+79 TO STA. 46+50 RT
-L- STA. 55+50 TO STA. 57+50 LT
-L- STA. 60+00 TO STA. 57+50 LT
-L- STA. 87+28 TO STA. 90+00 RT
-L- STA. 127+09 TO STA. 129+916 RT; 3:1 SLOPES
-L- STA. 128+46 TO STA. 128+97 LT; 3:1 SLOPES
-L- STA. 138+67 TO STA. 140+50 LT
-L- STA. 141+50 TO STA. 143+00 LT
-L- STA. 143+50 TO STA. 144+55 LT
-YKRP-STA. 18+90 TO STA. 242+50 RT




d= 2.0 Ft. Type of Liner = Class B Rip-Rap -L- STA. 68+33 TO STA. 71+28 LT -L- STA. 140+50 TO STA. 141+50 LT -L- STA. 148+00 TO STA. 149+50 LT; KEEP OUT OF WETLAND -YRPD- STA. 10+77 TO STA. 13+06 LT





-L- STA. 145+50 TO STA. 148+00 LT -YRPB- STA. 17+50 TO STA. 19+00 LT -YRPB- STA. 19+50 TO STA. 20+78 LT -YIRPD- STA. 17+00 TO STA. 19+00 RT





SHEET NO.


PROJECT REFERENCE NO.


DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED






















NOTE B


€ SECTION


DISSIPATOR POOL

HALF PLAN

BERNY TO A SAN TO A S


RIP-RAPPED ENERGY DISSIPATOR BASIN *NOTE A: IF EXIT VELOCITY OF BASIN IS SPECIFIED, EXTEND BASIN AS REQUIRED TO OBTAIN SUFFICIENT CROSS SECTIONAL AREA AT SECTION A-A SUCH THAT Q dos/CROSS SECTION AREA AT SEC. A-J9 = SPECIFIED VELOCITY.









Natura Ground








-tc →/B →/A DIAMETER OF PIPE, WIDTH OF BOX OR SPAN OF PIPE–ARCH CULVERTS SEC. D-D *ALL DIMENSIONS APPROXIMATE IN FT 5/05


PLANS PREPARED BY RUMMEL, KLEPPER & KAHL, LLP 900 RIDGEFIELD DRIVE SUITE 350 RALEIGH, NORTH CAROLINA 27609-3960 NC LICENSE NO. F-0112 • (919) 878-9560



































PLANS PREPARED BY:

RUMMEL, KLEPPER & KAHL, LLP
900 RIDGEFIELD DRIVE SUITE 350
RALEIGH, NORTH CAROLINA 27609–3960
NC LICENSE NO. F-0112 • (919) 878–9560

(19/20j8

FOR _L_ PROFILE SEE SHT. 27