



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

MICHAEL F. EASLEY
GOVERNOR

LYNDO TIPPETT
SECRETARY

May 9, 2006

U. S. Army Corps of Engineers
Regulatory Field Office
151 Patton Avenue, Room 208
Asheville, NC 28801-5006

ATTN.: Mr. Steve Lund
NCDOT Coordinator

Subject: **RE-APPLICATION for Individual Section 404 and 401 permits for TIP R-2616** for the proposed widening of US 601 from the South Carolina State Line to north of Marion Lee Road (SR 2105) south of Monroe in Union County; NCDOT Division 10. Federal Project No. STP-NHS-601(4), State Project No. 8.1690303, WBS Element 34485.1.1.

Dear Sir:

Due to additional concerns noted by the North Carolina Division of Water Quality in a Return of Application letter dated March 17, 2006, changes to the jurisdictional impacts for this project were necessary. These changes include the addition of sites that attained jurisdictional status since the original 2002 verification, and a pipe realignment request, both of which are addressed below. This application replaces the original and subsequent applications dated July 21, 2005, October 7, 2005, and February 16, 2006.

The NCDOT proposes to widen US 601 from the South Carolina State Line to north of Marion Lee Road (SR 2105). The proposed project will consist of widening the existing two lane facility to a four lane grassed median facility. The total length is approximately 10.8 miles and will require approximately 200 feet of right of way. This application package consists of the cover letter, ENG Form 4345, permit (hydraulic) drawings, half size roadway plan sheets, and EEP Mitigation Acceptance Letter.

Purpose and Need: As identified in the reevaluation of the EA, the primary purpose of this action is to improve highway safety on US 601, a two-lane, undivided facility situation in rolling terrain with associate poor stopping sight distances. This section of US 601 has a history of severe crashes and a Fatal Crash Rate significantly higher than the statewide average.

The secondary purpose of this action is to increase the capacity of the facility.

Summary of Impacts: Impacts on jurisdictional areas of the proposed project consist of a total of 0.353 acre of permanent wetland impacts, 3.202 linear feet of permanent stream impact, 910 linear feet of temporary stream impact, and 3.47 acres of permanent surface water (pond) impact.

Summary of Mitigation: The project has been designed to avoid and minimize impacts to jurisdictional areas throughout the NEPA and design processes. Compensatory mitigation for jurisdictional streams and wetlands will be provided by the North Carolina Ecosystem Enhancement Program.

NEPA DOCUMENT STATUS

The United States Department of Transportation Federal Highway Administration (FHWA) and the North Carolina Department of Transportation (NCDOT) approve the previous administrative actions of this project including the *Environmental Assessment (EA)* on May 24, 1994 and the *Finding of No Significant Impact (FONSI)* on September 29, 1994. Section 129 (Reevaluations) of Part 771 (Environmental Impact and Related Procedures) of Title 23 (Highway) of the *Code of Federal Regulations* requires that NCDOT consult with FHWA to determine whether the approved environmental documents remain valid. FHWA and NCDOT concluded that a Reevaluation should be conducted due to the elapsed time since the *FONSI* and need for updated impacts to the human and natural environment. Copies of the EA and FONSI have been provided to regulatory review agencies involved in the approval process. Additional copies will be provided upon request.

MERGER PROCESS SUMMARY

Purpose and Need (Concurrence Point 1, signed 3/31/2003): “The primary purpose of this action is to improve highway safety on US 601. The secondary purpose is to increase the capacity of the facility.”

Alternatives (Concurrence Point 2, signed 3/31/2003):

- 1) No-build / routine maintenance continues
- 2) Asymmetrical widening to a 4-lane, median divided, shoulder-section facility

Bridging Decisions (Concurrence Point 2A, signed 3/16/2004): “The Team concurs with the proposed box culvert and bridging decisions for the five major crossings on US 601 as presented during this meeting.”

Least Environmentally Damaging Practicable Alternative – LEDPA (Concurrence Point 3, signed 3/16/2004): “The LEDPA is an asymmetrical, best-fit widening of US 601 to a 4-lane, median divided, shoulder-section facility.”

Avoidance and Minimization (Concurrence Point 4A signed 1/25/2005): “The Merger Process Team concurred that the jurisdictional impacts have been avoided and minimized

to the maximum extent practicable based on current information and design available at this time.”

The context of this project with respect to the remaining concurrence points was discussed at the January 25, 2005 meeting. The Merger Process Team agreed to skip Concurrence Point 4B (30 % Hydraulic Design Review) and address Concurrence Point 4C (Permit Drawings Review) at the next concurrence meeting.

100% Hydraulic Design/ Permit Drawings Review (Concurrence Point 4C): Concurrence was reached on March 16, 2005.

INDEPENDENT UTILITY

The subject project is in compliance with 23 CFR Part 771.111(f) which lists the Federal Highway Administration (FHWA) characteristics of independent utility of a project:

- (1) The project connects logical termini and is of sufficient length to address environmental matters on a broad scope,
- (2) The project is usable and a reasonable expenditure, even if no additional transportation improvements are made in the area;
- (3) The project does not restrict consideration of alternatives for other reasonably foreseeable transportation improvements.

RESOURCE STATUS

Wetland delineations: Potential wetland communities were investigated pursuant to the 1987 Corps of Engineers Wetland Delineation Manual. Mr. Steve Lund of the U.S. Army Corps of Engineers verified the wetlands and surface waters on December 17, 2002 and March 7, 2006. Each impact is described in detail below. Site and station numbers correspond with the permit (hydraulic) drawings included in this application. Sites with the letter “A” after the site number indicate this site was added after the March 7, 2006 verification.

Impacts to Waters of the United States

Site 1A (L 24+12)

A jurisdictional stream and wetland were identified by the NCDWQ and ACE on March 7, 2006. Project construction will result in 0.036 acre of permanent impact to wetlands and 104 feet of permanent impacts to streams. There will also be 10 feet of temporary impacts to surface waters for this site.

Site 1 (L 102+00 to 106+05)

A 5’x 3’ concrete barrel culvert, carrying an unnamed tributary to Mill Creek (J-15), will be replaced with two 54” reinforced concrete pipes. This proposed activity will result in 223’ of permanent stream impact and 75’ of temporary stream impacts.

Site 2 (L 119+35)

A 3'x 7' triple barrel culvert, carrying Mill Creek (J-14), will be replaced with a 3'x 10' triple barrel culvert. One of the barrels will be silled to allow for natural stream dimensions to continue through the structure. This proposed activity will result in 166' of permanent stream impact and 40' of temporary stream impacts.

Site 3 (L 129+70)

A 8'x 13' sextuple barrel culvert, carrying Lanes Creek (J-13), will be replaced with two 130' bridges (2 spans @ 65'). This proposed activity will result in 150' of temporary stream impacts to construct the bridge. NCDOT subtracted 39 linear feet of permanent stream impact from the total permanent stream impact for the project for removing the box culvert.

Site 4 (L 145+40)

A 21" pipe, carrying an unnamed tributary to Lanes Creek (J-12), will be replaced with a 42" reinforced concrete pipe. This proposed activity will result in 48' of permanent stream impact and 10' of temporary stream impacts.

Site 5 (180+30 RT)

A 24" concrete pipe, carrying an unnamed tributary to Gum Log Branch (J-11), will be replaced with a 48" reinforced concrete pipe. This proposed activity will result in 240' of permanent stream impact and 47' of temporary stream impacts. This system has been realigned per the request of the North Carolina Division of Water Quality in a letter dated March 17, 2006. Due to this realignment, permanent stream impacts have increased from 140' to 240' and temporary impacts have increased from 11' to 47'.

Site 6 (180+30 LT)

The proposed replacement of the 24" pipe from Site 5 will result in 0.009 acre of permanent wetland impact.

Site 7 (L 180+30 to 183+00)

Due to the encroachment of the expanded road, 215' of an unnamed tributary to Gum Log Branch (J-10) will be permanently impacted. There will be 10 feet of stream temporarily impacted to create a diversion.

Site 8A (L 206+00)

A jurisdictional stream and wetland were identified by the NCDWQ and ACE on March 7, 2006. Project construction at this location will result in 150 feet of permanent stream impact and 10 feet of temporary stream impact. The wetland located at this site is outside of the project area.

Site 8 (L 215+70)

A 24" concrete pipe will be replaced with a new 24" reinforced concrete pipe. This proposed activity will result in 0.009 acre of wetland impact.

Site 9 (L 221+70 LT)

Due to the encroachment of the expanded roadway, 0.83 acre of surface water (pond) will be drained.

Site 10 (L 231+20)

A double 4' concrete box culvert, carrying an unnamed tributary to Wicker Branch (J-9) will be replaced with a 54" reinforced concrete pipe. This proposed activity will result in 170' of permanent stream impact and 22' of temporary stream impacts. An additional wetland was located at this site by the NCDWQ and ACE on March 7, 2006. Project construction at this location will result in 0.047 acre of permanent wetland impact.

Site 11 (L 242+35)

A 5' double barrel culvert, carrying an unnamed tributary to Wicker Branch (J-8), will be replaced with a 66" reinforced concrete pipe. This proposed activity will result in 161' of permanent stream impact and 20' of temporary stream impacts.

Site 12 (L 248+30 to 250+09)

A 3'x 3' concrete culvert, carrying an unnamed tributary to Wicker Branch (J-7), will be replaced with a 48" reinforced concrete pipe. This proposed activity will result in 290' of permanent stream impact and 22' of temporary stream impacts.

Site 13 (L 281+51)

A double 8'x 7' concrete box culvert, carrying an unnamed tributary to Wicker Branch (J-6), will be replaced with a single 12'x 10' reinforced concrete box culvert. This proposed activity will result in 128' of permanent stream impact and 40' of temporary stream impacts.

Site 14 (L 288+06.5)

A double 8'x 6' concrete box culvert, carrying an unnamed tributary to Cowpens Branch (J-5), will be replaced with a double barrel 8'x 7' reinforced concrete box culvert. One of the barrels will be silled to allow for natural stream dimensions to continue through the structure. This proposed activity will result in 124' of permanent stream impact and 62' of temporary stream impacts.

Site 15 (L 290+00 to 294+30)

A 30" concrete pipe, carrying an unnamed tributary to Cowpens Branch (J-4), will be replaced with two 30" reinforced concrete pipes. Also, due to the road expansion parallel to the stream, these activities will result in 466' of permanent stream impact and 62' of temporary stream impacts.

Site 16 (L 315+56)

A 40 foot long double (2'x 7') concrete box culvert, carrying Wicker Branch (J-3), will be replaced with a single 16' x 8' bottomless structure. This activity will result in 25' of permanent stream impact. (Permanent stream impacts are necessary due to the difference between the existing stream location and the new channel in the bottomless structure.) There will be 240' of temporary stream impact to accommodate construction of the new structure. (NCDOT has subtracted 40 feet of permanent stream impact from the total amount of permanent stream impacts.)

Site 17 (L 342+00 LT)

Due to the encroachment of the expanded roadway, 0.31 acre of surface water (pond) will be drained.

Site 18 (L 349+50 RT)

Due to the installation of a 30" reinforced concrete pipe and encroachment of the widened facility, 0.04 acre of wetland will be permanently impacted, and 0.08 acre of surface water (pond) will be permanently impacted.

Site 19 (L 349+50 LT)

Due to the encroachment of the expanded roadway, 0.47 acre of surface water (pond) will be drained. This drainage will result in the dewatering of a fringe wetland to the pond. Therefore, this impact will also result in 0.04 acre of permanent wetland impact.

Site 20 (L 400+00 RT)

Due to the encroachment of the expanded roadway, 0.58 acre of surface water (pond) will be drained.

Site 21 (L 422+00 RT)

Due to the encroachment of the expanded roadway, 0.45 acre of surface water (pond) will be drained.

Site 22 (L 426+03 to 430+50)

A 54" reinforced concrete pipe will be installed carrying an unnamed tributary to Buck Branch resulting in 460' of permanent stream impact and 30' of temporary stream impact.

Site 23 (L 474+07 to 476+41)

A 24" pipe will be replaced with a new 24" reinforced concrete pipe, resulting in 0.115 acre of permanent wetland impact.

Site 23A (L 495+00)

A jurisdictional stream and wetland were identified by the NCDWQ and ACE on March 7, 2006. Project construction at this location will result in 160' of permanent stream impact and 30' of temporary stream impact.

Site 24 (L 534+20)

A 24" reinforced concrete pipe, carrying an unnamed tributary to Buck Branch, will be replaced with a 48" reinforced concrete pipe. This proposed activity will result in 151' of permanent stream impact and 30' of temporary stream impacts.

Site 25 (L 549+60)

A 24" pipe will be replaced with a 36" reinforced concrete pipe. Due to the proximity of a water supply watershed, a hazardous spill retention basin will be constructed at the outlet of this pipe. These activities will result in 0.057 acre of wetland impact.

Site 26 (L 575+85)

A 24" reinforced concrete pipe will be extended, resulting in 0.290 acre of surface water (pond) impact.

PROTECTED SPECIES

Plants and animals with Federal classification of Endangered (E) or Threatened (T) are protected under provisions of Section 7 and Section 9 of the Endangered Species Act of 1973, as amended. As of January 29, 2003, the U.S. Fish and Wildlife Service (FWS) lists two federally protected species for Union County (Table 1). Concurrence has been received from the USFWS in a letter dated April 1, 2004 stating, "Given the information provided, we agree that there will be no effect to federally listed species for the subject project."

†On March 6, 2007, the USFWS has added Michaux's Sumac (*Rhus michauxii*) to the list of Federally Protected Species to Union County. A subsequent survey was conducted on April 13, 2006 by NCDOT biologists Michael Turchy, Tyler Stanton, John Merritt, and Kris Dramby. A reference population was located on in Marston, Richmond County, NC, before the project surveys were conducted. R-2616 contains several fragmented areas with potential habitat for the species. A 12 person- hour survey was conducted and no populations of Michaux's sumac were located, resulting in a biological conclusion of No Effect.

Table 1. Federally Protected Species for Union County

Common Name	Scientific Name	Status	Biological Conclusion
Schweinitz's sunflower	<i>Helianthus schweinitzii</i>	Endangered	No Effect
Carolina heelsplitter	<i>Lasmigona decorata</i>	Endangered	No Effect
†Michaux's Sumac	<i>Rhus michauxii</i>	Endangered	No Effect

Endangered - A taxon "in danger of extinction throughout all or a significant portion of its range."

INDIRECT CUMULATIVE IMPACT ANALYSIS

Existing rules for the 401 Water Quality Certification Program (15A NCAC 2H .0506(b)(4) require that the DWQ determine that a project "does not result in cumulative impacts, based on past or reasonably anticipated future impacts, that cause or will cause a violation of downstream water quality standards."

An Indirect and Cumulative Effects Report (ICE) was completed for this project in 2003. Because of the rural location, and lack of other infrastructure facilities, indirect and secondary impacts attributed to this project are expected to be minimal. Copies of this report are available upon request.

There are no impaired (303d) streams in the project area.

CULTURAL RESOURCES

Archaeology & Historical Structures: Archaeological resource survey work was conducted to determine if significant archaeological resources might be disturbed. In a letter dated April 3, 1992, eleven recorded archaeological sites were studied and were all determined to be not eligible for the National Register by NCDOT archaeologists with

concurrence from the SHPO. This document is found in Appendix D in the Reevaluation EA.

In a letter dated January 17, 2003, also found in the Appendix D section of the Reevaluation EA, SHPO commented that “We have conducted a review of the proposed undertaking and are aware of no historic resources which would be affected by the project.”

FEMA COMPLIANCE

Union County is currently a participant in the National Flood Insurance Regular Program. The crossing of Mill Creek, Lanes Creek, Cowpens Branch and Wicker Branch are located in designated flood hazard zones.

WILD AND SCENIC RIVER SYSTEM

The project will not impact any designated Wild and Scenic Rivers or any rivers included in the list of study rivers (Public Law 90-542, as amended).

MITIGATION OPTIONS

The Corps of Engineers has adopted, through the Council on Environmental Quality (CEQ), a wetland mitigation policy that embraces the concept of “no net loss of wetlands” and sequencing. The purpose of this policy is to restore and maintain the chemical, biological, and physical integrity of the Waters of the United States. Mitigation of wetland and surface water impacts has been defined by the CEQ to include: avoiding impacts, minimizing impacts, rectifying impacts, reducing impacts over time and compensating for impacts (40 CFR 1508.20). Executive Order 11990 (Protection of Wetlands) and Department of Transportation Order 5660.1A (Preservation of the Nations Wetlands), emphasize protection of the functions and values provided by wetlands. These directives require that new construction in wetlands be avoided as much as possible and that all-practicable measures are taken to minimize or mitigate impacts to wetlands.

Avoidance and Minimization: This project has been designed using asymmetrical widening. Using this method, the department has avoided impacting many wetlands and reduced impacts to wetlands to the greatest extent practicable. Other specific examples of avoidance and minimization measures include:

- The removal of a culvert carrying Lanes Creek and replacing the structure with two 130’ bridges.
- The installation of a bottomless culvert at Wicker Branch.
- The removal and replacement of all perched culverts. These structures will be buried a minimum of 1 foot to accommodate the passage of aquatic organisms.

- When applicable, multiple barrel culverts will be silled to continue the natural stream dimensions throughout the culvert structure, but can also accommodate larger flow during storm events.
- Fill slopes in jurisdictional areas have been designed at a 2:1 slope.

Compensation: The primary emphasis of the compensatory mitigation is to reestablish a condition that would have existed if the project were not built. As previously stated, mitigation is limited to reasonable expenditures and practicable considerations related to highway operation. Mitigation is generally accomplished through a combination of methods designed to replace wetland functions and values lost as a result of construction of the project. These methods consist of creation of new wetlands from uplands, borrow pits, and other non-wetland areas; restoration of wetlands; and enhancement of existing wetlands. Where such options may not be available, or when existing wetlands and wetland-surface water complexes are considered to be important resources worthy of preservation, consideration is given to preservation as at least one component of a compensatory mitigation proposal.

FHWA Step Down Compliance

All compensatory mitigation must be in compliance with 23 CFR Part 777.9, "Mitigation of Impacts" that describes the actions that should be followed to qualify for Federal-aid highway funding. This process is known as the FHWA "Step Down" procedures:

1. Consideration must be given to mitigation within the right-of-way and should include the enhancement of existing wetlands and the creation of new wetlands in the highway median, borrow pit areas, interchange areas and along the roadside.
2. Where mitigation within the right-of-way does not fully offset wetland losses, compensatory mitigation may be conducted outside the right-of-way including enhancement, creation, and preservation.

Based upon the agreements stipulated in the "Memorandum of Agreement Among the North Carolina Department of Environment and Natural Resources, the North Carolina Department of Transportation, and the U.S. Army Corps of Engineers, Wilmington District" (MOA), it is understood that the North Carolina Department of Environment and Natural Resources Ecosystem Enhancement Program (EEP), will assume responsibility for satisfying the federal Clean Water Act compensatory mitigation requirements for NCDOT projects. The offsetting mitigation will derive from an inventory of assets already in existence within the same 8-digit cataloguing unit. The Department has avoided and minimized impacts to jurisdictional resources to the greatest extent possible as described above. The remaining, unavoidable impacts will be offset by compensatory mitigation provided by the EEP program. A copy of this acceptance by the EEP is included in this application package.


REGULATORY APPROVALS

Application is hereby made for a Department of the Army for a Section 404 Individual Permit and a Section 401 Water Quality Certification for the above described activities. In compliance with Section 143-215.3D(e) of the NCAC we will provide \$475.00 to act as payment for processing the Section 401 permit application previously noted in this application (see Subject line). We are providing five copies of this application to the North Carolina Department of Environment and Natural Resources, Division of Water Quality.

We also anticipate that comments from the North Carolina Wildlife Resources Commission (NCWRC) will be required prior to authorization by the Corps of Engineers. By copy of this letter and attachment, NCDOT hereby requests NCWRC review. NCDOT requests that NCWRC forward their comments to the Corps of Engineers.

Thank you for your assistance with this project. If you have any questions or need additional information, please contact Mr. Michael Turchy at maturchy@dot.state.nc.us or (919) 715-1468. A copy of this application will also be posted at <http://www.ncdot.org/planning/pe/naturalunit/Permit.html>.

Sincerely,



Gregory J. Thorpe, Ph.D., Environmental Management Director
Project Development and Environmental Analysis Branch

Cc list:

W/attachment

Mr. John Hennessy, NCDWQ (5 Copies)
Ms. Marella Buncick, USFWS
Ms. Marla Chambers, NCWRC
Ms. Becky Fox, USEPA – Whittier, NC
Mr. Ronald Mikulak, USEPA – Atlanta, GA
Mr. Clarence W. Coleman, P.E., FHWA
Dr. David Chang, P.E., Hydraulics
Mr. Greg Perfetti, P.E., Structure Design
Mr. Mark Staley, Roadside Environmental
Mr. Barry Moose, P.E., Division Engineer, Div 10
Mr. Larry Thompson, DEO, Division 10

W/o attachment

Mr. Jay Bennett, P.E., Roadway Design
Mr. Majed Alghandour, P. E., Programming and TIP
Mr. Art McMillan, P.E., Highway Design
Mr. Scott McLendon, USACE, Wilmington
Ms. Beth Harmon, EEP
Mr. Todd Jones, NCDOT External Audit Branch
Mr. Carl Goode, PE, Human Environment Unit Head
Mr. Mark Pierce, P.E., PDEA Project Planning Eng

**APPLICATION FOR DEPARTMENT OF THE ARMY PERMIT
(33 CFR 325)**

**OMB APPROVAL NO. 0710-003
Expires December 31, 2004**

Public reporting burden for this collection of information is estimated to average 10 hours per response, although the majority of applications should require 5 hours or less. This includes the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden, to Department of Defense, Washington Headquarters Service Directorate of Information Operations and Reports, 1215 Jefferson Davis Highway, Suite 1204, Arlington, VA 22202-4302; and to the Office of Management and Budget, Paperwork Reduction Project (0710-0003), Washington, DC 20503. Respondents should be aware that notwithstanding any other provision of law, no person shall be subject to any penalty for failing to comply with a collection of information if it does not display a currently valid OMB control number. Please **DO NOT RETURN** your form to either of those addresses. Completed applications must be submitted to the District Engineer having jurisdiction over the location of the proposed activity.

PRIVACY ACT STATEMENT

Authority: Rivers and Harbors Act, Section 10, 33 USC 403; Clean Water Act, Section 404, 33 USC 1344; Marine Protection, Research and Sanctuaries Act, 33 USC 1413, Section 103. Principal Purpose: Information provided on this form will be used in evaluating the application for a permit. Routine Uses: This information may be shared with the Department of Justice and other federal, state, and local government agencies. Submission of requested information is voluntary, however, if information is not provided the permit application cannot be evaluated nor can a permit be issued.

One set of original drawings or good reproducible copies which show the location and character of the proposed activity must be attached to this application (see sample drawings and instructions) and be submitted to the District Engineer having jurisdiction over the location of the proposed activity. An application that is not completed in full will be returned.

(ITEMS 1 THRU 4 TO BE FILLED BY THE CORPS)

1. APPLICATION NO.	2. FIELD OFFICE CODE	3. DATE RECEIVED	4. DATE APPLICATION COMPLETED
--------------------	----------------------	------------------	-------------------------------

(ITEMS BELOW TO BE FILLED BY APPLICANT)

5. APPLICANT'S NAME North Carolina Department of Transportation Project Development & Environmental Analysis	8. AUTHORIZED AGENT'S NAME AND TITLE (an agent is not required)
6. APPLICANT'S ADDRESS 1548 Mail Service Center Raleigh, NC 27699-1548	9. AGENT'S ADDRESS
7. APPLICANT'S PHONE NOS. W/AREA CODE a. Residence b. Business 919-733-3141	10. AGENT'S PHONE NOS. W/AREA CODE a. Residence b. Business

11. STATEMENT OF AUTHORIZATION

I hereby authorize, _____ to act in my behalf as my agent in the processing of this application and to furnish, upon request, supplemental information in support of this permit application.

APPLICANT'S SIGNATURE

DATE

NAME, LOCATION, AND DESCRIPTION OR PROJECT OR ACTIVITY

12. PROJECT NAME OR TITLE (see instructions) R-2616	14. PROJECT STREET ADDRESS (if applicable)
13. NAME OF WATERBODY, IF KNOWN (if applicable) Buck Branch, Wicker Branch, Cowpens Branch, Gum Log Branch, Lanes Creek, and several Unnamed tributaries systems to the aforementioned streams.	
15. LOCATION OF PROJECT Union NC COUNTY STATE	

16. OTHER LOCATION DESCRIPTIONS, IF KNOWN (see instructions) Section, Township, Range, Lat/Lon, and/or Accessors's Parcel Number, for example.

17. DIRECTIONS TO THE SITE

Please see attached vicinity map and cover letter.

18. **Nature of Activity** (Description of project, include all features)

Widening a current US 601 from a two lane, to a 4 lane undivided facility on existing location using asymmetrical widening.

19. **Project Purpose** (Describe the reason or purpose of the project, see instructions)

To increase safety and capacity of US 601.

USE BLOCKS 20-22 IF DREDGED AND/OR FILL MATERIAL IS TO BE DISCHARGED

20. **Reason(s) for Discharge**

Impacts will result from widening the shoulders, raising the grade of the highway, and lengthening/ replacing hydraulic structures.

21. **Type(s) of Material Being Discharged and the Amount of Each Type in Cubic Yards**

See attached cover letter.

22. **Surface Area in Acres of Wetlands or Other Waters Filled** (see instructions)

See attached cover letter.

23. **Is Any Portion of the Work Already Complete?** Yes ___ No X IF YES, DESCRIBE THE COMPLETED WORK

24. **Addresses of Adjoining Property Owners, Lessees, Etc., Whose Property Adjoins the Waterbody** (If more than can be entered here, please attach a supplemental list).

Please see adjacent property landowners page attached to the permit drawing package.

25. **List of Other Certifications or Approvals/Denials Received from other Federal, State, or Local Agencies for Work Described in This Application.**

AGENCY	TYPE APPROVAL*	IDENTIFICATION NUMBER	DATE APPLIED	DATE APPROVED	DATE DENIED
--------	----------------	-----------------------	--------------	---------------	-------------

N/A

* Would include but is not restricted to zoning, building, and flood plain permits

26. Application is hereby made for a permit or permits to authorize the work described in this application. I certify that the information in this application is complete and accurate. I further certify that I possess the authority to undertake the work described herein or am acting as the duly authorized agent of the applicant.

SIGNATURE OF APPLICANT

DATE

SIGNATURE OF AGENT

DATE

The application must be signed by the person who desires to undertake the proposed activity (applicant) or it may be signed by a duly authorized agent if the statement in block 11 has been filled out and signed.

18 U.S.C. Section 1001 provides that: Whoever, in any manner within the jurisdiction of any department or agency of the United States knowingly and willfully falsifies, conceals, or covers up any trick, scheme, or disguises a material fact or makes any false, fictitious or fraudulent statements or representations or makes or uses any false writing or document knowing same to contain any false, fictitious or fraudulent statements or entry, shall be fined not more than \$10,000 or imprisoned not more than five years or both.



April 11, 2006

Mr. Gregory J. Thorpe, Ph.D.
Environmental Management Director
Project Development and Environmental Analysis Branch
North Carolina Department of Transportation
1548 Mail Service Center
Raleigh, North Carolina 27699-1548

Dear Dr. Thorpe:

Subject: EEP Mitigation Acceptance Letter:

R-2616, US 601 Widening, Union County

The purpose of this letter is to notify you that the Ecosystem Enhancement Program (EEP) will provide the riverine wetland, non-riverine wetland, and stream mitigation for the subject project. Based on the information supplied by you in a letter dated April 7, 2006, the impacts are located in CU 03040105 of the Yadkin River Basin in the Southern Piedmont (SP) Eco-Region, and are as follows:

Riverine Wetland Impacts:	0.158 acre
Non-Riverine Wetland Impacts:	0.195 acre
Stream Impacts:	3,202 feet

This mitigation acceptance letter replaces the mitigation acceptance letters issued on July 19, 2005 and January 31, 2006. Compensatory wetland and stream mitigation for this project will be provided in accordance with the Memorandum of Agreement between the North Carolina Department of Environment and Natural Resources, the North Carolina Department of Transportation, and the U. S. Army Corps of Engineers, signed on July 22, 2003 (Tri-Party MOA). EEP commits to implementing sufficient compensatory wetland and stream mitigation to offset the impacts with this project as previously listed by the end of the MOA Year in which this project is permitted, in accordance with Section X of the Tri-Party MOA. If the above referenced impact amounts are revised, then this mitigation acceptance letter will no longer be valid and a new mitigation acceptance letter will be required from EEP.

Restoring... Enhancing... Protecting Our State


North Carolina Ecosystem Enhancement Program, 1652 Mail Service Center, Raleigh, NC 27699-1652 / 919-715-0476 / www.nceep.net



Dr. Thorpe
R-2616 Mitigation Acceptance
Page Two

If you have any questions or need additional information, please contact Ms. Beth Harmon at 919-715-1929.

Sincerely,

A handwritten signature in black ink, appearing to read "James B. Gilmore, Jr.", written over the printed name.

William D. Gilmore, P.E.
EEP Director

cc: Mr. Steve Lund, USACE-Asheville
Mr. John Hennessy, Division of Water Quality, Wetlands/401 Unit
File: R-2616 Revised-2



April 20, 2006

Mr. Steve Lund
U. S. Army Corps of Engineers
Asheville Regulatory Field Office
151 Patton Avenue, Room 208
Asheville, North Carolina 28801-5006

Dear Mr. Lund:

Subject: EEP Mitigation Acceptance Letter:

R-2616, US 601 Widening, Union County from the South Carolina State Line to North of SR 2105 (Marion Lee Road); Yadkin River Basin (CU 03040105); Southern Piedmont (SP) Eco-Region

The purpose of this letter is to notify you that the Ecosystem Enhancement Program (EEP) will provide mitigation for the unavoidable impacts associated with the above referenced project. The impacts as reported by the NCDOT in their April 7, 2006 mitigation request are as follows:

Riverine Wetland Impacts:	0.158 acre
Non-Riverine Wetland Impacts:	0.195 acre
Stream Impacts:	3,202 feet

This mitigation strategy letter replaces the mitigation strategy letters issued on July 19, 2005 and January 31, 2006. Mitigation for this project will be provided in accordance with Section X of the Memorandum of Agreement between the N. C. Department of Environment and Natural Resources, the N. C. Department of Transportation, and the U. S. Army Corps of Engineers signed on July 22, 2003. EEP commits to implement sufficient compensatory wetland and stream mitigation up to a 2:1 ratio to offset the impacts associated with this project by the end of the MOA year in which this project is permitted. If the impacts change from the above listed amount, then this mitigation strategy letter will no longer be valid and a new mitigation strategy letter will be required from EEP.

Restoring... Enhancing... Protecting Our State




North Carolina Ecosystem Enhancement Program, 1652 Mail Service Center, Raleigh, NC 27699-1652 / 919-715-0476 / www.nceep.net

Mr. Steve Lund
April 20, 2006
Page Two




If you have any questions or need additional information, please contact Ms. Beth Harmon at 919-715-1929.

Sincerely,

A handwritten signature in black ink, appearing to read "James B. Standfill Jr".

William D. Gilmore, P.E.
EEP Director

cc: Mr. Gregory J. Thorpe, Ph.D., NCDOT-PDEA
Mr. John Hennessy, Division of Water Quality, Wetlands/401 Unit
File: R-2616 Revised




N. C. DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
UNION COUNTY
PROJECT 34485.1.2 (R-2616 A&B)

US 601 FROM THE SOUTH
CAROLINA STATE LINE
TO NORTH OF
SR 2105 (MARION LEE RD.)

Permit Drawings Sheet 1 of 66

WETLAND LEGEND

— WLB — WETLAND BOUNDARY




WETLAND



DENOTES FILL IN WETLAND



DENOTES PERM. SURFACE WATER IMPACTS



DENOTES FILL IN SURFACE WATER (POND)




DENOTES TEMPORARY FILL IN WETLAND



DENOTES EXCAVATION IN WETLAND



DENOTES TEMPORARY SURFACE WATER IMPACT



DENOTES MECHANIZED CLEARING

→ → FLOW DIRECTION

— TB — TOP OF BANK

— WE — EDGE OF WATER

— C — PROP. LIMIT OF CUT

— F — PROP. LIMIT OF FILL

— ▲ — PROP. RIGHT OF WAY

— NG — NATURAL GROUND

— PL — PROPERTY LINE


— TDE — TEMP. DRAINAGE EASEMENT

— PDE — PERMANENT DRAINAGE EASEMENT

— EAB — EXIST. ENDANGERED ANIMAL BOUNDARY

— EPB — EXIST. ENDANGERED PLANT BOUNDARY

— ▽ — WATER SURFACE




LIVE STAKES




BOULDER

— — COIR FIBER ROLLS



PROPOSED BRIDGE



PROPOSED BOX CULVERT



PROPOSED PIPE CULVERT


(DASHED LINES DENOTE EXISTING STRUCTURES)

12"-48" PIPES

54" PIPES & ABOVE




SINGLE TREE



WOODS LINE



DRAINAGE INLET



ROOTWAD




RIP RAP




ADJACENT PROPERTY OWNER OR PARCEL NUMBER IF AVAILABLE



PREFORMED SCOUR HOLE



LEVEL SPREADER (LS)



DITCH / GRASS SWALE

N. C. DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
UNION COUNTY
PROJECT 34485.12 (R-2616 A&B)

US 601 FROM THE SOUTH
CAROLINA STATE LINE
TO NORTH OF
SR 2105 (MARION LEE RD)

Permit Drawings Sheet 2 of 66

IMPACT SUMMARY

Site No.	Station (From/To)	Structure Size	WETLAND IMPACTS					SURFACE WATER IMPACTS				
			Permanent Fill In Wetlands (ac)	Temp. Fill In Wetlands (ac)	Excavation In Wetlands (ac)	Mechanized Clearing in Wetlands (ac)	Hand Clearing In Wetlands (ac)	Permanent SW Impacts (ac)	Temp. SW Impacts (ac)	Exist. Chan. Impacts Permanent (ft)	Exist. Chan. Impacts Temp. (ft)	Natural Stream Design (ft)
1A	L 24+12	2 @ 42" RCP	0.013			0.023		0.007	0.001	104	10	
1	L 102+00 to 106+50	2 @ 54" RCP						0.02	0.01	223	75	
2	L 119+34	3 @ 10'X8' RCBC						0.08	0.01	166	40	
3	L 129+50	(2) 2 SPAN@65' BRIDGE							0.15		150	39**
4	L 148+91 LT	42" RCP						0.003	0.001	48	10	
5	L 180+30 RT & LT	48" RCP						0.02	0.003	240	47	
6	L 180+68 LT	48" RCP	0.006			0.003						
7	L 180+30 to 183+00 LT	Earthen Fill						0.03	0.004	215	10	
8A	L 206+00	36" RCP						0.01	0.001	150	10	
8	L 215+70 RT	24" RCP	0.006			0.003						
9	L 221+70 LT	Drain Pond						0.83				
10	L 231+20	54" RCP	0.034			0.013		0.01	0.001	170	22	
11	L 242+35	66" RCP						0.04	0.003	161	20	
12	L 248+30 to 251+09	48" RCP						0.04	0.003	290	22	
13	L 281+51	12'X10' RCBC						0.04	0.01	128	40	
14	L 288+06.5	2 @ 8'X7' RCBC						0.04	0.01	124	62	
15	L 290+00 to 294+30	2 @ 30" RCP						0.06	0.010	466	62	
16	L 315+56 *	16'X8' Bottomless Structure						0.01	0.08	25	240	40*
17	L 342+00 LT	Drain Pond						0.31				
18	L 349+50 RT	Road Fill; Temp Drain Pond	0.040					0.08	0.81			
19	L 349+50 LT	Drain Pond			0.04***			0.47				
20	L 400+00 RT	Drain Pond						0.58				
21	L 422+00 LT	Drain Pond						0.45				
22	L 426+03 to 430+50	54" RCP						0.03	0.001	460	30	
23	L 474+07 to 476+41	24" RCP	0.110			0.005						
23A	L 495+00	42" RCP						0.01	0.001	160	30	
24	L 534+20	48" RCP						0.01	0.001	151	30	
25	L 549+60	36" RCP	0.030			0.027						
26	L 575+85 LT	24" RCP						0.29				
TOTALS:			0.24	0.00	0.00	0.07	0.00	3.47	1.11	3281	910	0

* Stream replacement by addition of bottomless culvert.

** Stream that is currently culverted that will be spanned.

*** Wetland adjacent to drained pond- dewatered wetland.

NORTH CAROLINA DEPARTMENT OF
TRANSPORTATION
UNION COUNTY
WBS - 34485.122 (R-2616)

SHEET

Apr-06

PROPERTY OWNERS

PARCEL NO.

NAMES

ADDRESSES

26	ANNE M. COLLINS	
27	MARION F. COX DELANO. S. COX JOHN ROBERT COX RUTH C. COX	
28	DAVID MICHAEL BOOTH WENDY M. BOOTH	
29	ANNL P. HOWEY	
36	JERRY E. THOMAS ELSIE L. THOMAS	
39	WILLIAM HOLT EARNHART JANET GODWIN EARNHART	
37	TRUSTEES OF GALILEE BAPTIST CHRCH	
40	MILDRED S. SUTTON	
44	PHILLIP EDWARD DEESE	
46	BURL H. GRIFFIN DOROTHY H. GRIFFIN	
47	GERALD K. HARGETT DIANE R. HARGETT	
56	ROY L. WALTERS ELAINE R. WALTERS	
55	ANNE M. BAUCOM	
58	CAROL B. INGRAM	

N. C. DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
UNION COUNTY
PROJECT 34485.12 (R-2616 A&B)

US 601 FROM THE SOUTH
CAROLINA STATE LINE
TO NORTH OF
SR 2105 (MARION LEE RD.)

Permit Drawings Sheet 4 of 66

PROPERTY OWNERS

PARCEL NO.

NAMES

ADDRESSES

57	MANGUM FAMILY PARTNERSHIP, L.P.	
59	CARL W. MANGUM, JR.	
69	ROGER V. LANE JEANETTE F. LANE	
70	BUDDY HOWELL DYER	
71	B.D. PARKER LOIS L. PARKER	
72	BETTY R. KRIMMINGER	
82	WALTER E. ALBRIGHT CAROL J. ALBRIGHT	
83	HUBER DRAKE	
97	TAE HYUN CHUN IN SOOK CHUN	
115	DELORES P. PEREZ	
114	JOHNNY R. WALKER JULIE WALKER	
136	JAMES W. SELF NANCY W. SELF	
135	CELESTE A. BRYCHEK	
137	WILLIAM B. MULDROW BETTY W. MULDROW	
159	STEPHANIE M. CRIPE THOMAS JOSEPH CRIPE	

N. C. DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
UNION COUNTY
PROJECT 34485.12 (R-2616 A&B)

US 601 FROM THE SOUTH
CAROLINA STATE LINE
TO NORTH OF
SR 2105 (MARION LEE RD.)

Permit Drawings Sheet 5 of 66

PROPERTY OWNERS

PARCEL NO.

NAMES


ADDRESSES

161	GARREN BLAIR DEAN PEGGY R. DEAN	
160	DENNIS M. SUTTON REBECCA M. SUTTON	
162	FRANCES C. VICK	
167	THOMAS F. RITZ BARBARA A. RITZ	
168	AADELADE C. CLAWSON	
173	FRANCES C. VICK	

N. C. DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
UNION COUNTY
PROJECT 34485.1.2 (R-2616 A&B)


US 601 FROM THE SOUTH
CAROLINA STATE LINE
TO NORTH OF
SR 2105 (MARION LEE RD)

Permit Drawings Sheet 6 of 66




-L- STA. 39+00 TO 40+00 LT
-L- STA. 39+50 TO 41+00 RT
-L- STA. 43+00 TO 46+50 RT
-L- STA. 45+50 TO 47+50 LT
-L- STA. 48+00 TO 51+00 RT
-L- STA. 56+50 TO 57+00 RT
-L- STA. 75+00 TO 76+50 LT
-L- STA. 80+00 TO 84+00 LT
-L- STA. 80+00 TO 81+45 RT
-L- STA. 87+00 TO 87+70 LT
-L- STA. 88+50 TO 90+40 RT
-L- STA. 102+50 TO -Y2- 11+40 RT
-L- STA. 159+00 TO 160+00 LT
-L- STA. 177+00 TO 177+60 RT
-L- STA. 179+00 TO 180+68 RT
-L- STA. 187+00 TO 188+00 RT
-L- STA. 193+00 TO 194+00 RT
-L- STA. 208+50 TO 210+00 RT
-L- STA. 258+00 TO 260+00 LT
-L- STA. 263+00 TO 265+00 LT
-L- STA. 269+00 TO 271+58 LT

-L- STA. 336+50 TO 337+00 LT
-L- STA. 342+33 TO 344+00 LT
-L- STA. 380+50 TO 381+35 LT
-L- STA. 384+50 TO 385+72 LT
-L- STA. 443+50 TO 447+00 RT
-L- STA. 448+50 TO 449+70 LT
-L- STA. 449+70 TO 450+50 LT
-L- STA. 467+00 TO 469+54 RT
-L- STA. 480+00 TO 481+60 RT
-L- STA. 484+50 TO 485+00 RT
-L- STA. 516+00 TO 516+50 LT
-L- STA. 537+50 TO 538+00 RT
-L- STA. 538+00 TO 538+50 RT
-L- STA. 567+50 TO 568+16 RT
-L- STA. 568+16 TO 570+00 RT
-L- STA. 575+00 TO 575+92 RT
-Y7- STA. 26+00 TO 26+50 LT
-Y14- STA. 13+00 TO 13+60 RT
-Y16- STA. 7+50 TO 8+00 RT
-Y18- STA. 4+00 TO 4+50 LT



-L- STA. 103+00 TO 104+45 LT
-L- STA. 130+50 TO 135+50 LT
-L- STA. 135+43 TO 136+00 RT
-L- STA. 151+00 TO 153+50 LT
-L- STA. 167+76 TO 169+00 RT
-L- STA. 172+24 TO 173+32 RT
-L- STA. 172+24 TO 206+21 LT
-L- STA. 230+00 TO 231+6 RT
-L- STA. 236+36 TO 242+46 LT
-L- STA. 242+50 TO 243+50 RT
-L- STA. 250+26 TO 251+00 LT
-L- STA. 279+50 TO 281+00 RT
-L- STA. 312+00 TO 312+90 LT
-L- STA. 312+80 TO 316+90 LT
-L- STA. 331+30 TO 332+56 LT
-L- STA. 334+80 TO 335+60 LT
-L- STA. 349+00 TO 350+80 LT

-L- STA. 362+00 TO 363+00 RT
-L- STA. 362+50 TO 363+40 LT
-L- STA. 370+50 TO 372+00 LT
-L- STA. 396+80 TO 400+6 RT
-L- STA. 396+56 TO 401+50 LT
-L- STA. 430+00 TO 433+00 RT
-L- STA. 432+35 TO 433+50 LT
-L- STA. 437+46 TO 439+50 RT
-L- STA. 467+75 TO 468+80 LT
-L- STA. 516+50 TO 519+58 LT
-L- STA. 520+50 TO 524+00 RT
-L- STA. 530+78 TO 534+27 RT
-L- STA. 550+50 TO 551+25 RT
-L- STA. 552+70 TO 555+00 LT
-L- STA. 553+80 TO 555+50 RT
-L- STA. 562+00 TO 563+00 RT
-Y6- STA. 13+00 TO 15+00 RT
-Y9- STA. 11+00 TO 12+00 LT
-Y13- STA. 21+00 TO 21+74 LT




-L- 21+20 (MED)
-L- 23+00 (MED)
-L- 26+50 (MED)
-L- 31+40 (MED)
-L- 37+80 (MED)
-L- 44+00 (MED)
-L- 49+00 (MED)
-L- 57+00 (MED)
-L- 62+20 (MED)
-L- 64+50 (MED)
-L- 67+30 (MED)
-L- 70+50 (MED)
-L- 73+90 (MED)
-L- 81+62 (MED)
-L- 84+00 (MED)
-L- 87+80 (MED)
-L- 91+20 (MED)
-L- 96+61 (MED)
-L- 115+60 (MED)

-L- 120+40 (MED)
-L- 128+30 (MED)
-L- 137+35 (MED)
-L- 142+39 (MED)
-L- 146+50 (MED)
-L- 148+76 (MED)
-L- 158+70 (MED)
-L- 168+65 (MED)
-L- 173+45 (MED)
-L- 178+00 (MED)
-L- 203+61 (MED)
-L- 229+20 (MED)
-L- 234+00 (MED)
-L- 235+00 (MED)
-L- 238+90 (MED)
-L- 250+70 (MED)
-L- 258+20 (MED)
-L- 262+20 (MED)
-L- 263+20 (MED)
-L- 269+10 (MED)

-L- 271+60 (MED)
-L- 276+50 (MED)
-L- 278+50 (MED)
-L- 284+70 (MED)
-L- 288+80 (MED)
-L- 290+80 (MED)
-L- 298+20 (MED)
-L- 302+90 (MED)
-L- 304+30 (MED)
-L- 305+40 (MED)
-L- 311+50 (MED)
-L- 326+10 (MED)
-L- 327+60 (MED)
-L- 332+00 (MED)
-L- 335+50 (MED)
-L- 349+60 (MED)
-L- 352+30 (MED)
-L- 354+00 (MED)
-L- 358+50 (MED)
-L- 362+50 (MED)

-L- 364+50 (MED)
-L- 371+20 (MED)
-L- 375+80 (MED)
-L- 380+20 (MED)
-L- 393+10 (MED)
-L- 404+50 (MED)
-L- 412+00 (MED)
-L- 412+70 (MED)
-L- 414+00 (MED)
-L- 415+75 (MED)
-L- 420+20 (MED)
-L- 430+50 (MED)
-L- 436+20 (MED)
-L- 438+00 (MED)
-L- 451+80 (MED)
-L- 454+20 (MED)
-L- 460+60 (MED)
-L- 463+30 (MED)
-L- 466+50 (MED)
-L- 468+90 (MED)


-L- 485+00 (MED)
-L- 498+90 (MED)
-L- 500+10 (MED)
-L- 502+50 (MED)
-L- 505+20 (MED)
-L- 514+70 (MED)
-L- 513+40 (MED)
-L- 516+50 (MED)
-L- 522+30 (MED)
-L- 528+60 (MED)
-L- 531+50 (MED)
-L- 534+10 (MED)
-L- 541+80 (MED)
-L- 546+90 (MED)
-L- 549+30 (MED)
-L- 561+40 (MED)
-L- 564+00 (MED)
-L- 573+90 (MED)
-L- 575+80 (MED)
-L- 581+00 (MED)



-L- 23+00 (LT)
-L- 26+50 (LT)
-L- 120+39 (LT)
-L- 128+30 (LT)
-L- 137+37 (LT)
-L- 229+00 (LT)

-L- 234+00 (LT)
-L- 244+50 (LT)
-L- 276+50 (LT)
-L- 288+80 (LT)
-L- 311+50 (LT)
-L- 324+50 (LT)


-L- 404+50 (LT)
-L- 485+00 (LT)
-L- 511+70 (LT)
-L- 516+50 (LT)
-L- 546+90 (LT)




-L- 23+00 (RT)
-L- 26+50 (RT)
-L- 120+41 (RT)
-L- 128+40 (RT)
-L- 137+35 (RT)

-L- 229+50 (RT)
-L- 278+50 (RT)
-L- 285+00 (RT)
-L- 290+80 (RT)


-L- 302+90 (RT)
-L- 364+50 (RT)
-L- 502+50 (RT)
-L- 541+80 (RT)

Permit Drawings Sheet 7 of 66


-L- STA. 37+80 TO 39+50 RT
-L- STA. 314+00 TO 316+00 LT




-L- STA. 149+50 TO 152+10 RT
-L- STA. 329+32 TO 331+50 RT
-L- STA. 379+20 TO 381+00 RT




-L- STA. 70+00 TO 71+5 RT
-L- STA. 180+50 TO 182+32 LT
-L- STA. 291+50 TO 294+00 LT




-L- STA. 426+28 TO 430+00 RT




-L- STA. 40+00 TO 40+65 LT




-L- STA. 249+50 TO 250+65 RT




-L- STA. 360+60 TO 361+96 RT




-L- STA. 393+00 TO 395+60 LT




-L- STA. 490+60 TO 495+08 LT




-L- STA. 473+50 TO 476+64 LT




-L- STA. 16+00 TO 119+00 LT
-L- STA. 185+50 TO 187+50 LT
-L- STA. 335+62 TO 336+50 LT
-L- STA. 342+85 TO 344+50 RT
-L- STA. 363+30 LT TO -Y10- 6+20 RT
-L- STA. 476+37 TO 478+00 RT
-L- STA. 538+50 TO 539+03 LT
-L- STA. 559+50 TO 561+00 RT
-Y12- STA. 17+00 TO 18+91 RT
-Y12- STA. 17+50 TO 18+91 LT
-Y14- STA. 13+00 TO 13+80 LT




-L- STA. 356+50 TO 358+00 RT




-L- STA. 205+38 TO 206+72 RT
-L- STA. 237+50 TO 238+35 LT
-L- STA. 341+50 TO 342+85 RT
-L- STA. 475+50 TO 476+37 RT
-L- STA. 548+50 TO 549+50 RT
-L- STA. 560+50 TO 561+68 LT




-L- STA. 492+00 TO 494+84 RT
-L- STA. 494+84 TO 498+90 RT




-L- STA. 292+50 TO 293+00 RT
-L- STA. 293+00 TO 296+00 RT
-L- STA. 306+00 TO 307+40 RT
-L- STA. 375+70 TO 380+50 LT
-L- STA. 508+50 TO 511+65 LT
-L- STA. 557+75 TO 560+50 LT
-L- STA. 587+00 TO 592+62 LT




-L- STA. 559+00 TO 560+50 LT




-L- STA. 220+50 TO 221+75 LT




-L- STA. 35+70 TO 37+80 RT




-L- STA. 73+90 TO 74+60 RT
-L- STA. 145+50 TO 146+00 RT
-L- STA. 146+20 TO 146+20 RT
-L- STA. 363+10 TO 364+20 LT




-L- STA. 56+35 TO 56+60 RT
-L- STA. 88+50 TO 90+40 RT
-L- STA. 177+60 TO 177+70 RT
-L- STA. 449+66 TO 449+70 LT
-L- STA. 476+64 TO 477+00 LT
-L- STA. 583+00 TO 583+32 RT




-L- STA. 348+83 TO 349+59 RT




-L- STA. 105+72 RT




-L- STA. 148+39 LT




-L- STA. 180+44 LT




-L- STA. 148+39 LT




-L- STA. 231+23 RT




-L- STA. 242+16 RT
-L- STA. 430+11 LT




-L- STA. 248+68 RT




-L- STA. 289+90 RT




-L- STA. 430+11 LT
-L- STA. 534+25 LT





-L- STA. 119+00 LT
-L- STA. 241+40 RT
-L- STA. 249+49 RT



-L- STA. 149+50 TO 152+13 RT




-L- STA. 180+68 RT



SECTION A-A
(NOT TO SCALE)

L-25' MEASURED FROM
UPSTREAM END OF CULVERT.
EXCAVATION = 25 CUYD.
CONSTRUCT TO LIMITS SHOWN IN PLAN.





L-30' MEASURED FROM
DOWNSTREAM END OF CULVERT.
EXCAVATION = 20 CUYD.
CLASS I RIP RAP - 20 TONS.
CONSTRUCT TO LIMITS SHOWN IN PLAN.

SECTION B-B
(NOT TO SCALE)

REPRESENTS CHANNEL EXCAVATION

-L- 24 + 12

NAD / 83

Permit Drawings Sheet 8 of 66

SCALE: 1" = 100'



- | | |
|---|--------------------------------|
|  | FILL IN WETLAND |
|  | PERMANENT SURFACE WATER IMPACT |
|  | MECHANIZED CLEARING |
|  | TEMPORARY SURFACE WATER IMPACT |

SITE 1A


-L- 24+12

PROJECT REFERENCE NO.	SHEET NO.
R-2616 A&B	4
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION	
INCOMPLETE PLANS DO NOT USE FOR A.W. ACQUISITION	

Permit Drawings Sheet 9 of 66





- FILL IN WETLAND
- PERMANENT SURFACE WATER IMPACT
- MECHANIZED CLEARING
- TEMPORARY SURFACE WATER IMPACT



SITE 1 -L- 102+40



PROJECT REFERENCE NO.	SHEET NO.
R-2616 A&B	10
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
PRELIMINARY PLANS	
INCOMPLETE PLANS	
DO NOT USE FOR R/W ACQUISITION	

Permit Drawings Sheet 10 of 66



SCALE: 1" = 100'



- FILL IN WETLAND
- PERMANENT SURFACE WATER IMPACT
- MECHANIZED CLEARING
- TEMPORARY SURFACE WATER IMPACT






SITE 1 -L- 102+40

PROJECT REFERENCE NO.	SHEET NO.
R-2516 A&B	10
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION	
INCOMPLETE PLANS DO NOT USE FOR 30% ACQUISITION	

Permit Drawings Sheet 11 of 66





- FILL IN WETLAND
- PERMANENT SURFACE WATER IMPACT
- MECHANIZED CLEARING
- TEMPORARY SURFACE WATER IMPACT




SITE 2 -L- STA 119 + 34

ENGLISH

PROJECT REFERENCE NO.		SHEET NO.	
R-2616 A&B		11	
ROADWAY DESIGN ENGINEER		HYDRAULICS ENGINEER	
PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION INCOMPLETE PLANS DO NOT USE FOR R/T ACQUISITION			

Permit Drawings Sheet 12 of 66


SITE 2 -L- STA 119+34



ENGLISH

PROJECT REFERENCE NO.	SHEET NO.
R-2616 A&B	11
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION	
INCOMPLETE PLANS DO NOT USE FOR CONSTRUCTION	


Permit Drawings Sheet 13 of 66



SITE 2 -L- STA 119+34

PROJECT REFERENCE NO.	SHEET NO.
R-2616 ABB	11A
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION	
INCOMPLETE PLANS DO NOT USE FOR R/F ACQUISITION	



Permit Drawings Sheet 14 of 66



SITE 2 -L- STA 119+34

PROJECT REFERENCE NO.	SHEET NO.
R-2616 ADD	118
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION	
INCOMPLETE PLANS DO NOT USE FOR R/W ACQUISITION	

Permit Drawings Sheet 15 of 66



PROJECT REFERENCE NO.	SHEET NO.
R-2616 A&B	12
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION INCOMPLETE PLANS DO NOT USE FOR E / V ACQUISITION	

SECTION A-A
EXISTING DITCH
(Not to Scale)

Natural Ground

T


D

B


Natural Ground

T = 35.0 ft
D = 6.5 ft
B = 24.0 ft
NWS = 1.2 ft

MARION F. COX
DELANO S. COX
JOHN ROBERT COX
RUTH C. COX
DB 615 PG 451





SITE 3 -L- STA. 129 + 50



NAD 83

PROJECT REFERENCE NO. R-2616 A&B	SHEET NO. 12
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION	
INCOMPLETE PLANS DO NOT USE FOR U.S. ACQUISITION	

Permit Drawings Sheet 17 of 66




SCALE: 1" = 100'

- FILL IN WETLAND
- PERMANENT SURFACE WATER IMPACT
- MECHANIZED CLEARING
- TEMPORARY SURFACE WATER IMPACT




SITE 3 -L- STA 129 + 50


PROJECT REFERENCE NO.		SHEET NO.	
R-2616 AMB		12A	
ROADWAY DESIGN ENGINEER		HYDRAULICS ENGINEER	
PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION INCOMPLETE PLANS DO NOT USE FOR R/FW ACQUISITION			

Permit Drawings Sheet 18 of 66

VERTICAL SCALE: 1" : 50'



HORIZONTAL SCALE: 1" : 50'



NO SCUPPERS ARE REQUIRED FOR SOUTH BOUND LANES BRIGE.


EXCAVATION 600 CU.YD.




SITE 3 -L- STA 129+50

PROJECT REFERENCE NO.	SHEET NO.
K-2616 A&B	128
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION	
INCOMPLETE PLANS DO NOT USE FOR R/W ACQUISITION	


Permit Drawings Sheet 19 of 66



VERTICAL SCALE: 1" = 50'






HORIZONTAL SCALE: 1" = 50'





SITE 4 -L- STA. 148+91

PROJECT REFERENCE NO.	SHEET NO.
R-2616 A&B	13
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION	
INCOMPLETE PLANS DO NOT USE FOR R/W ACQUISITION	



Permit Drawings Sheet 20 of 66





- FILL IN WETLAND
- PERMANENT SURFACE WATER IMPACT
- MECHANIZED CLEARING
- TEMPORARY SURFACE WATER IMPACT



PROJECT REFERENCE NO.		SHEET NO.	
R-2416 A&B		13	
ROADWAY DESIGN ENGINEER		HYDRAULICS ENGINEER	
PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION			
INCOMPLETE PLANS DO NOT USE FOR R/W ACQUISITION			



-
- The legend consists of four rows, each with a square symbol box on the left and a text label on the right:
- Symbol: A square filled with diagonal lines from top-left to bottom-right. Text: **FILL IN WETLAND**
 - Symbol: A square with diagonal lines from top-left to bottom-right and a horizontal line across the middle. Text: **PERMANENT SURFACE WATER IMPACT**
 - Symbol: A square with a dotted pattern. Text: **MECHANIZED CLEARING**
 - Symbol: A square with diagonal lines from top-left to bottom-right and a horizontal line across the middle, with the letters 'TS' in the top-left and bottom-right corners. Text: **TEMPORARY SURFACE WATER IMPACT**







ENGLISH




SITE 5 -L- STA. 180+00 (RT.)
 SITE 6 -L- STA. 180+00 (LT.)
 SITE 7 -L- STA. 183+00 (LT.)

PROJECT REFERENCE NO. K-2616 A&B	SHEET NO. 16
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION INCOMPLETE PLANS DO NOT USE FOR E.A.W. ACQUISITION	

Permit Drawings Sheet 22 of 66







- FILL IN WETLAND
- PERMANENT SURFACE WATER IMPACT
- MECHANIZED CLEARING
- TEMPORARY SURFACE WATER IMPACT





SITE 5 -L- STA. 180+00 (RT.)
 SITE 6 -L- STA. 180+00 (LT.)
 SITE 7 -L- STA. 183+00 (LT.)

Permit Drawings Sheet 23 of 66



- FILL IN WETLAND
- PERMANENT SURFACE WATER IMPACT
- MECHANIZED CLEARING
- TEMPORARY SURFACE WATER IMPACT





SITE 8A -L- STA. 206 + 00




PROJECT REFERENCE NO. R-2616 A&B	SHEET NO. 17
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION INCOMPLETE PLANS DO NOT USE FOR R/W ACQUISITION	

Permit Drawings Sheet 24 of 66




- FILL IN WETLAND
- PERMANENT SURFACE WATER IMPACT
- MECHANIZED CLEARING
- TEMPORARY SURFACE WATER IMPACT




SITE 8A

-L- STA. 206 + 00



PROJECT REFERENCE NO.	SHEET NO.
R-2616 A&B	17
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION	
INCOMPLETE PLANS DO NOT USE FOR A/E/W ACQUISITION	

Permit Drawings Sheet 25 of 66




50' 0 100'



SCALE: 1" = 100'




- FILL IN WETLAND
- PERMANENT SURFACE WATER IMPACT
- MECHANIZED CLEARING
- TEMPORARY SURFACE WATER IMPACT



SITE 8 -L- STA. 215 + 70

PROJECT REFERENCE NO.	SHEET NO.
R-2616 A&B	18
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION	
INCOMPLETE PLANS DO NOT USE FOR R/W ACQUISITION	

Permit Drawings Sheet 26 of 66






- FILL IN WETLAND
- PERMANENT SURFACE WATER IMPACT
- MECHANIZED CLEARING
- TEMPORARY SURFACE WATER IMPACT




SITE 8 -L- STA. 215+70

PROJECT REFERENCE NO.	SHEET NO.
R-2616 A&B	18
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION	
INCOMPLETE PLANS DO NOT USE FOR R/W ACQUISITION	

Permit Drawings Sheet 27 of 66







- FILL IN WETLAND
- PERMANENT SURFACE WATER IMPACT
- MECHANIZED CLEARING
- TEMPORARY SURFACE WATER IMPACT



SITE 9 -L- STA. 221 + 00 LT.
SITE 10 -L- STA. 231 + 20

PROJECT REFERENCE NO.		SHEET NO.	
R-2616 A&B		19	
ROADWAY DESIGN ENGINEER		HYDRAULICS ENGINEER	
PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION			
INCOMPLETE PLANS DO NOT USE FOR R/W ACQUISITION			


Permit Drawings Sheet 28 of 66

FILL IN WETLAND

PERMANENT SURFACE WATER IMPACT

MECHANIZED CLEARING

TEMPORARY SURFACE WATER IMPACT









50' 0 100'



SCALE: 1" : 100'

SITE 9 -L- STA. 221+00 LT.
SITE 10 -L- STA. 231+20

Permit Drawings Sheet 29 of 66



SCALE: 1" = 100'



- FILL IN WETLAND
- PERMANENT SURFACE WATER IMPACT
- MECHANIZED CLEARING
- TEMPORARY SURFACE WATER IMPACT



SITE 11 -L- STA. 242+35

PROJECT REFERENCE NO.	SHEET NO.
R-2616 A&B	20
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION	
INCOMPLETE PLANS DO NOT USE FOR B/L ACQUISITION	

Permit Drawings Sheet 30 of 66



SCALE: 1" = 100'



- FILL IN WETLAND
- PERMANENT SURFACE WATER IMPACT
- MECHANIZED CLEARING
- TEMPORARY SURFACE WATER IMPACT




SITE 11 -L- STA. 242+35

PROJECT REFERENCE NO.	SHEET NO.
R-2516 A&B	20
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION	
INCOMPLETE PLANS DO NOT USE FOR ACQUISITION	



Permit Drawings Sheet 31 of 66



- FILL IN WETLAND
- PERMANENT SURFACE WATER IMPACT
- MECHANIZED CLEARING
- TEMPORARY SURFACE WATER IMPACT



SITE 11 -L- STA. 242 + 35


Permit Drawings Sheet 32 of 66

ENGLISH

SITE 12 -L- STA. 250+00

PROJECT REFERENCE NO.	SHEET NO.
R-2614 A&B	21
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION	
INCOMPLETE PLANS DO NOT USE FOR R/W ACQUISITION	


Permit Drawings Sheet 33 of 66



SITE 12 -L- STA. 250+00





PROJECT REFERENCE NO.		SHEET NO.	
R-2616 A&B		21	
ROADWAY DESIGN ENGINEER		HYDRAULICS ENGINEER	
PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION			
INCOMPLETE PLANS DO NOT USE FOR R/W ACQUISITION			

Permit Drawings Sheet 34 of 66




MATCHLINE -L- STA. 248+00.00 SEE SHEET 20

MATCHLINE -L- STA. 262+00.00 SEE SHEET 22




SITE 13 -L- STA. 281 + 51
 SITE 14 -L- STA. 288 + 06.5
 SITE 15 -L- STA. 290 + 00 - 294 + 30





PROJECT REFERENCE NO.	SHEET NO.
R-2616 A&B	23
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION	
INCOMPLETE PLANS DO NOT USE FOR R/W ACQUISITION	

Permit Drawings Sheet 35 of 66






SITE 13 -L- STA. 281 + 51
 SITE 14 -L- STA. 288 + 06.5
 SITE 15 -L- STA. 290 + 00 - 294 + 30






PROJECT REFERENCE NO.	SHEET NO.
R-2616 A&B	23
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION	
INCOMPLETE PLANS DO NOT USE FOR R/W ACQUISITION	

Permit Drawings Sheet 36 of 66



- NOTES:
1. ALL STONES ARE TO BE STRUCTURE STONE.
 2. GAPS BETWEEN BOULDERS SHALL BE MINIMIZED BY FITTING BOULDERS TOGETHER, PLUMBING WITH STRUCTURE STONE CLASS A AND NO. 47 AND LINING WITH FILTER FABRIC.
 3. DIMENSIONS AND SLOPES MAY BE ADJUSTED TO FIT BY THE ENGINEER.
 4. A DOUBLE FOOTER BOULDER SHALL BE UTILIZED IN SAND BED MATERIAL.
 5. FOOTER BOULDERS AND SILL BOULDERS SHALL BE NATIVE STONE OR SHOT ROCK, CUBICAL OR RECTANGULAR IN SHAPE.
 6. ACCEPTABLE BOULDERS SHALL HAVE THE FOLLOWING MINIMUM DIMENSIONS: 8' x 8' x 1'.



- FILL IN WETLAND
- PERMANENT SURFACE WATER IMPACT
- MECHANIZED CLEARING
- TEMPORARY SURFACE WATER IMPACT




SITE 13 -L- STA 281+51

PROJECT REFERENCE NO.	SHEET NO.
R-2616 A&B	23A
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION	
INCOMPLETE PLANS DO NOT USE FOR R/W ACQUISITION	

Permit Drawings Sheet 37 of 66



VERTICAL SCALE: 1" : 50'





HORIZONTAL SCALE: 1" : 50'



SITE 13 -L- STA 281+51

PROJECT REFERENCE NO.	SHEET NO.
R-2616 AMB	238
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION	
INCOMPLETE PLANS DO NOT USE FOR R/W ACQUISITION	


Permit Drawings Sheet 38 of 66



SITE 14 -L- STA 288 + 06.5

PROJECT REFERENCE NO.	SHEET NO.
R-2616 A&B	23C
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION	
INCOMPLETE PLANS DO NOT USE FOR R/W ACQUISITION	

Permit Drawings Sheet 39 of 66




289


288

287

286



VERTICAL SCALE: 1" : 50'



HORIZONTAL SCALE: 1" : 50'



SITE 14 -L- STA 288 + 06.5

PROJECT REFERENCE NO.	SHEET NO.
R-2616 A&B	23D
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION	
INCOMPLETE PLANS DO NOT USE FOR R/F ACQUISITION	




Permit Drawings Sheet 40 of 66

286

100 LT

0

100 RT





SITE 15 -L- STA. 290+00 RT - 294+30 LT




PROJECT REFERENCE NO.	SHEET NO.
R-2616 A&B	24
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION	
INCOMPLETE PLANS DO NOT USE FOR R/W ACQUISITION	

Permit Drawings Sheet 41 of 66



SCALE: 1" = 100'




- FILL IN WETLAND
- PERMANENT SURFACE WATER IMPACT
- MECHANIZED CLEARING
- TEMPORARY SURFACE WATER IMPACT



SITE 15 -L- STA. 290+00 RT - 294+30 LT

PROJECT REFERENCE NO.	SHEET NO.
R-2616 AAB	24
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION	
INCOMPLETE PLANS DO NOT USE FOR R/W ACQUISITION	





Permit Drawings Sheet 42 of 66



SITE 16 -L- STA. 315 + 56

PROJECT REFERENCE NO.	SHEET NO.
R-2616 A&B	25
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION	
INCOMPLETE PLANS DO NOT USE FOR R/W ACQUISITION	

Permit Drawings Sheet 43 of 66







- FILL IN WETLAND
- PERMANENT SURFACE WATER IMPACT
- MECHANIZED CLEARING
- TEMPORARY SURFACE WATER IMPACT




SITE 16 -L- STA. 315 + 56

PROJECT REFERENCE NO.	SHEET NO.
R-2616 A&B	25
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION	
INCOMPLETE PLANS DO NOT USE FOR A/E V. ACQUISITION	

Permit Drawings Sheet 44 of 66



SCALE: 1" = 100'




- FILL IN WETLAND
- PERMANENT SURFACE WATER IMPACT
- MECHANIZED CLEARING
- TEMPORARY SURFACE WATER IMPACT



SITE 16 -L- STA 315+56

PROJECT REFERENCE NO.	SHEET NO.
R-2616 A&B	25A
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION	
INCOMPLETE PLANS DO NOT USE FOR R/W ACQUISITION	



Permit Drawings Sheet 45 of 66



SITE 16 -L- STA 315+56

PROJECT REFERENCE NO.	SHEET NO.
R-2616 AMB	288
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION	
INCOMPLETE PLANS DO NOT USE FOR R/W ACQUISITION	

Permit Drawings Sheet 46 of 66





8/17/99


SITE 17 -L- STA. 342+00

PROJECT REFERENCE NO.	SHEET NO.
R-2616 A&B	27
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION	
INCOMPLETE PLANS DO NOT USE FOR R/W ACQUISITION	

Permit Drawings Sheet 47 of 66



- FILL IN WETLAND
- PERMANENT SURFACE WATER IMPACT
- MECHANIZED CLEARING
- TEMPORARY SURFACE WATER IMPACT




scale AT HY221524

MATCHLINE -L- STA. 332+00.00 SEE SHEET 26

MATCHLINE -L- STA. 346+00.00 SEE SHEET 28





SITE 18 -L- STA. 349 + 50 RT
SITE 19 -L- STA. 349 + 50 LT



Permit Drawings Sheet 49 of 66

MATCHLINE -L- STA. 346+00.00 SEE SHEET 27

MATCHLINE -L- STA. 360+00.00 SEE SHEET 29




- EXCAVATION IN WETLAND
- FILL IN WETLAND
- PERMANENT SURFACE WATER IMPACT
- MECHANIZED CLEARING
- TEMPORARY SURFACE WATER IMPACT





SITE 18 -L- STA. 349+50 RT
SITE 19 -L- STA. 349+50 LT

PROJECT REFERENCE NO. R-2616 A&B		SHEET NO. 28
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER	
PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION		
INCOMPLETE PLANS DO NOT USE FOR R/W ACQUISITION		

Permit Drawings Sheet 50 of 66




MATCHLINE -L- STA. 346+00.00 SEE SHEET 27



SCALE: 1" = 100'

- EXCAVATION IN WETLAND
- FILL IN WETLAND
- PERMANENT SURFACE WATER IMPACT
- MECHANIZED CLEARING
- TEMPORARY SURFACE WATER IMPACT




MATCHLINE -L- STA. 360+00.00 SEE SHEET 29

SITE 20 -L- STA. 400 + 00

PROJECT REFERENCE NO. R-2616 A&B	SHEET NO. 31
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION	
INCOMPLETE PLANS DO NOT USE FOR A/E WORK	

Permit Drawings Sheet 51 of 66



ENGLISH

SITE 20 -L- STA. 400 + 00

PROJECT REFERENCE NO.	SHEET NO.
L-2616 A&B	31
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION	
INCOMPLETE PLANS DO NOT USE FOR CONSTRUCTION	


Permit Drawings Sheet 52 of 66

MATCHLINE -L- STA. 388+00.00 SEE SHEET 30

MATCHLINE -L- STA. 402+00.00 SEE SHEET 32



- FILL IN WETLAND
- PERMANENT SURFACE WATER IMPACT
- MECHANIZED CLEARING
- TEMPORARY SURFACE WATER IMPACT






PROJECT REFERENCE NO.		SHEET NO.	
R-2616 A&B		33	
ROADWAY DESIGN ENGINEER		HYDRAULICS ENGINEER	

PRELIMINARY PLANS

DO NOT USE FOR CONSTRUCTION


INCOMPLETE PLANS

DO NOT USE FOR A/E ACCREDITATION







MATCHLINE -L- STA. 430+00.00 SEE SHEET 34

SITE 22 -L- STA. 430 + 50




PROJECT REFERENCE NO.		SHEET NO.	
R-2616 A&B		34	
ROADWAY DESIGN ENGINEER		HYDRAULICS ENGINEER	
PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION INCOMPLETE PLANS DO NOT USE FOR R/C ACQUISITION			

Permit Drawings Sheet 55 of 66

-




SITE 22 -L- STA. 430 + 50






PROJECT REFERENCE NO. R-2616 A&B	SHEET NO. 34
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION	
INCOMPLETE PLANS DO NOT USE FOR R/W ACQUISITION	

Permit Drawings Sheet 56 of 66



MATCHLINE -L- STA. 430+00.00 SEE SHEET 33



MATCHLINE -L- STA. 444+00.00 SEE SHEET 35



- FILL IN WETLAND
- PERMANENT SURFACE WATER IMPACT
- MECHANIZED CLEARING
- TEMPORARY SURFACE WATER IMPACT







SITE 23 -L- STA. 474+07
- STA. 476+41





- FILL IN WETLAND
- PERMANENT SURFACE WATER IMPACT
- MECHANIZED CLEARING
- TEMPORARY SURFACE WATER IMPACT

PROJECT REFERENCE NO. R-2616 A&B	SHEET NO. 37
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION	
INCOMPLETE PLANS DO NOT USE FOR R/E ACQUISITION	

Permit Drawings Sheet 57 of 66




SITE 23 -L- STA. 474 + 07
- STA. 476 + 41



- FILL IN WETLAND
- PERMANENT SURFACE WATER IMPACT
- MECHANIZED CLEARING
- TEMPORARY SURFACE WATER IMPACT

PROJECT REFERENCE NO. R-2616 A&B	SHEET NO. 37
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION	
INCOMPLETE PLANS DO NOT USE FOR R/W ACQUISITION	

Permit Drawings Sheet 58 of 66




SITE 23A -L- STA. 495 + 00

PROJECT REFERENCE NO. R-2616 A&B	SHEET NO. 38
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION INCOMPLETE PLANS DO NOT USE FOR R/W ACQUISITION	

-  FILL IN WETLAND
-  PERMANENT SURFACE WATER IMPACT
-  MECHANIZED CLEARING
-  TEMPORARY SURFACE WATER IMPACT

Permit Drawings Sheet 59 of 66







SITE 23A

-L-



STA. 495 + 00

PROJECT REFERENCE NO.	SHEET NO.
R-2616 A&B	38
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION	
INCOMPLETE PLANS DO NOT USE FOR Bidding or Construction	

-  FILL IN WETLAND
-  PERMANENT SURFACE WATER IMPACT
-  MECHANIZED CLEARING
-  TEMPORARY SURFACE WATER IMPACT



Permit Drawings Sheet 60 of 66






SITE 24 -L- STA. 534+20

PROJECT REFERENCE NO.	SHEET NO.
R-2616 A&B	41
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION	
INCOMPLETE PLANS DO NOT USE FOR R/W ACQUISITION	

Permit Drawings Sheet 61 of 66


- FILL IN WETLAND
- PERMANENT SURFACE WATER IMPACT
- MECHANIZED CLEARING
- TEMPORARY SURFACE WATER IMPACT





SITE 24 -L- STA. 534+20

PROJECT REFERENCE NO.		SHEET NO.
R-2416 A&B		41
ROADWAY DESIGN ENGINEER		HYDRAULICS ENGINEER
PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION		
INCOMPLETE PLANS DO NOT USE FOR A/E ACQUISITION		

Permit Drawings Sheet 62 of 66



- FILL IN WETLAND
- PERMANENT SURFACE WATER IMPACT
- MECHANIZED CLEARING
- TEMPORARY SURFACE WATER IMPACT




SCALE: 1" = 100'




SITE 25 -L- STA. 549+60

PROJECT REFERENCE NO.	SHEET NO.
R-2416 A&B	42
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION	
INCOMPLETE PLANS DO NOT USE FOR R/W ACQUISITION	




- FILL IN WETLAND
- PERMANENT SURFACE WATER IMPACT
- MECHANIZED CLEAR
- TEMPORARY SURFACE WATER IMPACT

Permit Drawings Sheet 63 of 66



SITE 25 -L- STA. 549+60


ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION	
INCOMPLETE PLANS DO NOT USE FOR R/W ACQUISITION	




- FILL IN WETLAND
- PERMANENT SURFACE WATER IMPACT
- MECHANIZED CLEARING
- TEMPORARY SURFACE WATER IMPACT

Permit Drawings Sheet 64 of 66

MATCHLINE -L- STA. 542+00.00 SEE SHEET 41



MATCHLINE -L- STA. 556+00.00 SEE SHEET 43



CURVE L-14
Pls Sta 555+00.00 Pl Sta 556+00.00 Pls Sta 558.1





SITE 26 -L- STA. 575+85

-  FILL IN WETLAND
-  PERMANENT SURFACE WATER IMPACT
-  MECHANIZED CLEARING
-  TEMPORARY SURFACE WATER IMPACT

PROJECT REFERENCE NO. R-2616 A&B	SHEET NO. 44
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION	
INCOMPLETE PLANS DO NOT USE FOR R/W ACQUISITION	

Permit Drawings Sheet 65 of 66




SITE 26 -L- STA. 575 + 85

PROJECT REFERENCE NO. R-2616 A&B	SHEET NO. 44
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION	
INCOMPLETE PLANS DO NOT USE FOR R/W ACQUISITION	

-  FILL IN WETLAND
-  PERMANENT SURFACE WATER IMPACT
-  MECHANIZED CLEARING
-  TEMPORARY SURFACE WATER IMPACT

Permit Drawings Sheet 66 of 66



See Sheet 1-A For Index of Sheets
See Sheet 1-B For Conventional Symbols



STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS

UNION COUNTY

LOCATION: US 601 FROM NORTH OF THE SOUTH CAROLINA
STATE LINE TO NORTH OF SR 2105
(MARION LEE RD.)

TYPE OF WORK: GRADING, DRAINAGE, PAVING, WIDENING, SIGNING,
GUARDRAIL, CULVERTS AND STRUCTURE

STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	R-2616	1	
WBS NO.	P.A. PROJ. NO.	DESCRIPTION	
34485.1.2	STP-NHS-601(4)	P.E.	
34485.2.4	STP-601(18)	R/W, Utilities	



NCDOT CONTACT: Doug Taylor, PE
ROADWAY DESIGN UNIT - ENGINEERING COORDINATION


THIS IS A PARTIAL CONTROLLED ACCESS PROJECT WITH
ACCESS BEING LIMITED TO ONE ENTRANCE PER PROPERTY

PROPERTIES WITH GREATER THAN 2000' OF FRONTAGE
MAY RECEIVE ADDITIONAL ACCESS POINTS

CLEARING ON THIS PROJECT SHALL BE PERFORMED
TO THE LIMITS ESTABLISHED BY METHOD III.

PRELIMINARY PLANS
DO NOT USE FOR CONSTRUCTION

GRAPHIC SCALES



DESIGN DATA

ADT 2002 = 12,000
ADT 2025 = 23,800
DHV = 10 %
D = 60 %
T = 24 % *
V = 60 MPH
* TTST 17 % + DUAL 7 %

PROJECT LENGTH

LENGTH ROADWAY TIP PROJECT R-2616A&B = 10.852 ± MI.
LENGTH OF STRUCTURES, TIP PROJECT R-2616A&B = 0.029 ± MI.
TOTAL LENGTH OF TIP PROJECT R-2616A&B* = 10.881 MI.

*NOTE: LENGTH BASED ON NBL -L-

Prepared in the Office of:
RALPH WHITEHEAD ASSOCIATES, INC.
for the North Carolina Department of Transportation

2002 STANDARD SPECIFICATIONS

RIGHT OF WAY DATE:
October 3, 2005

LETTING DATE:
June 20, 2006

JOHN N. JOHNSON, P.E.
PROJECT ENGINEER

GERALD BARBOUR
PROJECT DESIGN ENGINEER

HYDRAULICS ENGINEER

SIGNATURE: _____ P.E.
ROADWAY DESIGN
ENGINEER

SIGNATURE: _____ P.E.

DIVISION OF HIGHWAYS STATE OF NORTH CAROLINA



STATE HIGHWAY DESIGN ENGINEER

CONTRACT: TIP PROJECT: R-2616

8/17/99

REVISIONS

32406:
PARCEL 3, NAME CHANGED

DATUM DESCRIPTION

THE LOCALIZED COORDINATE SYSTEM DEVELOPED FOR THIS PROJECT IS BASED ON THE STATE PLANE COORDINATES ESTABLISHED BY NC DOT FOR MONUMENT "R2616-13" WITH NAD 1983/95 STATE PLANE GRID COORDINATES OF NORTHING: 418037.380111 EASTING: 1562547.518111 THE AVERAGE COMBINED GRID FACTOR USED ON THIS PROJECT (GROUND TO GRID) IS: 0.99986650 THE N.C. LAMBERT GRID BEARING AND LOCALIZED HORIZONTAL GROUND DISTANCE FROM "R2616-13" TO L- STATION PC: 17+71.00 IS S 23°56'23.87" E 28.1677' ALL LINEAR DIMENSIONS ARE LOCALIZED HORIZONTAL DISTANCES VERTICAL DATUM USED IS NAVD 88

THE DESIGN BUILD TEAM WILL COORDINATE THE ALIGNMENT OF R-2616 WITH THE EXISTING ALIGNMENT OF SCDOT PROJECT NO. BNH-PDCB(004)


THIS IS A PARTIAL CONTROLLED ACCESS PROJECT WITH ACCESS BEING LIMITED TO ONE ENTRANCE PER PROPERTY PROPERTIES WITH GREATER THAN 100' OF FRONTAGE MAY RECEIVE ADDITIONAL ACCESS POINTS

W RALPH WHITHEAD ASSOCIATES
CONSULTING ENGINEERS
P.O. BOX 35624
CHARLOTTE, NORTH CAROLINA 28235

PROJECT REFERENCE NO.		SHEET NO.
R-2616 A&B		4
RAW SHEET NO.		
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER	

5' MONOLITHIC ISLAND
FULL DEPTH PAVED SHOULDER
PAVEMENT REMOVAL

NAD 83



MATCHLINE -L- STA. 26+00.00 SEE SHEET 5

CURVE EOP1-2

PI Sta 21+46.23 Os = 0°17'11.3" Ls = 100.00' LT = 66.67' ST = 33.33'	PI Sta 24+35.54 Δ = 2°55'57.5" (LT) D = 0°34'22.6" L = 511.84' T = 255.98' SE = 0.02 FT./FT.	PI Sta 27+24.74 Os = 0°17'11.3" Ls = 100.00' LT = 66.67' ST = 33.33'
--	---	--

CURVE EOP2-2

PI Sta 23+77.16 Os = 0°57'17.7" Ls = 200.00' LT = 133.34' ST = 66.67'	PI Sta 26+25.99 Δ = 3°28'40.8" (LT) D = 0°57'17.7" T = 182.16' L = 364.22' R = 6000.00' SE = 0.03 FT./FT.	PI Sta 28+74.71 Os = 0°57'17.7" Ls = 200.00' LT = 133.34' ST = 66.67'
---	---	---

CURVE EOP1-1

PI Sta 18+16.87 Os = 0°17'11.3" Δ = 0°37'19.3" (RT) D = 0°34'22.6" L = 100.00' T = 54.28' R = 10000.00' SE = NC (MATCH SCDOT)	PI Sta 19+25.28 Δ = 0°37'19.3" (RT) D = 0°34'22.6" L = 108.57' T = 54.28' R = 10000.00'	PI Sta 20+12.90 Os = 0°17'11.3" Ls = 100.00' LT = 66.67' ST = 33.33'
--	--	--

CURVE EOP2-1

PI Sta 19+07.44 Δ = 2°35'58.8" (RT) D = 0°57'10.3" T = 136.44' L = 272.83' R = 6013.00' SE = 0.03 FT./FT.	PI Sta 20+10.49 Os = 0°57'10.3" Ls = 200.00' LT = 133.34' ST = 66.67'
---	---

CURVE L-1

PI Sta 15+70.76 Os = 7°40'37.3" (RT) D = 0°57'06.1" T = 403.94' L = 806.66' R = 6020.33'	PI Sta 20+40.15 Os = 0°57'06.1" Ls = 200.00' LT = 133.34' ST = 66.67'
---	---

CURVE L-2

PI Sta 23+06.82 Os = 1°00'00.0" Ls = 200.00' LT = 133.34' ST = 66.67'	PI Sta 25+09.22 Δ = 2°42'50.8" (LT) D = 1°00'00.0" T = 135.73' L = 271.41' R = 5729.58'	PI Sta 27+11.56 Os = 1°00'00.0" Ls = 200.00' LT = 133.34' ST = 66.67'
---	--	---

SEE SHEET 47 FOR -L- PROFILE.


REVISIONS	
32406:	PARCEL 3, NAME CHANGED & PARCEL NO. CHANGE

THIS IS A PARTIAL CONTROLLED ACCESS PROJECT WITH
ACCESS BEING LIMITED TO ONE ENTRANCE PER PROPERTY

PROPERTIES WITH GREATER THAN 200' OF FRONTAGE
MAY RECEIVE ADDITIONAL ACCESS POINTS

 RALPH WHITEHEAD ASSOCIATES CONSULTING ENGINEERS P.O. BOX 35624 CHARLOTTE, NORTH CAROLINA 28335	PROJECT REFERENCE NO.		SHEET NO.
	R-2616 A&B		5
	RAW SHEET NO.		
	ROADWAY DESIGN ENGINEER 	HYDRAULICS ENGINEER	

	5" MONOLITHIC ISLAND
	FULL DEPTH PAVED SHOULDER
	PAVEMENT REMOVAL




CURVE EOPI-2		
Pis Sta 21+46.23	Pi Sta 24+35.54	Pis Sta 27+24.74
$\Theta_s = 0^\circ 17' 11.3''$	$\Delta = 2^\circ 55' 57.5''$ (LT)	$\Theta_s = 0^\circ 17' 11.3''$
$L_s = 100.00'$	$D = 0^\circ 34' 22.6''$	$L_s = 100.00'$
$LT = 66.67'$	$L = 511.84'$	$LT = 66.67'$
$ST = 33.33'$	$T = 255.98'$	$ST = 33.33'$
	$R = 10,000.00'$	
	$SE = 0.02 \text{ FT./FT.}$	

CURVE EOP2-2				CURVE L-2			
Pis Sta 23+77.6	PI Sta 26+25.99	Pis Sta 28+74.71	Pis Sta 23+06.82	PI Sta 25+09.22	Pis Sta 27+11.56		
Θs = 0° 57' 17.7"	Θs = 3° 28' 40.8" (LT)	Θs = 0° 57' 17.7"	Θs = 1° 00' 00.0"	Θs = 2° 42' 50.8" (LT)	Θs = 1° 00' 00.0"		
Ls = 200.00'	D = 0° 57' 17.7"	Ls = 200.00'	Ls = 200.00'	D = 1° 00' 00.0"	Ls = 200.00'		
LT = 133.34'	T = 182.16'	LT = 133.34'	LT = 133.34'	T = 135.73'	LT = 133.34'		
ST = 66.67'	L = 364.22'	ST = 66.67'	ST = 66.67'	L = 271.4'	ST = 66.67'		
	R = 6,000.00'			R = 5729.58'			
	SE = 0.03 FT./FT.						

SEE SHEET 48 FOR -L- PROFILE.

09-MAY-2006 07:59
r:\roadway\proj\2616-rdy-psh\06.dgn



8/17/99

REVISIONS

32406:
PARCEL 9, NAME CHANGE
PARCEL 10, NAME CHANGE
PARCEL 17, NAME CHANGE
PARCEL 22, NAME CHANGE

THIS IS A PARTIAL CONTROLLED ACCESS PROJECT WITH
ACCESS BEING LIMITED TO ONE ENTRANCE PER PROPERTY

PROPERTIES WITH GREATER THAN 200' OF FRONTAGE
MAY RECEIVE ADDITIONAL ACCESS POINTS




RALPH WHITEHEAD ASSOCIATES
CONSULTING ENGINEERS
P.O. BOX 35624
CHARLOTTE, NORTH CAROLINA 28235

PROJECT REFERENCE NO.		SHEET NO.
R-2616 A&B		7
R/W SHEET NO.		
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER	

5' MONOLITHIC ISLAND
FULL DEPTH PAVED SHOULDER
PAVEMENT REMOVAL

MATCHLINE -L- STA. 54 + 00.00 SEE SHEET 6

MATCHLINE -L- STA. 68 + 00.00 SEE SHEET 8



SEE SHEET 50 FOR -L- PROFILE.

8/17/99

REVISIONS

32406:
PARCEL 17 NAME CHANGE
PARCEL 18 NAME CHANGE & PROP. LINE CHANGE
PARCEL 18A NAME CHANGE & PROP. LINE ADDITION
PARCEL 22 NAME CHANGE


THIS IS A PARTIAL CONTROLLED ACCESS PROJECT WITH
ACCESS BEING LIMITED TO ONE ENTRANCE PER PROPERTY

PROPERTIES WITH GREATER THAN 300' OF FRONTAGE
MAY RECEIVE ADDITIONAL ACCESS POINTS

W RALPH WHITEHEAD ASSOCIATES
CONSULTING ENGINEERS
P.O. BOX 35624
CHARLOTTE, NORTH CAROLINA 28235

PROJECT REFERENCE NO.		SHEET NO.
R-2616 A&B		8
RW SHEET NO.		
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER	

5' MONOLITHIC ISLAND
FULL DEPTH PAVED SHOULDER
PAVEMENT REMOVAL



09-MAY-2006 07:59
\\csc\shared\2616_rdy_psh08.dgn
\\csc\shared\2616_rdy_psh08.dgn

SEE SHEET 51 FOR -L- PROFILE.

8/17/99

REVISIONS

32406
PARCEL 22 NAME CHANGE & PROP. LINE ADDITION
PARCEL 22B NAME & PROP. LINE ADDITION
PARCEL 26A NAME CHANGE

THIS IS A PARTIAL CONTROLLED ACCESS PROJECT WITH
ACCESS BEING LIMITED TO ONE ENTRANCE PER PROPERTY

PROPERTIES WITH GREATER THAN 200' OF FRONTAGE
MAY REQUEST ADDITIONAL ACCESS POINTS



RALPH WHITEHEAD ASSOCIATES
CONSULTING ENGINEERS
P.O. BOX 35624
CHARLOTTE, NORTH CAROLINA 28235

PROJECT REFERENCE NO. R-2616 A&B SHEET NO. 9

ROADWAY DESIGN ENGINEER HYDRAULICS ENGINEER

5' MONOLITHIC ISLAND
FULL DEPTH PAVED SHOULDER
PAVEMENT REMOVAL

MATCHLINE -L- STA. 82+00.00 SEE SHEET 8

MATCHLINE -L- STA. 96+00.00 SEE SHEET 10

CURVE L-3

Pls Sta 76+33.34	Pls Sta 78+70.77	Pls Sta 81+08.10
$\theta_s = 1'00'00.0''$	$\Delta = 3'24'51.6''$ (LT)	$\theta_s = 1'00'00.0''$
$L_s = 200.00'$	$D = 1'00'00.0''$	$L_s = 200.00'$
$LT = 133.34'$	$T = 170.77'$	$LT = 133.34'$
	$L = 341.43'$	$ST = 66.67'$
	$R = 5729.58'$	
	$SE = 0.03$	

CURVE L-4

Pls Sta 83+74.77	Pls Sta 86+12.20	Pls Sta 88+49.53
$\theta_s = 1'00'00.0''$	$\Delta = 3'24'51.6''$ (RT)	$\theta_s = 1'00'00.0''$
$L_s = 200.00'$	$D = 1'00'00.0''$	$L_s = 200.00'$
$LT = 133.34'$	$T = 170.77'$	$LT = 133.34'$
$ST = 66.67'$	$L = 341.43'$	$ST = 66.67'$
	$R = 5729.58'$	
	$SE = 0.03$	



SEE SHEET 52 FOR -L- PROFILE.

8/17/99

37406 NAME CHANGE PARCEL 22C
37406 NAME CHANGE PARCEL 26

37406 NAME CHANGE & PROP. LINE ADDITION PARCEL 26A
37406 NAME CHANGE & PROP. LINE ADDITION PARCEL 22B
37406 NAME CHANGE PARCEL 22

09-MAY-2006 07:59
RAYCONDA\RAYCONDA\2616.rdy-ph10.dgn
2616.rdy-ph10.dgn



PROJECT REFERENCE NO. R-2616 A&B		SHEET NO. 10
RW SHEET NO.		HYDRAULICS ENGINEER
ROADWAY DESIGN ENGINEER		
RALPH WHITEHEAD ASSOCIATES CONSULTING ENGINEERS P.O. BOX 35624 CHARLOTTE, NORTH CAROLINA 28235		

5' MONOLITHIC ISLAND
FULL DEPTH PAVED SHOULDER
PAVEMENT REMOVAL
PAVING STONES


MARION F. COX
DELANO S. COX
JOHN ROBERT COX
RUTH C. COX

MATCHLINE -L- STA. 96+00.00 SEE SHEET 9


MATCHLINE -L- STA. 110+00.00 SEE SHEET 11

SEE SHEET 53 FOR -L- PROFILE.
SEE SHEET 89 FOR -Y1- & -Y2- PROFILE.

THIS IS A PARTIAL CONTROLLED ACCESS PROJECT WITH ACCESS BEING LIMITED TO ONE ENTRANCE PER PROPERTY
PROPERTIES WITH GREATER THAN 300' OF FRONTAGE MAY RECEIVE ADDITIONAL ACCESS POINTS




32406	
PARCEL 22A	NAME CHANGE & PARCEL NO. ADDITION
PARCEL 22C	NAME CHANGE & PROP. LINE ADDITION



NAD 83

WATCHLINE -L- STA. 122 + 00.00 SEE SHEET 12



CURVE L-5

Pis	Sta	$115+75.79$	Δ	Sta	$116+13.22$	Pis	Sta	$118+50.55$
Θ_s		$1^{\circ}00'00.0''$	$\Pi =$	$3^{\circ}24'51.6''(RT)$		Θ_s		$1^{\circ}00'00.0''$
Ls		$200.00'$	$D =$	$1^{\circ}00'00.0''$		Ls		$200.00'$
Lt		$133.34'$	$T =$	$10.77'$		Lt		$133.34'$
ST		$66.67'$	$L =$	$34.43'$		ST		$66.67'$
			$R =$	$5.729.58'$				
			$SE =$	0.03 FT/FT				

NATURAL GROUND

LOW FLOW CHANNEL

CLASS I RIP RAP

15' (TYP)

2' (TYP)

VARIES

13' TO 17'

2:1

2:1

L = 30' MEASURED FROM DOWNSTREAM END OF CULVERT.
EXCAVATION - 20 CU YDS.
CLASS I RIP RAP - 20 TONS.
CONSTRUCT TO LIMITS SHOWN IN PLAN.

SECTION B-B
(NOT TO SCALE)

REPRESENTS CHANNEL EXCAVATION

SEE SHEET 54 FOR -L- PROFILE.


8/17/99
09-MAY-2006 08:00:06 0616.rdy-psht2.dgn
R-2616 A&B

REVISIONS

3/24/04
PARCEL 22A NAME CHANGE & PARCEL NO. ADDITION

THIS IS A PARTIAL CONTROLLED ACCESS PROJECT WITH
ACCESS BEING LIMITED TO ONE ENTRANCE PER PROPERTY

PROPERTIES WITH GREATER THAN 300' OF FRONTAGE
MAY RECEIVE ADDITIONAL ACCESS POINTS



TYPICAL SECTION ON STRUCTURES


SBL STA.128+93± TO STA.130+23±
NBL STA.128+77± TO STA.130+07±

RALPH WHITEHEAD ASSOCIATES
CONSULTING ENGINEERS
P.O. BOX 35624
CHARLOTTE, NORTH CAROLINA 28235

PROJECT REFERENCE NO.	SHEET NO.
R-2616 A&B	12
R/W SHEET NO.	
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER



5' MONOLITHIC ISLAND
FULL DEPTH PAVED SHOULDER
PAVEMENT REMOVAL

MARION F. COX
DELANO S. COX
JOHN ROBERT COX
RUTH C. COX
DB 645 PG 454



CURVE L-6


PIs Sta 121+17.22	PI Sta 123+54.65	PIs Sta 125+91.98
$\Delta s = 1'00'00''$	$\Delta = 3'24'51.6''$ (LT)	$\Delta s = 1'00'00''$
$Ls = 200.00'$	$D = 1'00'00''$	$Ls = 200.00'$
$LT = 133.34'$	$T = 170.77'$	$LT = 133.34'$
$ST = 66.67'$	$L = 341.43'$	$ST = 66.67'$
	$R = 5729.58'$	
	$SE = 0.03$ FT/FT	




SEE SHEET 55 FOR -L- PROFILE.

THIS IS A PARTIAL CONTROLLED ACCESS PROJECT WITH
ACCESS BEING LIMITED TO ONE ENTRANCE PER PROPERTY

PROPERTIES WITH GREATER THAN 200' OF FRONTAGE
MAY RECEIVE ADDITIONAL ACCESS POINTS



	5' MONOLITHIC ISLAND
	FULL DEPTH PAVED SHOULDER
	PAVEMENT REMOVAL



SEE SHEET 56 FOR -L- PROFILE.

8/17/99

REVISIONS


THIS IS A PARTIAL CONTROLLED ACCESS PROJECT WITH
ACCESS BEING LIMITED TO ONE ENTRANCE PER PROPERTY

PROPERTIES WITH GREATER THAN 200' OF FRONTAGE
MAY RECEIVE ADDITIONAL ACCESS POINTS

W RALPH WHITEHEAD ASSOCIATES
CONSULTING ENGINEERS
P.O. BOX 35624
CHARLOTTE, NORTH CAROLINA 28335


PROJECT REFERENCE NO.		SHEET NO.
R-2616 A&B		14
RW SHEET NO.		
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER	

5' MONOLITHIC ISLAND
FULL DEPTH PAVED SHOULDER
PAVEMENT REMOVAL



MATCHLINE -L- STA. 150 + 00.00 SEE SHEET 13

MATCHLINE -L- STA. 164 + 00.00 SEE SHEET 15



09 MAY 2006 08:00
C:\PROJECTS\2616.rdw_psh14.dgn
\$\$\$\$\$

SEE SHEET 57 FOR -L- PROFILE.

09-MAY-2006 08:00
 \$\$\$USERNAME\$\$\$
 \\roadway\projr2616-rdy-ps15.dgn

THIS IS A PARTIAL CONTROLLED ACCESS PROJECT WITH
ACCESS BEING LIMITED TO ONE ENTRANCE PER PROPERTY

PROPERTIES WITH GREATER THAN 200' OF FRONTAGE
MAY RECEIVE ADDITIONAL ACCESS POINTS

PROJECT REFERENCE NO.		SHEET NO.	
R-2616 A&B		15	
RW SHEET NO.			
ROADWAY DESIGN ENGINEER		HYDRAULICS ENGINEER	
			

	5' MONOLITHIC ISLAND
	FULL DEPTH PAVED SHOULDER
	PAVEMENT REMOVAL



SEE SHEET 59 FOR -L- PROFILE.

8/17/99

REVISIONS

THIS IS A PARTIAL CONTROLLED ACCESS PROJECT WITH
ACCESS BEING LIMITED TO ONE ENTRANCE PER PROPERTY
PROPERTIES WITH GREATER THAN 200' OF FRONTAGE
MAY RECEIVE ADDITIONAL ACCESS POINTS

W RALPH WHITEHEAD ASSOCIATES
CONSULTING ENGINEERS
P.O. BOX 35624
CHARLOTTE, NORTH CAROLINA 28235


PROJECT REFERENCE NO.		SHEET NO.
R-2616 A&B		17
RW SHEET NO.		HYDRAULICS ENGINEER
ROADWAY DESIGN ENGINEER		

5' MONOLITHIC ISLAND
FULL DEPTH PAVED SHOULDER
PAVEMENT REMOVAL

NAD 83

MATCHLINE -L- STA. 192 + 00.00 SEE SHEET 16

MATCHLINE -L- STA. 206 + 00.00 SEE SHEET 18



CURVE L-7		
Pls Sta 204+46.67	PI Sta 206+88.03	Pls Sta 209+29.28
Os = 1'00'00.0"	Δ = 3'29'33.8" (LT)	Os = 1'00'00.0"
Ls = 200.00'	D = 1'00'00.0"	Ls = 200.00'
LT = 133.34'	T = 174.69'	LT = 133.34'
ST = 66.67'	L = 349.27'	ST = 66.67'
	R = 5729.58'	
	SE = 0.03 FT/FT	

SEE SHEET 60 FOR -L- PROFILE.

8/17/99

REVISIONS

40406
PARCEL 36
REMOVED PROP. RW LINE ALONG -Y4R-

THIS IS A PARTIAL CONTROLLED ACCESS PROJECT WITH
ACCESS BEING LIMITED TO ONE ENTRANCE PER PROPERTY

PROPERTIES WITH GREATER THAN 300' OF FRONTAGE
MAY RECEIVE ADDITIONAL ACCESS POINTS




RALPH WHITEHEAD ASSOCIATES
CONSULTING ENGINEERS
P.O. BOX 35624
CHARLOTTE, NORTH CAROLINA 28235

PROJECT REFERENCE NO.		SHEET NO.
R-2616 A&B		18
RW SHEET NO.		
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER	

5' MONOLITHIC ISLAND
FULL DEPTH PAVED SHOULDER
PAVEMENT REMOVAL

MATCHLINE -L- STA. 206+00.00 SEE SHEET 17


MATCHLINE -L- STA. 220+00.00 SEE SHEET 19



CURVE L-7		
Pls Sta 204+46.67	Pls Sta 206+88.03	Pls Sta 209+29.28
θs = 1'00'00.0"	Δ = 3'29'33.8" (LT)	θs = 1'00'00.0"
Ls = 200.00'	D = 1'00'00.0"	Ls = 200.00'
LT = 133.34'	T = 174.69'	LT = 133.34'
ST = 66.67'	L = 349.27'	ST = 66.67'
	R = 5729.58'	
	SE = 0.03 FT/FT	

CURVE L-8		
Pls Sta 211+95.94	Pls Sta 214+33.96	Pls Sta 216+71.87
θs = 1'00'00.0"	Δ = 3'25'33.4" (RT)	θs = 1'00'00.0"
Ls = 200.00'	D = 1'00'00.0"	Ls = 200.00'
LT = 133.34'	T = 171.35'	LT = 133.34'
ST = 66.67'	L = 342.59'	ST = 66.67'
	R = 5729.58'	
	SE = 0.03 FT/FT	

CURVE Y4R-1	
Pls Sta 7+16.97	Δ = 26'59'06.7" (RT)
D = 10'00'00"	L = 269.85'
T = 137.48'	R = 572.96'
e = 05	



SEE SHEET 61 FOR -L- PROFILE.

09-MAY-2006 08:01
2616.rdy-peh18.dgn
2616.rdy-peh18.dgn

09-MAY-2006 08:01
r:\roadway\proj\2616_rdy-psh19.dgn

THIS IS A PARTIAL CONTROLLED ACCESS PROJECT WITH ACCESS BEING LIMITED TO ONE ENTRANCE PER PROPERTY

PROPERTIES WITH GREATER THAN 50% OF FRONTAGE MAY RECEIVE ADDITIONAL ACCESS POINTS

DENVER ED RORIE
JOY D. RORIE
DB 235 PG 24

294.58'
N55°27'59"W

71.05'
S55°4'35"W


EIP

NAD 83

RALPH WHITEHEAD ASSOCIATES
CONSULTING ENGINEERS
P.O. BOX 35624
CHARLOTTE, NORTH CAROLINA 28235

PROJECT REFERENCE NO. R-2616 A&B
SHEET NO. 19
RW SHEET NO.

ROADWAY DESIGN ENGINEER
HYDRAULICS ENGINEER




09-MAY-2006 08:01
r:\roadway\proj\2616-rdy-psh20.dgn


REVISIONS	
3/24/06	ADDED C/A BREAK

THIS IS A PARTIAL CONTROLLED ACCESS PROJECT WITH
ACCESS BEING LIMITED TO ONE ENTRANCE PER PROPERTY

PROPERTIES WITH GREATER THAN 200' OF FRONTAGE
MAY RECEIVE ADDITIONAL ACCESS POINTS



PROJECT REFERENCE NO.		SHEET NO.	
R-2616 AMB		20	
RW SHEET NO.			
ROADWAY DESIGN ENGINEER		HYDRAULICS ENGINEER	
[REDACTED]		[REDACTED]	



SEE SHEET 63 FOR -L- PROFILE.

REVISIONS

3/24/06
PARCEL 45 NAME CHANGE
PARCEL 44 REMOVED THE LABEL & ADDED C/A BREAK
PARCEL 46 NAME CHANGE & ADDED C/A BREAK

THIS IS A PARTIAL CONTROLLED ACCESS PROJECT WITH
ACCESS BEING LIMITED TO ONE ENTRANCE PER PROPERTY
SEE
PROPERTIES WITH GREATER THAN 200' OF FRONTAGE
MAY RECEIVE ADDITIONAL ACCESS POINTS



RALPH WHITEHEAD ASSOCIATES
CONSULTING ENGINEERS
 P.O. BOX 35624
 CHARLOTTE, NORTH CAROLINA 28233


PROJECT REFERENCE NO.	SHEET NO.
D-2414-ADD	21

RAW SHEET NO.

ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
----------------------------	------------------------

PREMIER ART PLANS
 100% COTTON
 100% COTTON

	5" MONOLITHIC ISLAND
	FULL DEPTH PAVED SHOULDER
	PAVEMENT REMOVAL
	PAVING STONES



SEE SHEET 64 FOR -L- PROFILE.
SEE SHEET 90 FOR -Y6- & -Y7- PROFILE.

8/17/99

09-MAY-2006 08:02 2616.rdy.psh22.dgn
\$3\$8\$US\$RMANC\$3\$

REVISIONS	
3/24/06 PARCEL 52 PARCEL 54	NAME CHANGE & INCREASED DRIVE TO 32' ADDED CA BREAK


RALPH WHITEHEAD ASSOCIATES
CONSULTING ENGINEERS
P.O. BOX 35624
CHARLOTTE, NORTH CAROLINA 28235

PROJECT REFERENCE NO.		SHEET NO.	
R-2616 A&B		22	
RW SHEET NO.			
ROADWAY DESIGN ENGINEER		HYDRAULICS ENGINEER	
			

- 5' MONOLITHIC ISLAND
- FULL DEPTH PAVED SHOULDER
- PAVEMENT REMOVAL
- PAVING STONES

THIS IS A PARTIAL CONTROLLED ACCESS PROJECT WITH
ACCESS BEING LIMITED TO ONE ENTRANCE PER PROPERTY

PROPERTIES WITH GREATER THAN 200' OF FRONTAGE
MAY RECEIVE ADDITIONAL ACCESS POINTS



SEE SHEET 65 FOR -L- PROFILE.

8/17/99

REVISIONS

3/24/06
PARCEL 57 INCREASED DRIVE WIDTH TO 25'

THIS IS A PARTIAL CONTROLLED ACCESS PROJECT WITH
ACCESS BEING LIMITED TO ONE ENTRANCE PER PROPERTY
PROPERTIES WITH GREATER THAN 200' OF FRONTAGE
MAY REQUEST ADDITIONAL ACCESS POINTS



RALPH WHITEHEAD ASSOCIATES
CONSULTING ENGINEERS
P.O. BOX 35624
CHARLOTTE, NORTH CAROLINA 28235


PROJECT REFERENCE NO. SHEET NO.

R-2616 A&B 23

RAW SHEET NO.




ROADWAY DESIGN ENGINEER HYDRAULICS ENGINEER

5' MONOLITHIC ISLAND
FULL DEPTH PAVED SHOULDER
PAVEMENT REMOVAL



MATCHLINE -L- STA. 276+00.00 SEE SHEET 22

MATCHLINE -L- STA. 290+00.00 SEE SHEET 24



PLAN VIEW
ROCK INLET SILL
SCALE: NTS

- NOTES:
1. ALL STONES ARE TO BE STRUCTURE STONE.
 2. GAPS BETWEEN BOULDERS SHALL BE MINIMIZED BY FITTING BOULDERS TOGETHER, PLUGGING WITH STRUCTURE STONE CLASS A AND NO. 87 AND LINING WITH FILTER FABRIC.
 3. DIMENSIONS AND SLOPES MAY BE ADJUSTED TO FIT BY THE ENGINEER.
 4. A DOUBLE FOOTER BOULDER SHALL BE UTILIZED IN SAND BED MATERIAL.
 5. FOOTER BOULDERS AND SILL BOULDERS SHALL BE NATIVE STONE OR SHOT ROCK, CUBICAL OR RECTANGULAR IN NATURE.
 6. ACCEPTABLE BOULDERS SHALL HAVE THE FOLLOWING MINIMUM DIMENSIONS: 3' X 2' X 1'.

SEE SHEET 66 FOR -L- PROFILE.

09-MAY-2006 08:02
\\p0000000\p0000000\2616-rdy-pah23.dgn
\$\$\$\$\$USER\$\$\$\$\$

8/17/99

REVISIONS

3/24/06
PARCEL 57
PARCEL 61
PARCEL 59
PARCEL 63
PARCEL 63A
ADDED CA BREAK LT. OF STA. 298+30
NAME CHANGE
PARCEL NO. CHANGE
NAME CHANGE
NAME & PARCEL NO. ADDITION

THIS IS A PARTIAL CONTROLLED ACCESS PROJECT WITH
ACCESS BEING LIMITED TO ONE ENTRANCE PER PROPERTY

PROPERTIES WITH GREATER THAN 200' OF FRONTAGE
MAY REQUEST ADDITIONAL ACCESS POINTS

W RALPH WHITEHEAD ASSOCIATES
CONSULTING ENGINEERS
P.O. BOX 35624
CHARLOTTE, NORTH CAROLINA 28335


PROJECT REFERENCE NO.		SHEET NO.
R-2616 A&B		24
RW SHEET NO.		
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER	

5' MONOLITHIC ISLAND
FULL DEPTH PAVED SHOULDER
PAVEMENT REMOVAL

MATCHLINE -L- STA. 290 + 00.00 SEE SHEET 23

MATCHLINE -L- STA. 304 + 00.00 SEE SHEET 25


09-MAY-2006 08:02_616_rdy_psh24.dgn
R:\PROJECTS\2006\05\09\050524\616.dgn



SEE SHEET 67 FOR -L- PROFILE.


REVISIONS	
32406 PARCEL 63	NAME CHANGE & PROP. LINE ADDITION

THIS IS A PARTIAL CONTROLLED ACCESS PROJECT WITH
ACCESS BEING LIMITED TO ONE ENTRANCE PER PROPERTY
PROPERTIES WITH GREATER THAN 300' OF FRONTAGE
MAY RECEIVE ADDITIONAL ACCESS POINTS



PROJECT REFERENCE NO.		SHEET NO.	
R-2616 A&B		25	
RAW SHEET NO.			
ROADWAY DESIGN ENGINEER		HYDRAULICS ENGINEER	
[REDACTED]		[REDACTED]	

	5' MONOLITHIC ISLAND
	FULL DEPTH PAVED SHOULDER
	PAYEMENT REMOVAL



SEE SHEET 68 FOR -L- PROFILE.

8/17/99
09-MAY-2006 08:03
C:\WORK\2616-RD\2616.dgn
\$\$\$\$\$USERNAME\$\$\$\$\$

REVISIONS

THIS IS A PARTIAL CONTROLLED ACCESS PROJECT WITH
ACCESS BEING LIMITED TO ONE ENTRANCE PER PROPERTY

PROPERTIES WITH GREATER THAN 300' OF FRONTAGE
MAY RECEIVE ADDITIONAL ACCESS POINTS



- 5' MONOLITHIC ISLAND
- FULL DEPTH PAVED SHOULDER
- PAVEMENT REMOVAL
- PAVING STONES

W RALPH WHITEHEAD ASSOCIATES
CONSULTING ENGINEERS
P.O. BOX 35624
CHARLOTTE, NORTH CAROLINA 28235

PROJECT REFERENCE NO. R-2616 A&B		SHEET NO. 26	
RW SHEET NO.		HYDRAULICS ENGINEER	
ROADWAY DESIGN ENGINEER			

MATCHLINE -L- STA. 318 + 00.00 SEE SHEET 25

MATCHLINE -L- STA. 332 + 00.00 SEE SHEET 27



SEE SHEET 69 FOR -L- PROFILE.
SEE SHEET 89 FOR -Y8- PROFILE.
SEE SHEET 91 FOR -Y9- PROFILE.

8/17/99

REVISIONS

THIS IS A PARTIAL CONTROLLED ACCESS PROJECT WITH ACCESS BEING LIMITED TO ONE ENTRANCE PER PROPERTY

PROPERTIES WITH GREATER THAN 200' OF FRONTAGE MAY RECEIVE ADDITIONAL ACCESS POINTS


W RALPH WHITEHEAD ASSOCIATES
CONSULTING ENGINEERS
P.O. BOX 35624
CHARLOTTE, NORTH CAROLINA 28235

PROJECT REFERENCE NO.		SHEET NO.
R-2616 A&M		28
R/W SHEET NO.		
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER	

5' MONOLITHIC ISLAND
FULL DEPTH PAVED SHOULDER
PAVEMENT REMOVAL

MATCHLINE -L- STA. 346 + 00.00 SEE SHEET 27

MATCHLINE -L- STA. 360 + 00.00 SEE SHEET 29



SEE SHEET T1 FOR -L- PROFILE.

8/17/99

REVISIONS

3/24/06
PARCEL 91 NAME CHANGE
PARCEL 92 NAME CHANGE

THIS IS A PARTIAL CONTROLLED ACCESS PROJECT WITH
ACCESS BEING LIMITED TO ONE ENTRANCE PER PROPERTY

PROPERTIES WITH GREATER THAN 200' OF FRONTAGE
MAY RECEIVE ADDITIONAL ACCESS POINTS



RALPH WHITEHEAD ASSOCIATES
CONSULTING ENGINEERS
P.O. BOX 35624
CHARLOTTE, NORTH CAROLINA 28235

PROJECT REFERENCE NO. SHEET NO.

R-2616 A&B

29

R/W SHEET NO.


ROADWAY DESIGN
ENGINEER

HYDRAULICS
ENGINEER

8" MONOLITHIC ISLAND
FULL DEPTH PAVED SHOULDER
PAVEMENT REMOVAL

MATCHLINE -L- STA. 360 + 00.00 SEE SHEET 28

MATCHLINE -L- STA. 374 + 00.00 SEE SHEET 30



SEE SHEET 72 FOR -L- PROFILE.
SEE SHEET xx FOR -Y2- PROFILE.
SEE SHEET xx FOR -Y2- PROFILE.

09-MAY-2006 09:03
R-2616.rdy_psh29.dgn
R-2616.dwg

8/17/99

REVISIONS

3/24/06
PARCEL 91 NAME CHANGE
PARCEL 92A NAME CHANGE, ADDITIONAL PROP. LINE, & ADDED C/A BREAK

THIS IS A PARTIAL CONTROLLED ACCESS PROJECT WITH
ACCESS BEING LIMITED TO ONE ENTRANCE PER PROPERTY


PROPERTIES WITH GREATER THAN 300' OF FRONTAGE
MAY RECEIVE ADDITIONAL ACCESS POINTS



RALPH WHITEHEAD ASSOCIATES
CONSULTING ENGINEERS
P.O. BOX 33624
CHARLOTTE, NORTH CAROLINA 28235


PROJECT REFERENCE NO. R-2616 A&B SHEET NO. 30

RDW SHEET NO. ROADWAY DESIGN ENGINEER HYDRAULICS ENGINEER




MATCHLINE -L- STA 374+00.00 SEE SHEET 29

MATCHLINE -L- STA 388+00.00 SEE SHEET 31



SEE SHEET 73 FOR -L- PROFILE.




8/17/99

REVISIONS

W RALPH WHITEHEAD ASSOCIATES
CONSULTING ENGINEERS
P.O. BOX 35624
CHARLOTTE, NORTH CAROLINA 28235


PROJECT REFERENCE NO.		SHEET NO.
R-2616 A&B		33
RW SHEET NO.		
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER	

- 8" MONOLITHIC ISLAND
- FULL DEPTH PAVED SHOULDER
- PAVEMENT REMOVAL



MATCHLINE -L- STA. 416 + 00.00 SEE SHEET 32

MATCHLINE -L- STA. 430 + 00.00 SEE SHEET 34



THIS IS A PARTIAL CONTROLLED ACCESS PROJECT WITH
ACCESS BEING LIMITED TO ONE ENTRANCE PER PROPERTY

PROPERTIES WITH GREATER THAN 100' OF FRONTAGE
MAY RECEIVE ADDITIONAL ACCESS POINTS

SEE SHEET 76 FOR -L- PROFILE.

09 MAY 2006 08:04
C:\PROJECTS\2616-RD\2616-RD.dwg
\$\$\$\$\$USER\$\$(1)\$\$\$\$\$

8/17/99

REVISIONS

THIS IS A PARTIAL CONTROLLED ACCESS PROJECT WITH
ACCESS BEING LIMITED TO ONE ENTRANCE PER PROPERTY


PROPERTIES WITH GREATER THAN 200' OF FRONTAGE
MAY RECEIVE ADDITIONAL ACCESS POINTS



RALPH WHITEHEAD ASSOCIATES
CONSULTING ENGINEERS
P.O. BOX 35624
CHARLOTTE, NORTH CAROLINA 28235

PROJECT REFERENCE NO.		SHEET NO.
R-2616 A&B		34
R/W SHEET NO.		
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER	

8" MONOLITHIC ISLAND
FULL DEPTH PAVED SHOULDER
PAVEMENT REMOVAL



SEE SHEET 77 FOR -L- PROFILE.

3/24/06
PARCEL 121 REDUCED RW AT -Y14-
PARCEL 122 REDUCED RW AND CA AT -Y14-
PARCEL 191 REDUCED RW AND CA AT -Y14-
PARCEL 123 ADDED CA BREAK
ELIMINATED PROPOSED CROSS DRAIN PIPE AT -Y14- STA. 13+70


THIS IS A PARTIAL CONTROLLED ACCESS PROJECT WITH
ACCESS BEING LIMITED TO ONE ENTRANCE PER PROPERTY

PROPERTIES WITH GREATER THAN 200' OF FRONTAGE
MAY RECEIVE ADDITIONAL ACCESS POINTS

 RALPH WHITEHEAD ASSOCIATES
CONSULTING ENGINEERS
P.O. BOX 35624
CHARLOTTE, NORTH CAROLINA 28235

PROJECT REFERENCE NO.		SHEET N.	
R-2616 A&B		35	
RW / SHEET NO.			
ROADWAY DESIGN ENGINEER		HYDRAULICS ENGINEER	
			

	5' MONOLITHIC ISLAND
	FULL DEPTH PAVED SHOULDER
	PAVEMENT REMOVAL



SEE SHEET 78 FOR -L- PROFILE.
SEE SHEET 91 FOR -Y14- PROFILE.


REVISIONS



RALPH WHITEHEAD ASSOCIATES
CONSULTING ENGINEERS
P.O. BOX 35624
CHARLOTTE, NORTH CAROLINA 28235

PROJECT REFERENCE NO.		SHEET NO.	
R-2616 A&B		36	
RW SHEET NO.			
ROADWAY DESIGN ENGINEER		HYDRAULICS ENGINEER	
[Redacted Signature]		[Redacted Signature]	

	5' MONOLITHIC ISLAND
	FULL DEPTH PAVED SHOULDER
	PAVEMENT REMOVAL



THIS IS A PARTIAL CONTROLLED ACCESS PROJECT WITH
ACCESS BEING LIMITED TO ONE ENTRANCE PER PROPERTY

PROPERTIES WITH GREATER THAN 200' OF FRONTAGE
MAY RECEIVE ADDITIONAL ACCESS POINTS

SEE SHEET 79 FOR -L- PROFILE.

8/17/99
03-MAY-2006 08:05
616.rdy.psh37.dgn
3/24/06
PARCEL 136A
ADDITIONAL NAME & PROP. LINE

REVISIONS

3/24/06
PARCEL 136A
ADDITIONAL NAME & PROP. LINE

THIS IS A PARTIAL CONTROLLED ACCESS PROJECT WITH
ACCESS BEING LIMITED TO ONE ENTRANCE PER PROPERTY


PROPERTIES WITH GREATER THAN 200' OF FRONTAGE
MAY RECEIVE ADDITIONAL ACCESS POINTS

W
RALPH WHITEHEAD ASSOCIATES
CONSULTING ENGINEERS
P.O. BOX 35624
CHARLOTTE, NORTH CAROLINA 28235

PROJECT REFERENCE NO.		SHEET NO.
R-2616 A&B		37
RW SHEET NO.		
ROADWAY DESIGN ENGINEER		HYDRAULICS ENGINEER

8' MONOLITHIC ISLAND
FULL DEPTH PAVED SHOULDER
PAVEMENT REMOVAL

NAD 83



NOTE TO CONTRACTOR:
THIS WELL IS REQUIRED
TO BE PROTECTED
FROM DAMAGES BY ANY
CONSTRUCTION ACTIVITIES

CURVE L-12		
PIs Sta 466+33.31	PI Sta 469+22.60	PIs Sta 472+11.77
Es = 0' 45' 00.0"	Δ = 3' 20' 18.2" (LT)	Es = 0' 45' 00.0"
Ls = 200.00'	D = 0' 45' 00.0"	Ls = 200.00'
LT = 133.33'	T = 222.62'	LT = 133.33'
ST = 66.67'	L = 445.12'	ST = 66.67'
	R = 7.639.44'	
	SE = 0.03 FT/FT	

CURVE L-13		
PIs Sta 474+78.43	PI Sta 477+61.49	PIs Sta 480+44.44
Es = 0' 45' 00.0"	Δ = 3' 14' 42.1" (RT)	Es = 0' 45' 00.0"
Ls = 200.00'	D = 0' 45' 00.0"	Ls = 200.00'
LT = 133.33'	T = 216.39'	LT = 133.33'
ST = 66.67'	L = 432.67'	ST = 66.67'
	R = 7.639.44'	
	SE = 0.03 FT/FT	

SEE SHEET 80 FOR -L- PROFILE.


09-MAY-2006 08:05
...:\roadway\proj\2616-rdy-psh38.dgn

THIS IS A PARTIAL CONTROLLED ACCESS PROJECT WITH
ACCESS BEING LIMITED TO ONE ENTRANCE PER PROPERTY

PROPERTIES WITH GREATER THAN 300' OF FRONTAGE
MAY RECEIVE ADDITIONAL ACCESS POINTS

	RALPH WHITEHEAD ASSOCIATES CONSULTING ENGINEERS P.O. BOX 35624 CHARLOTTE, NORTH CAROLINA 28235	PROJECT REFERENCE NO. R-2616 A&B	SHEET NO. 38
	R/W SHEET NO.		
	ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER	

	5" MONOLITHIC ISLAND
	FULL DEPTH PAVED SHOULDER
	PAVEMENT REMOVAL



8/17/99 3/24/06 PARCEL 192 NAME CHANGE

REVISIONS

3/24/06
PARCEL 192 NAME CHANGE

THIS IS A PARTIAL CONTROLLED ACCESS PROJECT WITH
ACCESS BEING LIMITED TO ONE ENTRANCE PER PROPERTY

PROPERTIES WITH GREATER THAN 200' OF FRONTAGE
MAY REQUEST ADDITIONAL ACCESS POINTS

W RALPH WHITEHEAD ASSOCIATES
CONSULTING ENGINEERS
P.O. BOX 35624
CHARLOTTE, NORTH CAROLINA 28235


PROJECT REFERENCE NO.		SHEET NO.
R-2616 A&B		39
RAW SHEET NO.		
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER	

5' MONOLITHIC ISLAND
FULL DEPTH PAVED SHOULDER
PAVEMENT REMOVAL

NAD 83

MATCHLINE -L- STA. 500 + 00.00 SEE SHEET 38

MATCHLINE -L- STA. 514 + 00.00 SEE SHEET 40



SEE SHEET 82 FOR -L- PROFILE.
SEE SHEET 90 FOR -DRI- PROFILE

8/17/99

REVISIONS

THIS IS A PARTIAL CONTROLLED ACCESS PROJECT WITH ACCESS BEING LIMITED TO ONE ENTRANCE PER PROPERTY. PROPERTIES WITH GREATER THAN 200' OF FRONTAGE MAY RECEIVE ADDITIONAL ACCESS POINTS.

W RALPH WHITEHEAD ASSOCIATES
CONSULTING ENGINEERS
P.O. BOX 35624
CHARLOTTE, NORTH CAROLINA 28235

PROJECT REFERENCE NO.		SHEET NO.
R-2616 A&B		40
RW SHEET NO.		
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER	



5' MONOLITHIC ISLAND
FULL DEPTH PAVED SHOULDER
PAYEMENT REMOVAL

CURVE Y16-1
PI Sta 7+50.81
 $\Delta = 24^\circ 59' 18.5" (RT)$
 $D = 10' 00' 00.0"$
 $T = 126.96'$
 $L = 249.88'$
 $R = 572.96'$
 $SE = 0.05 \text{ FT/FT}$

NAD 83

MATCHLINE -L- STA. 514 + 00.00 SEE SHEET 39

MATCHLINE -L- STA. 528 + 00.00 SEE SHEET 41



SEE SHEET 83 FOR -L- PROFILE.
SEE SHEET 92 FOR -Y16- PROFILE.

03-MAY-2006 08:05
2616.rdy.psh40.dgn
3388 USER:RAC

09-MAY-2006 08:05
r:\roadway\proj\2616_rdy-psh41.dgn
\$\$\$\$\$USERNAME\$\$\$\$\$

REVISIONS

THIS IS A PARTIAL CONTROLLED ACCESS PROJECT WITH
ACCESS BEING LIMITED TO ONE ENTRANCE PER PROPERTY


PROPERTIES WITH GREATER THAN 200' OF FRONTAGE
MAY RECEIVE ADDITIONAL ACCESS POINTS



RALPH WHITEHEAD ASSOCIATES
CONSULTING ENGINEERS
P.O. BOX 35624
CHARLOTTE, NORTH CAROLINA 28235

PROJECT REFERENCE NO.		SHEET NO.	
R-2416 AM		41	
RW SHEET NO.			
ROADWAY DESIGN ENGINEER		HYDRAULICS ENGINEER	
[REDACTED]			

	5' MONOLITHIC ISLAND
	FULL DEPTH PAVED SHOULDER
	PAVEMENT REMOVAL



SEE SHEET 84 FOR -L- PROFILE.
SEE SHEET 92 FOR -Y17- PROFILE.

REVISIONS

32406
PARCEL 171A PARCEL NO. ADDITION

THIS IS A PARTIAL CONTROLLED ACCESS PROJECT WITH
ACCESS BEING LIMITED TO ONE ENTRANCE PER PROPERTY

PROPERTIES WITH GREATER THAN 200' OF FRONTAGE
MAY RECEIVE ADDITIONAL ACCESS POINTS




RALPH WHITEHEAD ASSOCIATES
CONSULTING ENGINEERS
P.O. BOX 35624
CHARLOTTE, NORTH CAROLINA 28235

PROJECT REFERENCE NO.	SHEET NO.
R-2616 A&B	42
RW SHEET NO.	
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
	

	5' MONOLITHIC ISLAND
	FULL DEPTH PAVED SHOULDER
	PAYEMENT REMOVAL

MATCHLINE -1- STA. 542+00.00 SEE SHEET 41



MATCHLINE -L- STA. 556 + 00.00 SEE SHEET 43

Pls Sta 555+08.88 $\Theta_s = 0^\circ 15' 00.0''$ Ls = 100.00' LT = 66.67' ST = 33.33'	Pl Sta 556+80.36 $\Delta = 1^\circ 22' 52.9''$ (LT) $D = 0^\circ 30' 00.0''$ L = 276.27' T = 138.14' R = 11,459.16' SE = 0.02 FT/FT	Pls Sta 558+51.82 $\Theta_s = 0^\circ 15' 00.0''$ Ls = 100.00' LT = 66.67' ST = 33.33'
--	---	--

SEE SHEET 85 FOR -L- PROFILE.

8/17/99

09-MAY-2006 08:05:16 [E:\rdy\psht43.dgn]
5588156-ROADWAY.DWG

REVISIONS

32406
PARCEL 171A PARCEL NO. ADDITION

THIS IS A PARTIAL CONTROLLED ACCESS PROJECT WITH
ACCESS BEING LIMITED TO ONE ENTRANCE PER PROPERTY

PROPERTIES WITH GREATER THAN 50% OF FRONTAGE
MAY RECEIVE ADDITIONAL ACCESS POINTS


W RALPH WHITEHEAD ASSOCIATES
CONSULTING ENGINEERS
P.O. BOX 35624
CHARLOTTE, NORTH CAROLINA 28235

PROJECT REFERENCE NO.		SHEET NO.
R-2616 A&B		43
RW SHEET NO.		
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER	

	5' MONOLITHIC ISLAND
	FULL DEPTH PAVED SHOULDER
	PAVEMENT REMOVAL

MATCHLINE -L- STA. 556 + 00.00 SEE SHEET 42

MATCHLINE -L- STA. 568 + 00.00 SEE SHEET 44



CURVE L-14

Pls Sta 555+08.88	Pl Sta 556+80.36	Pls Sta 558+51.82
Os = 0' 15' 00.0"	Δ = 1' 22' 52.9" (LT)	Os = 0' 15' 00.0"
Ls = 100.00'	D = 0' 30' 00.0"	Ls = 100.00'
LT = 66.67'	L = 276.27'	LT = 66.67'
ST = 33.33'	T = 138.14'	ST = 33.33'
	R = 11,459.16'	
	SE = 0.02 FT/FT	

SEE SHEET 86 FOR -L- PROFILE.

8/17/99

03-MAY-2006 08:05 616.rdy-ph44.dgn
\$\$\$\$\$US601A.DWG\$\$\$\$\$


W RALPH WHITEHEAD ASSOCIATES
CONSULTING ENGINEERS
P.O. BOX 34624
CHARLOTTE, NORTH CAROLINA 28235

PROJECT REFERENCE NO. R-2616 A&B		SHEET NO. 44	
RW SHEET NO.		HYDRAULICS ENGINEER	
ROADWAY DESIGN ENGINEER			

9" MONOLITHIC ISLAND
FULL DEPTH PAVED SHOULDER
PAVEMENT REMOVAL

THIS IS A PARTIAL CONTROLLED ACCESS PROJECT WITH ACCESS BEING LIMITED TO ONE ENTRANCE PER PROPERTY
PROPERTIES WITH GREATER THAN 300' OF FRONTAGE MAY RECEIVE ADDITIONAL ACCESS POINTS

MARION LEE, HEIRS
MARGARET LEE, HEIRS
AND OTHERS
WB 8 PG 038




CURVE Y18-1
PI Sta 7+76.58
 $\Delta = 31^\circ 46' 22.4''$ (RT)
D = 959' 59.9"
L = 317.73'
T = 163.07'
R = 572.96'
SE = 0.08 FT/FT

BL-88
-BL- 568+13.15 PINC=
-L- 574+71.22, 14.06' RT

NCCS "MARION"
-BL- 565+82.65 PINC

BL-87
-BL- 565+29.69 PINC =
-BY20- 13+64.97 POT=
-L- 571+91.12, 56.68' RT

-L- POT Sta. 570+04.90=
-Y18- POT Sta. 10+00.00



CURVE L-15
PIs Sta 571+70.67
 $\Theta_s = 0^\circ 45' 00.0''$
Ls = 200.00'
LT = 133.33'
ST = 66.67'
 $\Delta = 4^\circ 57' 09.5''$ (RT)
D = 0' 45' 00.0"
T = 330.38'
L = 660.35'
R = 7,639.44'
SE = 0.03 FT/FT

SPIRAL EOP4-1
PIs Sta 575+43.78
 $\Theta_s = 0^\circ 45' 08.2''$
Ls = 200.00'
LT = 133.33'
ST = 66.67'

CURVE L-16
PI Sta 581+37.94
 $\Theta_s = 2^\circ 24' 07.5''$ (LT)
D = 0' 30' 00.0"
Ls = 240.24'
LT = 133.33'
ST = 66.67'
R = 11,459.16'

SPIRAL EOP3-1
PIs Sta 579+38.83
 $\Theta_s = 0^\circ 44' 51.9''$
Ls = 200.00'
LT = 133.33'
ST = 66.67'

CURVE EOP3-2
PIs Sta 581+58.83
 $\Theta_s = 0^\circ 19' 30.0''$
Ls = 130.00'
LT = 86.67'
ST = 43.33'

CURVE EOP3-1
PIs Sta 584+33.03
 $\Theta_s = 2^\circ 18' 30.1''$ (LT)
D = 0' 30' 00.0"
Ls = 461.67'
LT = 230.87'
R = 11,459.16'
SE = 0.02 FT/FT



SEE SHEET 87 FOR -L- PROFILE.
SEE SHEET 92 FOR -18- PROFILE.

THIS IS A PARTIAL CONTROLLED ACCESS PROJECT WITH
ACCESS BEING LIMITED TO ONE ENTRANCE PER PROPERTY

PROPERTIES WITH GREATER THAN 200' OF FRONTAGE
MAY RECEIVE ADDITIONAL ACCESS POINTS

PROJECT REFERENCE NO.	SHEET NO.
R-2616 A&B	45
R/W SHEET NO.	
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
[Redacted Signature Area]	

	5" MONOLITHIC ISLAND
	FULL DEPTH PAVED SHOULDER
	PAVEMENT REMOVAL



END CONSTRUCTION PROJ.R-2616 A&B
-L- STA. 593+82.00





SEE SHEET 88 FOR -L- PROFILE.

8/17/99

REVISIONS

4-06-06
REMOVED PROP. RW LINE
REMOVED PROP. RW LINE
PARCEL 34
PARCEL 182

09-MAY-2006 08:06
R:\projects\2616\psh46.dgn
R:\projects\2616\psh46.dgn
R:\projects\2616\psh46.dgn



R RALPH WHITEHEAD ASSOCIATES
CONSULTING ENGINEERS
P.O. BOX 35424
CHARLOTTE, NORTH CAROLINA 28235

PROJECT REFERENCE NO.		SHEET NO.
R-2616 A&B		46
RW SHEET NO.		
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER	

3" MONOLITHIC ISLAND
FULL DEPTH PAVED SHOULDER
PAYMENT REMOVAL

THIS IS A PARTIAL CONTROLLED ACCESS PROJECT WITH ACCESS BEING LIMITED TO ONE ENTRANCE PER PROPERTY. PROPERTIES WITH GREATER THAN 300' OF FRONTAGE MAY RECEIVE ADDITIONAL ACCESS POINTS.
SEE SHEET 90 FOR -Y6- PROFILE.
SEE SHEET 90 FOR -Y7- PROFILE.
SEE SHEET 92 FOR -Y18- PROFILE.

