



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

ROY COOPER
GOVERNOR

J. ERIC BOYETTE
SECRETARY

February 26, 2021

U.S. Army Corps of Engineers
Raleigh Regulatory Field Office
3331 Heritage Trade Drive, Suite 105
Wake Forest, NC 27587

NCDEQ Water Resources
1611 Mail Service Center
Raleigh, NC 27699-1611

ATTN: Mr. Eric Alsmeyer and Mr. Rob Ridings

Subject: Request for Modification of the Phased Section 404 Individual Permit and Section 401 Individual Water Quality Certification, Neuse River Riparian Buffer Authorization for the construction of the Triangle Expressway Southeast Extension from NC-55 Bypass in Apex to I-40, Wake and Johnston Counties. TIP Nos. R-2721, R-2828, and R-2829. Debit \$570 from WBS 376731.TA2.

Reference: USACE Section 404 Authorization SAW-2009-02240, issued October 24, 2019, modified February 4, 2020, and corrected February 7, 2020, and modified April 30, 2020 and January 7, 2021.

NCDWR Water Quality Certification Number 4179 and Neuse River Riparian Buffer Authorization, issued February 15, 2019, modified January 30, 2020, April 20, 2020, June 1, 2020, and December 29, 2020.

Dear Sir:

As you are aware, the North Carolina Department of Transportation (NCDOT) applied for a phased Section 404 Individual Permit, Section 401 Individual Water Quality Certification (WQC), Neuse River Riparian Buffer Authorization, Non-404 Jurisdictional Wetlands and Waters Permit for the subject project in September 2018. The project, also known as Complete 540, encompasses three NCDOT Transportation Improvement Plan (TIP) projects: R-2721 (NC-55 Bypass to US-401), R-2828 (east of US-401 to I-40 Interchange) and R-2829 (east of I-40 to US 64/264). Revised permit applications were submitted in February 2019 and the NCDWR 401 and USACE 404 Permits were issued in February and October of 2019. Additionally, NCDOT received a modified 401 WQC for the Complete 540 Project on January 30, 2020, April 23, 2020, June 1, 2020, and December 29, 2020 from the NC Division of Water Resources (NCDWR) and a revised Department of the Army authorization #SAW-2009-02240 on February 7, 2020, April 29, 2020, and January 7, 2021.

Mailing Address:
NC DEPARTMENT OF TRANSPORTATION
TURNPIKE AUTHORITY
1578 MAIL SERVICE CENTER
RALEIGH NC 27699-1578

TELEPHONE: 919-707-2700
FAX: 919-715-551
Customer Service: 1-877-3684968

WEBSITE: NCDOT.GOV

Location:
1 SOUTH WILMINGTON STREET
RALEIGH NC, 27601

This letter is a request to modification on four sites of the R-2828 section of the Complete 540 project. Sites 32, 48, 49, and a new site (Site 91) are being modified.

Permit Site 32:

This double box culvert near Jordan Road has been completed, however, before the wing wall on the inlet side could be finished, excessive rain events caused the stream banks at the inlet at the wing wall to washout. The washout has required the installation of Class II rip rap on the bank. This work has been approved by the USACE and DWR and has already occurred. The rip rap has been placed below the original high-water mark; however, it does not extend across the channel. The bank is at about a 2:1 slope now that it is completed. As this bank stabilization exceeds the limits of the approved permanent impact, a permit modification is requested.

- Permit Site 32 (Permit Drawing 74 and 75 of 171, Plan Sheet 20)
 - Additional rip rap bank stabilization:
 - Increase of 22 LF of bank stabilization impact.

Permit Sites 48 & 49:

Since the 4C meeting and receiving the final permit drawings, Lane-Blythe Joint Venture (LBJV) enlisted a trestle designer to fully design the trestle to include girder erection/sequencing, crane placement during girder erections and to improve overall safety of operations utilizing the trestle. The original trestle plan placed the trestle on the south side of the two bridges west of Swift Creek and transitioned to between the bridges east of Swift Creek (Attachment A). This bend in the trestle posed significant concerns regarding the safe delivery and erection of the girders for the proposed bridge.

The new design removes the bend with a straight haul road which results in a safer delivery and erection of the bridge girders, a depiction of which is provided in Attachment B. The new haul road design is provided in revised Plan Sheet 29, but there is no change in jurisdictional impacts. All girder deliveries will be along this straightened portion of the trestle. This proposed design improves safety related to the delivery of other related bridge materials, that include formwork and reinforcing steel and removes any turning movements for concrete deliveries. This proposed design also eliminates permitted disturbance between the bridges east of Swift Creek.

The proposed design provides the following benefits:

- The trestle crossing is more perpendicular to Swift Creek.
- This placement decreased the required clear span width of Swift Creek from 110 feet to 85 feet; thus, minimizing the potential of any issues related to the spanning of Swift Creek.
- The trestle fingers were designed with an increased distance from top of existing bank from the required minimum 10 feet to edge of the trestle pile to a minimum of 15 feet. This distance will be field verified prior to placement of the trestle pile and can be adjusted, if needed, to accommodate this requirement.

As previously committed, this trestle will not be used for the conveyance on any earthen material across Swift Creek. In addition, 10" x 10" timbers will be placed longitudinally on each edge of the trestle to act as a curb or stop which will further minimize the potential of material getting into Swift Creek and the adjacent Underhill Mitigation site.

The new trestle design will result in the following changes in permitted impacts:

- Permit Site 48 (Buffer Drawing 20 of 42, Plan Sheet 28)
 - Alteration of work trestle configuration:
 - Increase of 2,160 square feet (Sq. Ft.) of Zone 1 Buffer Impacts
 - Increase of 1,168 Sq. Ft. of Zone 2 Buffer Impacts
- Permit Site 48 (Permit Drawing 105 and 106 of 171, Plan Sheet 28)
 - Alteration of work trestle configuration:
 - Increase of 0.014 acre of Hand Clearing Impacts
- Permit Site 49 (Permit Drawing 105 and 106 of 171, Plan Sheet 28)
 - Alteration of work trestle configuration:
 - Increase of 0.06 acre of Hand Clearing Impacts

Permit Site 91:

During the design stage, a haul road was planned that traveled parallel to the project along Gentle Rain Drive, which is a little used dead-end road. The haul road then cuts over to the project area. This haul road is critical to the project. It is not only much safer by avoiding areas of high traffic volumes, but significantly decreases the haul route, thereby reducing emissions and expediting project construction. The original placement of the haul road considered jurisdictional features, but unbeknownst to the planner the mapping used to choose the route showed streams and associated riparian buffers, but not the complete wetland boundary of Wetland WED. The boundary for WED was not completely shown as it had been “clipped” to the original project area boundary. Thus, it continued just outside the project right-of-way. As a result, it was not until LBJV was performing due diligence for the haul road in January 2021 that it was realized the proposed haul road placement was through a wetland, as shown in Figure 1.

Three Oaks personnel investigated the area to determine a route that would avoid and minimize impacts to Wetland WED and other jurisdictional features. After the field investigation, it was determined that Wetland WED could be avoided but Stream SDQ, which runs between Gentle Rain Drive and the project, could not be completely avoided. However, a section of the stream was identified where there had been a crossing at some point in the past. Utilizing this crossing would minimize impacts as the vegetation here was noticeably younger, the stream was straighter, and the area had already been graded to a gentler slope. Based on this information, the haul road has been revised to cross at this area. The haul road width has been reduced to 40' at the stream crossing and associated riparian buffers, which is the minimum needed to accommodate a single off-road scraper. This crossing will result in

- Permit Site 91 (Permit Drawing 132 and 133 of 171, Plan Sheet 37)
 - Temporary crossing of Stream SDQ due to haul road

- 66 linear feet (LF) of Temporary Stream Impacts
- Permit Site 91 (Buffer Drawing 25 of 42, Plan Sheet 37)
 - Temporary crossing of Stream SDQ due to haul road
 - Increase of 4,000 Sq. Ft. of Zone 1 Buffer Impacts
 - Increase of 2,577 Sq. Ft. of Zone 2 Buffer Impacts

The haul road will be in place for 15 months. Upon removal, the stream will be restored to pre-existing conditions and the riparian buffers revegetated. No mitigation is proposed for the temporary stream impacts and the riparian buffers impacts are an allowable activity.

Revised Impacts Summary R-2828

Due to the changes described above for R-2828, the total project impacts will now be as listed below.

Revised Table 4. R-2828 Jurisdictional Resources Impacts

Impact Type	Riparian Wetlands Temp./ Perm. (ac)	Non-Riparian Wetlands Perm. (ac)	Isolated Wetlands (ac)	Ponds (ac)	Isolated Ponds (ac)	Streams (lf)			Riparian Buffer (sq ft) Zone 1/2
	Perm.	Temp.	Structure* Stab.						
Neuse River Basin (HUC 03020201)	4.80 / 19.49	0.07	0.25	8.32	n/a	16,820	1,702	2,065	1,182,975 / 719,806

*Structure stabilization is pipe, culvert, and bank stabilization.

Revised Table 19 has been modified to show the updated riparian buffer impacts and the amount that each total increased is noted in parenthesis below.

Revised Table 19. Riparian Buffer Impacts (sq ft)

Mitigation Requirement	Allowable with mitigation*	Allowable with mitigation**	Allowable^	Total Impacts^	Wetlands in Buffer^^	Impacts Requiring Mitigation
Zone 1 Impact	158,309 (0)	885,686 (0)	138,980 (6,160)	1,182,975 (6,160)	179,656 (0)	864,339 (0)
Zone 2 Impact	103,074 (0)	528,324 (0)	88,408 (3,745)	719,806 (3,745)	84,166 (0)	547,232 (0)

* Impacts other than Road Crossing. **Road Crossing, ^ Includes utility impacts, ^^ Allowable non-mitigable buffer impacts have been deducted from wetlands in buffers.

Compensatory Mitigation

As noted, none of the modifications require compensatory mitigation, so there are no changes to the previous tables.

REGULATORY APPROVALS

Section 404: We are requesting a modification to the USACE Permit Number SAW-2009-02240 Section 404 Individual Permit for the above-described activities.

Section 401: We are requesting a modification to the WQC Permit Number 4179 Section 401 Individual Water Quality Certification and the Neuse Riparian Buffer Authorization. We are providing this application to NCDEQ, for their approval. Authorization to debit the \$570.00 Permit Modification Fee from TIP No. R-2828/WBS 37673.1.TA2 is hereby given.

The individual permit modification package for the Complete 540 project (STIP Projects R-2721, R-2828, and R-2829) is available at <https://xfer.services.ncdot.gov/pdea/PermApps/>

Thank you for your assistance with this project. If you have any questions or need additional information, please contact Deanna Riffey at driffe@ncdot.gov or 919-707-6151.

Sincerely,



DocuSigned by:

Rodger Rochelle

2CF80ADB9B414F0...

Rodger Rochelle, P.E.
North Carolina Turnpike Authority
Chief Engineer

cc: NCDOT Permit Application Standard Distribution List



Prepared For:




Complete 540 TIP R-2828

Permit Modification #3
Proposed Haul Road

Wake & Johnston Counties, North Carolina


Date:	January 2021
Scale:	0 150 300 Feet
Job No.:	18-105
Drawn By:	NMSO
Checked By:	MGW

Figure
1




SECTION ALONG EASTBOUND WORK LINE

SECTION TAKEN AT RIGHT ANGLES TO END BENTS AND BENTS
EASTBOUND BRIDGE SHOWN, WESTBOUND BRIDGE SIMILAR




DESTINED BY: J. SHERMAN DATE: AUG 2018
DRAWN BY: C. MAYHAY DATE: AUG 2018
CHECKED BY: M. WAGNER DATE: AUG 2018.
DES. ENGINEER REC'D. DATE: X

Attachment B



PLAN



ELEVATION

STRUCTURE 10: DUAL BRIDGES ON -L- (NC-540)
OVER SWIFT CREEK

KCI ASSOCIATES OF NORTH CAROLINA, P.A.
9711 SOUTHERN PINE BLVD
SUITE A
CHARLOTTE, NC 28273
704-499-9452

WORK TRESTLE

STRUCTURE 10: DUAL BRIDGES ON -L- (NC-540)
OVER SWIFT CREEK

WAKE AND JOHNSTON CO., NC
NCDOT PROJECT NO. R-2828


KCI JOB #911906280
JOB REF. #C19-69.07

DES. BY :	CKD. BY :	DATE :	SCALE :
JMV	AMC	10/20	NONE

CONTRACT: C204197

TIP PROJECT: R-2828

09/08/99




STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS

WAKE & JOHNSTON COUNTY

STATE	STATE PROJECT REFERENCE NO.	Sheet No.	Total Sheets
N.C.	R-2828	1	
STATE PROJ. NO.	F.A. PROJ. NO.	DESCRIPTION	
35516.3.GV1	NHP-0540(043)	DESIGN-BUILD	
35516.2.3	NHP-0540(043)	R/W	
35516.2.TA1	NHP-0540(043)	R/W	


Permit Drawing Package
Last Revised on 02/16/21

END TIP PROJECT R-2828
END CONSTRUCTION
-L-STA. 968 + 50.00



WETLAND AND SURFACE WATER IMPACTS PERMIT

PACKAGE R-2828
DATE: FEBRUARY 16, 2021



CLEARING ON THIS PROJECT SHALL BE PERFORMED
TO THE LIMITS ESTABLISHED BY METHOD III.

THIS IS A CONTROLLED ACCESS PROJECT WITH
ACCESS BEING LIMITED TO INTERCHANGES.

GRAPHIC SCALES



DESIGN DATA

ADT 2018 = NA
ADT 2040 = 53,400
DHV = 12 %
D = 65 %
T = 11 % *
V = 75 MPH
*(TTST 4 + DUAL 7)
FUNCTIONAL CLASS: FREEWAY

PROJECT LENGTH

LENGTH OF ROADWAY PROJECT R-2828	= 8.055 Miles
LENGTH OF STRUCTURE PROJECT R-2828	= 0.562 Miles
TOTAL LENGTH OF TIP PROJECT R-2828	= 8.617 Miles

NC DOT CONTACT:

DESIGN BUILD PROJECT ENGINEER -
TRANSPORTATION PROGRAM MANAGEMENT UNIT



Prepared In The Office of
FOR THE NORTH CAROLINA DEPARTMENT OF TRANSPORTATION
2018 STANDARD SPECIFICATIONS

RIGHT OF WAY DATE:
SEPT. 09, 2019

LETTING DATE:
DEC. 11, 2019

HYDRAULICS ENGINEER

P.E.
SIGNATURE:

DANIEL BRIDGES, PE
PROJECT ENGINEER

P.E.
SIGNATURE:

RONYELL THIGPEN, PE


PROJECT DESIGN ENGINEER



PERMIT DRAWING
SHEET 1 OF 171

REVISIONS

1/15/2021
C:\droectwise\ab\projectwise\wso-victor\koh\weu\d0348956\R2828-hud-frm-wet.osh20 cont.dan



INSET A

A horizontal graphic scale consisting of a black bar with white tick marks. The scale is labeled with '50' at both ends and '0' in the center. Below the scale, the words 'GRAPHIC SCALE' are printed in capital letters.

SITE #50

SDJ TEMPORARY SURFACE WATER IMPACT

 LANE **BLYTHE** **W**
434 Fayetteville


The logo consists of a stylized red 'W' and 'S' followed by a vertical red bar and a red parenthesis.


PROJECT REFERENCE NO.	SHEET NO.
R-2828	29
RW SHEET NO.	
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
DOCUMENT NOT CONSIDERED FINAL	


Permit Drawing Package
Last Revised on 02/16/21


**DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED**

MIT DRAWING
EET 111 OF 171









WETLAND AND SURACE WATER IMPACTS SUMMARY											Permit Drawing Package Last Revised on 02/16/21		
Site No.	Station (From/To)	Structure Size / Type	WETLAND IMPACTS					SURFACE WATER IMPACTS					
			Permanent Fill In Wetlands (ac)	Temp. Fill In Wetlands (ac)	Excavation in Wetlands (ac)	Mechanized Clearing in Wetlands (ac)	Hand Clearing in Wetlands (ac)	Permanent SW impacts (ac)	Temp. SW impacts (ac)	Existing Channel Impacts Permanent (ft)	Existing Channel Impacts Temp. (ft)	Natural Stream Design (ft)	
26A	707+50	Roadway Fill (SCM)						0.01	< 0.01	266	35		
26A	707+50	Culvert Stabilization (SCM)						< 0.01		65			
27	705+75 - 714+00	Roadway Fill (WDH)	2.44		0.03	0.24							
28	711+00 - 714+00 (LT)	Roadway Fill (SCN)						0.01	< 0.01	156	10		
29	726+50 - 728+00 (RT)	Drain Pond (PY)						1.40					
30	728+00 - 734+50 (RT)	Channel Change (SCQ)						0.06		673			
31	736+00	Roadway Fill (WDJ, SCQ)	0.38			0.09		0.03	< 0.01	130	58		
32	736+70 (LT) - 738+00 (RT)	2 @ 8'x9' RCBC (SCP)						0.07	0.02	379	92		
32	736+70 (LT) - 738+00 (RT)	Culvert Stabilization (SCP)						< 0.01		44			
32	736+70 (LT) - 738+00 (RT)	Bank Stabilization (SCP)						< 0.01		29			
33	759+00 (RT) - 759+82 (LT)	Roadway Fill (WDM)	0.39			0.03							
34	767+65 (RT)	Roadway Fill (WDN)				< 0.01							
35	782+00 (LT)	9'x8' RCBC (SCT)						0.05	< 0.01	441	37		
35	782+00 (LT)	Culvert Stabilization (SCT)						< 0.01		47			
35	782+00 (LT)	Bank Stabilization (SCT)						< 0.01		18			
36	782+00 - 787+20	Roadway Fill (WDO)	0.71		< 0.01	0.06							
37	785+90 (RT) - 787+70 (LT)	48" RCP (SCV)						0.03	< 0.01	394	20		
37	785+90 (RT) - 787+70 (LT)	Pipe Stabilization (SCV)						< 0.01		37			
38	788+00 (LT)	Roadway Fill (WDP)				< 0.01							
39	812+00 - 813+00 (LT)	Roadway Fill (WDS)	0.08										
40	812+90 - 813+37 (LT)	Channel Change (SDB)						< 0.01		54			
40	813+50 (LT)	Channel Change (SDC)						< 0.01		93			
40A*	-Y21- 40+00 (LT)	Roadway Fill (WDR)	0.09										
40B	-Y21- 44+40 (RT)	Roadway Fill (SCZ)						< 0.01	< 0.01	52	13		
SHEET 3 SUBTOTALS***:			4.09		0.03	0.43		1.70	0.03	2878	265	0	

NOTES:

*Represents an isolated wetland impact (also non-riparian)

**Represents any non-riparian wetland impact

***Rounded totals are sum of actual impacts

NC DEPARTMENT OF TRANSPORTATION

DIVISION OF HIGHWAYS

03/04/2020

WAKE & JOHNSTON

TIP NO.R-2828

WBS NO. 37673.1.TA2

WETLAND AND SURACE WATER IMPACTS SUMMARY

Site No.	Station (From/To)	Structure Size / Type	WETLAND IMPACTS					SURFACE WATER IMPACTS				
			Permanent Fill In Wetlands (ac)	Temp. Fill In Wetlands (ac)	Excavation in Wetlands (ac)	Mechanized Clearing in Wetlands (ac)	Hand Clearing in Wetlands (ac)	Permanent SW impacts (ac)	Temp. SW impacts (ac)	Existing Channel Impacts Permanent (ft)	Existing Channel Impacts Temp. (ft)	Natural Stream Design (ft)
41	813+50 (LT) - 829+50 (RT)	Channel Change (SCY)						0.21	0.05	1453	187	
41	-Y21- 44+50 (RT)	18" CSP (SCY)						< 0.01		58		
41	-Y21- 44+50 (RT)	Pipe Stabilization (SCY)						< 0.01		21		
41	829+50 (LT) - 834+00 (RT)	Bank Stabilization (SCY)						0.08		283		
42	BRIDGE 832+50 (RT)	Work Trestle (WDU)					0.02					
44	BRIDGE	Bridge	0.02				0.55		0.05		238	
44	BRIDGE	Bank Stabilization						0.01		44		
45	841+78 - 843+00 (LT)	Roadway Fill (WDV)	0.05			0.03						
47	856+50 - 861+50	Roadway Fill (WDV)	0.37			0.05						
48	861+40 - 866+30	Work Trestle (WDV)	0.02			< 0.01	0.65					
49	867+50 - 868+50	Work Trestle (WDY)	< 0.01				0.17					
50	876+00	14'X8' RCBC (SDJ)						0.03	< 0.01	318	46	
50	876+00	Culvert Stabilization (SDJ)						< 0.01		42		
50	876+00	Bank Stabilization (SDJ)						< 0.01		48		
50A	875+50 - 877+00	Roadway Fill (WDZ)	0.56			0.09						
51	890+00	42" RCP (SDK)						< 0.01	< 0.01	32	10	
51	890+00	Pipe Stabilization (SDK)						< 0.01		21		
51A	890+00	Roadway Fill (WEA)	0.29									
52	895+00	60" RCP (SDL)						0.05	< 0.01	588	20	
52	895+00	Pipe Stabilization (SDL)						< 0.01		39		
53	900+50 (LT) - 906+50 (RT)	42" RCP (SDM)						0.05	< 0.01	948	20	
53	900+50 (LT) - 906+50 (RT)	Pipe Stabilization (SDM)						< 0.01		47		
54	911+00 (LT) - 913+75 (RT)	Roadway Fill (WEC)	1.88			0.10						
SHEET 4 SUBTOTALS***:			3.19			0.27	1.40	0.45	0.10	3942	521	0

NOTES:

*Represents an isolated wetland impact (also non-riparian)

**Represents any non-riparian wetland impact

***Rounded totals are sum of actual impacts

NC DEPARTMENT OF TRANSPORTATION

DIVISION OF HIGHWAYS

03/04/2020

WAKE & JOHNSTON

TIP NO.R-2828

WBS NO. 37673.1.TA2

WETLAND AND SURACE WATER IMPACTS SUMMARY

Permit Drawing Package
Last Revised on 02/16/21

Site No.	Station (From/To)	Structure Size / Type	WETLAND IMPACTS					SURFACE WATER IMPACTS				
			Permanent Fill In Wetlands (ac)	Temp. Fill In Wetlands (ac)	Excavation in Wetlands (ac)	Mechanized Clearing in Wetlands (ac)	Hand Clearing in Wetlands (ac)	Permanent SW impacts (ac)	Temp. SW impacts (ac)	Existing Channel Impacts Permanent (ft)	Existing Channel Impacts Temp. (ft)	Natural Stream Design (ft)
80	-Y22FLYBD- 83+50 (RT)	Roadway Fill (WEV)	0.03									
81	-Y22RPDE- 29+50 (RT)	Roadway Fill (WEU)	0.04									
82	-Y22FLYBD- 113+30 (RT)	HSB Outlet SEH, (WFN(2))				0.05			< 0.01		10	
82	-Y22FLYBD- 113+30 (RT)	12" Pipe Stabil. (SEH)						< 0.01		15		
82A	-Y22SEC2- 382+00 - 386+00 (LT)	Channel Change (SEM)						0.04	< 0.01	422	20	
83	-Y22SEC2- 396+50 (LT)	Channel Change (SEK, WFF)				< 0.01		< 0.01	< 0.01	28	13	
84	-Y22SEC2- 405+00 (LT)	60" CMP & 72" WSP (SEL)							< 0.01		10	
84	-Y22SEC2- 405+00 (LT)	Pipe Stabilizatoin (SEL)						< 0.01		37		
85	-Y22SEC2- 416+00 (LT)	30" RCP Pipe Extension (SEV)						< 0.01	< 0.01	59	10	
85	-Y22SEC2- 416+00 (LT)	Pipe Stabilizatoin (SEV)						< 0.01		19		
87	-Y22SEC2- 474+20 (LT)	42" Pipe (SES)							< 0.01		10	
87	-Y22SEC2- 474+20 (LT)	Pipe Stabilization (SES)						< 0.01		10		
88	-Y22SEC2 (LT) - 80+00 (LT)	48" RCP (SES)						0.02	< 0.01	244	20	
88	-Y22SEC2 (LT) - 80+00 (LT)	Pipe Stabilizatoin (SES)						< 0.01		30		
91	Y22FLYCC 121+30/121+90 (RT)	Haul Road (SDQ)							0.01		66	
	SHEET 1 SUBTOTALS		2.36	< 0.01	0.08	0.16		3.88	0.01	2538	103	
	SHEET 2 SUBTOTALS		6.82		0.39	0.86	0.85	3.40	< 0.01	1834	57	
	SHEET 3 SUBTOTALS		4.09		0.03	0.43		1.70	0.03	2878	265	
	SHEET 4 SUBTOTALS		3.19			0.27	1.40	0.45	0.10	3942	521	
	SHEET 5 SUBTOTALS		0.09			0.03	1.56	0.36	0.02	4253	399	
TOTALS***:			16.62	< 0.01	0.50	1.79	3.81	9.88	0.20	16309	1504	0

NOTES:

*Represents an isolated wetland impact (also non-riparian)

**Represents any non-riparian wetland impact

***Rounded totals are sum of actual impacts

NC DEPARTMENT OF TRANSPORTATION

DIVISION OF HIGHWAYS

03/04/2020

WAKE & JOHNSTON

TIP NO.R-2828

WBS NO. 37673.1.TA2

SITE #48 NOTES:
 1. PERMANENT FILL IMPACT FOR PERMANENT BENTS.
 2. ALL CLEARING, INCLUDING UPLANDS, UNDER BRIDGE
 WILL BE HAND CLEARING.

Permit Drawing Package
 Last Revised on 02/16/21

DOCUMENT NOT CONSIDERED FINAL
 UNLESS ALL SIGNATURES COMPLETED

MATCH LINE SEE SHEET 27

-L- STA. 857+00.00

WDV

WDW


SDH

WDV

SDG

WDY

WDV



RIPARIAN BUFFER IMPACTS SUMMARY

Permit Drawing Package
Last Revised on 02/08/21

Site No.	Station (From/To)	Structure Size / Type	IMPACTS									BUFFER REPLACEMENT	
			TYPE			ALLOWABLE			MITIGABLE				
ROAD CROSSING	BRIDGE	PARALLEL IMPACT	ZONE 1 (ft ²)	ZONE 2 (ft ²)	TOTAL (ft ²)	ZONE 1 (ft ²)	ZONE 2 (ft ²)	TOTAL (ft ²)	ZONE 1 (ft ²)	ZONE 2 (ft ²)			
40B	803+66/804+26	Roadfill Ditch (SCY)			x				5079	2317	7396		
41	803+66/804+26	18" CSP (SCY)			x				5095	1729	6824		
41	812+81/827+66	Roadfill Ditch (SCY)			x				79241	46967	126208		
41	831+01/831+19	New Channel Tie In	x						1027	911	1938		
41	828+33/838+25	Bridge (SCY)		x		65438	37217	102655					
46	844+25/844+76	36" RCP			x					270	270		
48	866+00/868+47	Bridge (SDG)		x		16900	13266	30166					
50	875+30/877+40	14'X8' RCBC (SDJ)	x						25494	15386	40880		
51	888+93/889+94	42" RCP (SDK)	x			6023	5029	11052					
52	894+45/895+98	60" RCP (SDL)	x						36709	21474	58183		
53	900+35/907+05	42" RCP (SDM)	x						59490	36433	95923		
55	914+63/919+22	2@ 9'x9' RCBC (SDW)	x						50950	33292	84242		
56	913+58/917+59	Roadway Fill (SDV)	x						31949	22268	54217		
57	Y22RPB 24+86/26+00	54" RCP Pipe Extension (SDT)	x			6816	4456	11272					
57A	Y22RPB 25+94/27+66	Roadway Fill (SDS)			x				6090	4471	10561		
58	Y22FLYBD 48+12/46+10	42" pipe (SDT)	x						14654	8100	22754		
58A	Y22FLYCC 127+31/122+31	54" pipe (SDT)	x						32839	21340	54179		
59A	Y22FLYCC 116+13/117+87	Roadfill (SDQ)			x				3201	4149	7350		
70	Y17A 11+15/11+61	24" CSP (SCB1)	x						1931	589	2520		
72	Y21C 10+70/11+70	Roadfill			x				829	1377	2206		
73	Y22FLYBD 35+23/34+64	Roadfill	x			2357	1339	3696					
74	Y22FLYCC 33+58/34+58	Roadfill (SDV)			x				1566	2406	3972		
75	Y22FLYCC 36+14/38+48	Bridge		x		13991	9505	23496					
76	919+00/929+36	Roadfill (SDO)	x						64308	45001	109309		
TOTALS*:						111525	70812	182337	420452	268480	688932	0	0

NOTES:

NC DEPARTMENT OF TRANSPORTATION

DIVISION OF HIGHWAYS

02/24/2020

WAKE & JOHNSTON

TIP NO. R-2828

WBS NO. 37673.1.TA2

SHEET 38 OF 42

RIPARIAN BUFFER IMPACTS SUMMARY

Permit Drawing Package
Last Revised on 02/08/21

			IMPACTS									BUFFER REPLACEMENT		
			TYPE			ALLOWABLE			MITIGABLE					
Site No.	Station (From/To)	Structure Size / Type	ROAD CROSSING	BRIDGE	PARALLEL IMPACT	ZONE 1 (ft ²)	ZONE 2 (ft ²)	TOTAL (ft ²)	ZONE 1 (ft ²)	ZONE 2 (ft ²)	TOTAL (ft ²)	ZONE 1 (ft ²)	ZONE 2 (ft ²)	
78	Y22FLYCC 75+50	60" RCP Pipe Removal (SET)	x			785	618	1403	213	969	1182			
79	Y22FLYBD 82+61/84+16	54" RCP (SET)	x						37554	25277	62831			
79A	Y22RPDE 26+30/28+76	Borrow Site Excavation			x				0	721	721			
82	Y22FLYBD 113+57/113+98	Widening HSB (SEH)	x			2133	1426	3559						
82A	Y22 382+23/385+82	New Channel Tie In			x				13251	880	14131			
83	Y22 395+85/397+04	54" RCP (SEK)	x			1507	377	1884						
84	Y22 403+56/405+39	60" CMP & 72" WSP (SEL)	x			2355	565	2920						
87	Y22_SEC2 473+60/474+66	36" RCP (SES)	x			2764	1099	3863	0	397	397			
88	Y22RPDE 19+72/17+57	42" RCP (SES)	x						16259	8963	25222			
88A	Y22RPDE 13+30	Borrow Site Excavation			x				0	1075	1075			
90	Y22LPA 14+70/16+90	Roadway Fill (SDT)			x	551	405	956		857	857			
91	Y22FLYCC 121+30/121+90	Haul Road (SDQ)	x			4000	2577	6577						
	SHEET 1 SUBTOTALS						13360	10234	23594	513905	295720	809625	0	0
	SHEET 2 SUBTOTALS						109365	69644	179009	420452	268480	688932	0	0
	TOTALS*:						136820	86945	223765	1001634	603339	1604973	0	0

NOTES:

NC DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
03/04/2020
WAKE & JOHNSTON
TIP NO. R-2828
WBS NO. 37673.1.TA2
SHEET 20 OF 42