

Estimates Summary for TIP Project # 6.R.20

NCPProject #: Bridge #75

FA-Project#:

WBS Number

County: Columbus

Description: Low Impact Bridge

Date of Estimate: 1/16/2013

Prepared By: JRB

STATIONARY WORK ZONE SIGNS

DETOUR (M4-8)	7 signs	14 SF
DETOUR AHEAD (W20-2)	4 signs	64 SF
END DETOUR (M4-8a)	2 signs	6 SF
LEFT ARROW (M6-1)	2 signs	4 SF
NEXT LT (RT) (SP-4)	1 signs	4 SF
NO LT TURNS (R3-2)	1 signs	4 SF
NO RT TURNS (R3-1)	1 signs	4 SF
RD CLSD (W20-3)	2 signs	32 SF
RD CLSD 1000 FT (W20-3)	4 signs	64 SF
RD CLSD 500 FT(W20-3)	2 signs	32 SF
RD CLSD AHEAD (W20-3)	1 signs	16 SF
RD CLSD AHEAD (W20-3)	6 signs	96 SF
RIGHT ARROW (M6-1)	1 signs	2 SF
STOP (R1-1)	2 signs	32 SF
STOP AHD (W3-1)	2 signs	32 SF
STRAIGHT ARROW (M6-3)	4 signs	9 SF
TRUCK ENTRANCE (W14-12A)	2 signs	32 SF

TOTAL STATIONARY WORK ZONE SIGNS 447 SF

BARRICADE MOUNTED WORK ZONE SIGNS

DETOUR ARROW (M4-10)	2 signs	12 SF
DETOUR ARROW (M4-10)	2 signs	12 SF
RD CLSD (R11-2)	2 signs	20 SF
RD CLSD TO TRAFFIC (R11-4)	4 signs	50 SF

TOTAL BARRICADE MOUNTED WORK ZONE SIGNS 94 SF

WARNING FLAG SETS

12 EA

BARRICADES (TYPE III)

48 LF

Estimates Summary for TIP Project # 6.R.20

NCPProject #: Bridge #75

FA-Project#:

WBS Number

County: Columbus

Description: Low Impact Bridge

Date of Estimate: 1/16/2013

Prepared By: JRB

PAINT(4")

PA	WHITE EDGELINE (2X)	1340 LF
PI	YELLOW DOUBLE CENTER (2X)	1340 LF

TOTAL (4")		2680 LF
-------------------	--	----------------
