

STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	17BP.13.R.79	1	13

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
GEOTECHNICAL ENGINEERING UNIT

STRUCTURE
SUBSURFACE INVESTIGATION

PROJ. REFERENCE NO. 17BP.13.R.79 F.A. PROJ. N/A
COUNTY YANCEY
PROJECT DESCRIPTION DIVISION 13 EXPRESS DESIGN BUILD
BRIDGE REPLACEMENT

SITE DESCRIPTION BRIDGE NO. 144 OVER CREEK
ON SR-1317 (BIG BRUSH CREEK ROAD)

CONTENTS

<u>SHEET</u>	<u>DESCRIPTION</u>
1	TITLE SHEET
2	LEGEND
3	SITE PLAN
4 - 13	BORE LOG(S), CORE LOG(S), & CORE PHOTO(S)

PERSONNEL
A.F. RIGGS, JR.
J. BRANDSEN
S. HARDEE
S. LOW

INVESTIGATED BY S&ME, INC.
CHECKED BY A.F. RIGGS, JR.
SUBMITTED BY S&ME, INC.
DATE JULY, 2012

CAUTION NOTICE

THE SUBSURFACE INFORMATION AND THE SUBSURFACE INVESTIGATION ON WHICH IT IS BASED WERE MADE FOR THE PURPOSE OF PREPARING THE SCOPE OF WORK TO BE INCLUDED IN THE REQUEST FOR PROPOSAL. THE VARIOUS FIELD BORING LOGS, ROCK CORES, AND SOIL TEST DATA AVAILABLE MAY BE REVIEWED OR INSPECTED IN RALEIGH BY CONTACTING THE N.C. DEPARTMENT OF TRANSPORTATION, GEOTECHNICAL ENGINEERING UNIT AT 19191 707-6850. THE SUBSURFACE PLANS AND REPORTS, FIELD BORING LOGS, ROCK CORES, AND SOIL TEST DATA ARE NOT PART OF THE CONTRACT.


SOIL AND ROCK BOUNDARIES WITHIN A BOREHOLE ARE BASED ON GEOTECHNICAL INTERPRETATION UNLESS ENCOUNTERED IN A SAMPLE. INTERPRETED BOUNDARIES MAY NOT NECESSARILY REFLECT ACTUAL SUBSURFACE CONDITIONS BETWEEN SAMPLED STRATA, AND BOREHOLE INFORMATION MAY NOT NECESSARILY REFLECT ACTUAL SUBSURFACE CONDITIONS BETWEEN BORINGS. THE LABORATORY SAMPLE DATA AND THE IN SITU IN-PLACE TEST DATA CAN BE RELIED ON ONLY TO THE DEGREE OF RELIABILITY INHERENT IN THE STANDARD TEST METHOD. THE OBSERVED WATER LEVELS OR SOIL MOISTURE CONDITIONS INDICATED IN THE SUBSURFACE INVESTIGATIONS ARE AS RECORDED AT THE TIME OF THE INVESTIGATION. THESE WATER LEVELS OR SOIL MOISTURE CONDITIONS MAY VARY CONSIDERABLY WITH TIME ACCORDING TO CLIMATIC CONDITIONS INCLUDING TEMPERATURES, PRECIPITATION, AND WIND, AS WELL AS OTHER NON-CLIMATIC FACTORS.

THE DEPARTMENT DOES NOT WARRANT OR GUARANTEE THE SUFFICIENCY OR ACCURACY OF THE INVESTIGATION MADE, OR OPINION OF THE DEPARTMENT AS TO THE TYPE OF MATERIALS AND CONDITIONS TO BE ENCOUNTERED. THE BIDDER OR CONTRACTOR IS CAUTIONED TO MAKE SUCH INDEPENDENT SUBSURFACE INVESTIGATIONS AS HE DEEMS NECESSARY TO SATISFY HIMSELF AS TO CONDITIONS TO BE ENCOUNTERED ON THE PROJECT. THE CONTRACTOR SHALL HAVE NO CLAIM FOR ADDITIONAL COMPENSATION OR FOR AN EXTENSION OF TIME FOR ANY REASON RESULTING FROM THE ACTUAL CONDITIONS ENCOUNTERED AT THE SITE DIFFERING FROM THOSE INDICATED IN THE SUBSURFACE INFORMATION.

NOTE - THE INFORMATION CONTAINED HEREIN IS NOT IMPLIED OR GUARANTEED BY THE N.C. DEPARTMENT OF TRANSPORTATION AS BEING ACCURATE NOR IT IS CONSIDERED TO BE PART OF THE PLANS, SPECIFICATIONS, OR CONTRACT FOR THE PROJECT.

NOTE - BY HAVING REQUESTED THIS INFORMATION THE CONTRACTOR SPECIFICALLY WAIVES ANY CLAIMS FOR INCREASED COMPENSATION OR EXTENSION OF TIME BASED ON DIFFERENCES BETWEEN THE CONDITIONS INDICATED HEREIN AND THE ACTUAL CONDITIONS AT THE PROJECT SITE.

DRAWN BY: B. RATTI



<table border="1" style="float: right; width: 100%;"> <tr> <td style="width: 60%;">PROJECT REFERENCE NO. 17BP.13.R.79</td> <td style="width: 40%;">SHEET NO. 2</td> </tr> </table>						PROJECT REFERENCE NO. 17BP.13.R.79	SHEET NO. 2																																																																																																																				
PROJECT REFERENCE NO. 17BP.13.R.79	SHEET NO. 2																																																																																																																										
NORTH CAROLINA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS GEOTECHNICAL ENGINEERING UNIT SOIL AND ROCK LEGEND, TERMS, SYMBOLS, AND ABBREVIATIONS																																																																																																																											
SOIL DESCRIPTION			GRADATION																																																																																																																								
SOIL IS CONSIDERED TO BE THE UNCONSOLIDATED, SEMI-CONSOLIDATED, OR WEATHERED EARTH MATERIALS THAT CAN BE PENETRATED WITH A CONTINUOUS FLIGHT POWER AUGER, AND YIELD LESS THAN 100 BLOWS PER FOOT ACCORDING TO STANDARD PENETRATION TEST (AASHTO T206, ASTM D-1586). SOIL CLASSIFICATION IS BASED ON THE AASHTO SYSTEM. BASIC DESCRIPTIONS GENERALLY SHALL INCLUDE: CONSISTENCY, COLOR, TEXTURE, MOISTURE, AASHTO CLASSIFICATION, AND OTHER PERTINENT FACTORS SUCH AS MINERALOGICAL COMPOSITION, ANGULARITY, STRUCTURE, PLASTICITY, ETC. EXAMPLE: <i>VERY STIFF, GRAY, SILTY CLAY, MOST WITH INTERBEDDED FINE SAND LENSES, HIGH PLASTIC, A-7-6</i>			WELL GRADED - INDICATES A GOOD REPRESENTATION OF PARTICLE SIZES FROM FINE TO COARSE. UNIFORM - INDICATES THAT SOIL PARTICLES ARE ALL APPROXIMATELY THE SAME SIZE. (ALSO POORLY GRADED) GAP-GRADED - INDICATES A MIXTURE OF UNIFORM PARTICLES OF TWO OR MORE SIZES.																																																																																																																								
SOIL LEGEND AND AASHTO CLASSIFICATION			ANGULARITY OF GRAINS																																																																																																																								
<table border="1" style="width: 100%; font-size: 8px;"> <tr> <th>GENERAL CLASS.</th> <th colspan="4">GRANULAR MATERIALS (≤ 35% PASSING #200)</th> <th colspan="4">SILT-CLAY MATERIALS (> 35% PASSING #200)</th> <th colspan="4">ORGANIC MATERIALS</th> </tr> <tr> <th>GROUP CLASS.</th> <td colspan="2">A-1</td> <td colspan="2">A-3</td> <td colspan="2">A-2</td> <td colspan="2">A-4</td> <td colspan="2">A-5</td> <td colspan="2">A-7</td> <td colspan="2">A-1, A-2</td> </tr> <tr> <th>SYMBOL</th> <td colspan="2">A-1-a</td> <td colspan="2">A-1-b</td> <td colspan="2">A-2-4</td> <td colspan="2">A-2-5</td> <td colspan="2">A-2-6</td> <td colspan="2">A-2-7</td> <td colspan="2">A-3</td> </tr> <tr> <th>% PASSING</th> <td colspan="2">50 MX</td> <td colspan="2">30 MX</td> <td colspan="2">15 MX</td> <td colspan="2">50 MX</td> <td colspan="2">10 MX</td> <td colspan="2">5 MX</td> <td colspan="2">200</td> </tr> <tr> <th>LIQUID LIMIT</th> <td colspan="2">6 MX</td> <td colspan="2">NP</td> <td colspan="2">40 MX</td> <td colspan="2">41 MN</td> <td colspan="2">40 MX</td> <td colspan="2">41 MN</td> <td colspan="2">40 MX</td> </tr> <tr> <th>GROUP INDEX</th> <td colspan="2">0</td> <td colspan="2">0</td> <td colspan="2">0</td> <td colspan="2">4 MX</td> <td colspan="2">8 MX</td> <td colspan="2">12 MX</td> <td colspan="2">16 MX</td> </tr> <tr> <th>USUAL TYPES OF MAJOR MATERIALS</th> <td colspan="2">STONE FRAGS, GRAVEL, AND SAND</td> <td colspan="2">FINE SAND</td> <td colspan="2">SILTY OR CLAYEY GRAVEL AND SAND</td> <td colspan="2">SILTY SOILS</td> <td colspan="2">CLAYEY SOILS</td> <td colspan="2">SOILS WITH LITTLE OR MODERATE AMOUNTS OF ORGANIC MATTER</td> <td colspan="2">HIGHLY ORGANIC SOILS</td> </tr> <tr> <th>GEN. RATING AS A SUBGRADE</th> <td colspan="4">EXCELLENT TO GOOD</td> <td colspan="4">FAIR TO POOR</td> <td colspan="2">FAIR TO POOR</td> <td colspan="2">POOR</td> <td colspan="2">UNSATURABLE</td> </tr> </table>			GENERAL CLASS.	GRANULAR MATERIALS (≤ 35% PASSING #200)				SILT-CLAY MATERIALS (> 35% PASSING #200)				ORGANIC MATERIALS				GROUP CLASS.	A-1		A-3		A-2		A-4		A-5		A-7		A-1, A-2		SYMBOL	A-1-a		A-1-b		A-2-4		A-2-5		A-2-6		A-2-7		A-3		% PASSING	50 MX		30 MX		15 MX		50 MX		10 MX		5 MX		200		LIQUID LIMIT	6 MX		NP		40 MX		41 MN		40 MX		41 MN		40 MX		GROUP INDEX	0		0		0		4 MX		8 MX		12 MX		16 MX		USUAL TYPES OF MAJOR MATERIALS	STONE FRAGS, GRAVEL, AND SAND		FINE SAND		SILTY OR CLAYEY GRAVEL AND SAND		SILTY SOILS		CLAYEY SOILS		SOILS WITH LITTLE OR MODERATE AMOUNTS OF ORGANIC MATTER		HIGHLY ORGANIC SOILS		GEN. RATING AS A SUBGRADE	EXCELLENT TO GOOD				FAIR TO POOR				FAIR TO POOR		POOR		UNSATURABLE		MINERAL NAMES SUCH AS QUARTZ, FELDSPAR, MICA, TALC, KAOLIN, ETC. ARE USED IN DESCRIPTIONS WHENEVER THEY ARE CONSIDERED OF SIGNIFICANCE.		
GENERAL CLASS.	GRANULAR MATERIALS (≤ 35% PASSING #200)				SILT-CLAY MATERIALS (> 35% PASSING #200)				ORGANIC MATERIALS																																																																																																																		
GROUP CLASS.	A-1		A-3		A-2		A-4		A-5		A-7		A-1, A-2																																																																																																														
SYMBOL	A-1-a		A-1-b		A-2-4		A-2-5		A-2-6		A-2-7		A-3																																																																																																														
% PASSING	50 MX		30 MX		15 MX		50 MX		10 MX		5 MX		200																																																																																																														
LIQUID LIMIT	6 MX		NP		40 MX		41 MN		40 MX		41 MN		40 MX																																																																																																														
GROUP INDEX	0		0		0		4 MX		8 MX		12 MX		16 MX																																																																																																														
USUAL TYPES OF MAJOR MATERIALS	STONE FRAGS, GRAVEL, AND SAND		FINE SAND		SILTY OR CLAYEY GRAVEL AND SAND		SILTY SOILS		CLAYEY SOILS		SOILS WITH LITTLE OR MODERATE AMOUNTS OF ORGANIC MATTER		HIGHLY ORGANIC SOILS																																																																																																														
GEN. RATING AS A SUBGRADE	EXCELLENT TO GOOD				FAIR TO POOR				FAIR TO POOR		POOR		UNSATURABLE																																																																																																														
PI OF A-7-5 SUBGROUP IS ≤ LL - 30 ; PI OF A-7-6 SUBGROUP IS > LL - 30			COMPRESSION																																																																																																																								
SLIGHTLY COMPRESSIBLE MODERATELY COMPRESSIBLE HIGHLY COMPRESSIBLE			LIQUID LIMIT LESS THAN 31 LIQUID LIMIT EQUAL TO 31-50 LIQUID LIMIT GREATER THAN 50																																																																																																																								
PERCENTAGE OF MATERIAL			GROUND WATER																																																																																																																								
<table border="1" style="width: 100%; font-size: 8px;"> <tr> <th>ORGANIC MATERIAL</th> <th>GRANULAR SOILS</th> <th>SILT - CLAY SOILS</th> <th>OTHER MATERIAL</th> </tr> <tr> <td>TRACE OF ORGANIC MATTER</td> <td>2 - 3%</td> <td>3 - 5%</td> <td>TRACE</td> </tr> <tr> <td>LITTLE ORGANIC MATTER</td> <td>3 - 5%</td> <td>5 - 12%</td> <td>LITTLE</td> </tr> <tr> <td>MODERATELY ORGANIC</td> <td>5 - 10%</td> <td>12 - 20%</td> <td>SOME</td> </tr> <tr> <td>HIGHLY ORGANIC</td> <td>>10%</td> <td>>20%</td> <td>HIGHLY</td> </tr> </table>			ORGANIC MATERIAL	GRANULAR SOILS	SILT - CLAY SOILS	OTHER MATERIAL	TRACE OF ORGANIC MATTER	2 - 3%	3 - 5%	TRACE	LITTLE ORGANIC MATTER	3 - 5%	5 - 12%	LITTLE	MODERATELY ORGANIC	5 - 10%	12 - 20%	SOME	HIGHLY ORGANIC	>10%	>20%	HIGHLY	WATER LEVEL IN BORE HOLE IMMEDIATELY AFTER DRILLING STATIC WATER LEVEL AFTER 24 HOURS PERCHED WATER, SATURATED ZONE, OR WATER BEARING STRATA SPRING OR SEEP																																																																																																				
ORGANIC MATERIAL	GRANULAR SOILS	SILT - CLAY SOILS	OTHER MATERIAL																																																																																																																								
TRACE OF ORGANIC MATTER	2 - 3%	3 - 5%	TRACE																																																																																																																								
LITTLE ORGANIC MATTER	3 - 5%	5 - 12%	LITTLE																																																																																																																								
MODERATELY ORGANIC	5 - 10%	12 - 20%	SOME																																																																																																																								
HIGHLY ORGANIC	>10%	>20%	HIGHLY																																																																																																																								
CONSISTENCY OR DENSENESS			MISCELLANEOUS SYMBOLS																																																																																																																								
<table border="1" style="width: 100%; font-size: 8px;"> <tr> <th>PRIMARY SOIL TYPE</th> <th>COMPACTNESS OR CONSISTENCY</th> <th>RANGE OF STANDARD PENETRATION RESISTANCE (N-VALUE)</th> <th>RANGE OF UNCONFINED COMPRESSIVE STRENGTH (TONS/FT²)</th> </tr> <tr> <td>GENERALLY GRANULAR MATERIAL (NON-COHESIVE)</td> <td>VERY LOOSE LOOSE MEDIUM DENSE DENSE VERY DENSE</td> <td><4 4 TO 10 10 TO 30 30 TO 50 >50</td> <td>N/A</td> </tr> <tr> <td>GENERALLY SILT-CLAY MATERIAL (COHESIVE)</td> <td>VERY SOFT SOFT MEDIUM STIFF STIFF VERY STIFF HARD</td> <td><2 2 TO 4 4 TO 8 8 TO 15 15 TO 30 >30</td> <td><0.25 0.25 TO 0.50 0.5 TO 1.0 1 TO 2 2 TO 4 >4</td> </tr> </table>			PRIMARY SOIL TYPE	COMPACTNESS OR CONSISTENCY	RANGE OF STANDARD PENETRATION RESISTANCE (N-VALUE)	RANGE OF UNCONFINED COMPRESSIVE STRENGTH (TONS/FT ²)	GENERALLY GRANULAR MATERIAL (NON-COHESIVE)	VERY LOOSE LOOSE MEDIUM DENSE DENSE VERY DENSE	<4 4 TO 10 10 TO 30 30 TO 50 >50	N/A	GENERALLY SILT-CLAY MATERIAL (COHESIVE)	VERY SOFT SOFT MEDIUM STIFF STIFF VERY STIFF HARD	<2 2 TO 4 4 TO 8 8 TO 15 15 TO 30 >30	<0.25 0.25 TO 0.50 0.5 TO 1.0 1 TO 2 2 TO 4 >4	<table border="1" style="width: 100%; font-size: 8px;"> <tr> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td></td> </tr> </table>																																																																																																												
PRIMARY SOIL TYPE	COMPACTNESS OR CONSISTENCY	RANGE OF STANDARD PENETRATION RESISTANCE (N-VALUE)	RANGE OF UNCONFINED COMPRESSIVE STRENGTH (TONS/FT ²)																																																																																																																								
GENERALLY GRANULAR MATERIAL (NON-COHESIVE)	VERY LOOSE LOOSE MEDIUM DENSE DENSE VERY DENSE	<4 4 TO 10 10 TO 30 30 TO 50 >50	N/A																																																																																																																								
GENERALLY SILT-CLAY MATERIAL (COHESIVE)	VERY SOFT SOFT MEDIUM STIFF STIFF VERY STIFF HARD	<2 2 TO 4 4 TO 8 8 TO 15 15 TO 30 >30	<0.25 0.25 TO 0.50 0.5 TO 1.0 1 TO 2 2 TO 4 >4																																																																																																																								
TEXTURE OR GRAIN SIZE			ABBREVIATIONS																																																																																																																								
<table border="1" style="width: 100%; font-size: 8px;"> <tr> <th>U.S. STD. SIEVE SIZE</th> <th>4</th> <th>10</th> <th>40</th> <th>60</th> <th>200</th> <th>270</th> </tr> <tr> <th>OPENING (MM)</th> <td>4.75</td> <td>2.00</td> <td>0.42</td> <td>0.25</td> <td>0.075</td> <td>0.053</td> </tr> </table>			U.S. STD. SIEVE SIZE	4	10	40	60	200	270	OPENING (MM)	4.75	2.00	0.42	0.25	0.075	0.053	<table border="1" style="width: 100%; font-size: 8px;"> <tr> <td>AR - AUGER REFUSAL</td> <td>MED. - MEDIUM</td> <td>VST - VANE SHEAR TEST</td> </tr> <tr> <td>BT - BORING TERMINATED</td> <td>MICA - MICACEOUS</td> <td>WEA. - WEATHERED</td> </tr> <tr> <td>CL - CLAY</td> <td>MOD. - MODERATELY</td> <td>γ - UNIT WEIGHT</td> </tr> <tr> <td>CPT - CONE PENETRATION TEST</td> <td>NP - NON PLASTIC</td> <td>γ_d - DRY UNIT WEIGHT</td> </tr> <tr> <td>CSE. - COARSE</td> <td>ORG. - ORGANIC</td> <td></td> </tr> <tr> <td>DMT - DILATOMETER TEST</td> <td>PMT - PRESSUREMETER TEST</td> <td></td> </tr> <tr> <td>DPT - DYNAMIC PENETRATION TEST</td> <td>SAP. - SAPROLITIC</td> <td></td> </tr> <tr> <td>ε - VOID RATIO</td> <td>SD. - SAND, SANDY</td> <td></td> </tr> <tr> <td>F - FINE</td> <td>SL. - SILT, SILTY</td> <td></td> </tr> <tr> <td>FOSS. - FOSSILIFEROUS</td> <td>SLI. - SLIGHTLY</td> <td></td> </tr> <tr> <td>FRAC. - FRACTURED, FRACTURES</td> <td>TCR - TRICONE REFUSAL</td> <td></td> </tr> <tr> <td>FRAGS. - FRAGMENTS</td> <td>w - MOISTURE CONTENT</td> <td></td> </tr> <tr> <td>HL. - HIGHLY</td> <td>V - VERY</td> <td></td> </tr> </table>			AR - AUGER REFUSAL	MED. - MEDIUM	VST - VANE SHEAR TEST	BT - BORING TERMINATED	MICA - MICACEOUS	WEA. - WEATHERED	CL - CLAY	MOD. - MODERATELY	γ - UNIT WEIGHT	CPT - CONE PENETRATION TEST	NP - NON PLASTIC	γ _d - DRY UNIT WEIGHT	CSE. - COARSE	ORG. - ORGANIC		DMT - DILATOMETER TEST	PMT - PRESSUREMETER TEST		DPT - DYNAMIC PENETRATION TEST	SAP. - SAPROLITIC		ε - VOID RATIO	SD. - SAND, SANDY		F - FINE	SL. - SILT, SILTY		FOSS. - FOSSILIFEROUS	SLI. - SLIGHTLY		FRAC. - FRACTURED, FRACTURES	TCR - TRICONE REFUSAL		FRAGS. - FRAGMENTS	w - MOISTURE CONTENT		HL. - HIGHLY	V - VERY																																																																		
U.S. STD. SIEVE SIZE	4	10	40	60	200	270																																																																																																																					
OPENING (MM)	4.75	2.00	0.42	0.25	0.075	0.053																																																																																																																					
AR - AUGER REFUSAL	MED. - MEDIUM	VST - VANE SHEAR TEST																																																																																																																									
BT - BORING TERMINATED	MICA - MICACEOUS	WEA. - WEATHERED																																																																																																																									
CL - CLAY	MOD. - MODERATELY	γ - UNIT WEIGHT																																																																																																																									
CPT - CONE PENETRATION TEST	NP - NON PLASTIC	γ _d - DRY UNIT WEIGHT																																																																																																																									
CSE. - COARSE	ORG. - ORGANIC																																																																																																																										
DMT - DILATOMETER TEST	PMT - PRESSUREMETER TEST																																																																																																																										
DPT - DYNAMIC PENETRATION TEST	SAP. - SAPROLITIC																																																																																																																										
ε - VOID RATIO	SD. - SAND, SANDY																																																																																																																										
F - FINE	SL. - SILT, SILTY																																																																																																																										
FOSS. - FOSSILIFEROUS	SLI. - SLIGHTLY																																																																																																																										
FRAC. - FRACTURED, FRACTURES	TCR - TRICONE REFUSAL																																																																																																																										
FRAGS. - FRAGMENTS	w - MOISTURE CONTENT																																																																																																																										
HL. - HIGHLY	V - VERY																																																																																																																										
SOIL MOISTURE - CORRELATION OF TERMS			EQUIPMENT USED ON SUBJECT PROJECT																																																																																																																								
<table border="1" style="width: 100%; font-size: 8px;"> <tr> <th>SOIL MOISTURE SCALE (ATTERBERG LIMITS)</th> <th>FIELD MOISTURE DESCRIPTION</th> <th>GUIDE FOR FIELD MOISTURE DESCRIPTION</th> </tr> <tr> <td rowspan="2">LL - LIQUID LIMIT PL - PLASTIC LIMIT</td> <td>- SATURATED - (SAT.)</td> <td>USUALLY LIQUID; VERY WET, USUALLY FROM BELOW THE GROUND WATER TABLE</td> </tr> <tr> <td>- WET - (W)</td> <td>SEMISOLID; REQUIRES DRYING TO ATTAIN OPTIMUM MOISTURE</td> </tr> <tr> <td rowspan="2">OM - OPTIMUM MOISTURE SL - SHRINKAGE LIMIT</td> <td>- MOIST - (M)</td> <td>SOLID; AT OR NEAR OPTIMUM MOISTURE</td> </tr> <tr> <td>- DRY - (D)</td> <td>REQUIRES ADDITIONAL WATER TO ATTAIN OPTIMUM MOISTURE</td> </tr> </table>			SOIL MOISTURE SCALE (ATTERBERG LIMITS)	FIELD MOISTURE DESCRIPTION	GUIDE FOR FIELD MOISTURE DESCRIPTION	LL - LIQUID LIMIT PL - PLASTIC LIMIT	- SATURATED - (SAT.)	USUALLY LIQUID; VERY WET, USUALLY FROM BELOW THE GROUND WATER TABLE	- WET - (W)	SEMISOLID; REQUIRES DRYING TO ATTAIN OPTIMUM MOISTURE	OM - OPTIMUM MOISTURE SL - SHRINKAGE LIMIT	- MOIST - (M)	SOLID; AT OR NEAR OPTIMUM MOISTURE	- DRY - (D)	REQUIRES ADDITIONAL WATER TO ATTAIN OPTIMUM MOISTURE	<table border="1" style="width: 100%; font-size: 8px;"> <tr> <td> DRILL UNITS: ☐ MOBILE B- ☐ BK-51 ☐ CME-45C ☐ CME-550 ☐ PORTABLE MOIST ☒ CME-45B </td> <td> ADVANCING TOOLS: ☐ CLAY BITS ☐ 6" CONTINUOUS FLIGHT AUGER ☐ 8" HOLLOW AUGERS ☐ HARD FACED FINGER BITS ☐ TUNG.-CARBIDE INSERTS ☐ CASING ☐ W/ ADVANCER ☒ TRICONE 2 1/4" STEEL TEETH ☐ TRICONE " TUNG.-CARB. ☒ CORE BIT ☒ 3 1/4" HOLLOW AUGER </td> <td> HAMMER TYPE: ☒ AUTOMATIC ☐ MANUAL CORE SIZE: ☐ -B ☒ -N NWD4 ☐ -H HAND TOOLS: ☐ POST HOLE DIGGER ☐ HAND AUGER ☐ SOUNDING ROD ☐ VANE SHEAR TEST </td> </tr> </table>			DRILL UNITS: ☐ MOBILE B- ☐ BK-51 ☐ CME-45C ☐ CME-550 ☐ PORTABLE MOIST ☒ CME-45B	ADVANCING TOOLS: ☐ CLAY BITS ☐ 6" CONTINUOUS FLIGHT AUGER ☐ 8" HOLLOW AUGERS ☐ HARD FACED FINGER BITS ☐ TUNG.-CARBIDE INSERTS ☐ CASING ☐ W/ ADVANCER ☒ TRICONE 2 1/4" STEEL TEETH ☐ TRICONE " TUNG.-CARB. ☒ CORE BIT ☒ 3 1/4" HOLLOW AUGER	HAMMER TYPE: ☒ AUTOMATIC ☐ MANUAL CORE SIZE: ☐ -B ☒ -N NWD4 ☐ -H HAND TOOLS: ☐ POST HOLE DIGGER ☐ HAND AUGER ☐ SOUNDING ROD ☐ VANE SHEAR TEST																																																																																																						
SOIL MOISTURE SCALE (ATTERBERG LIMITS)	FIELD MOISTURE DESCRIPTION	GUIDE FOR FIELD MOISTURE DESCRIPTION																																																																																																																									
LL - LIQUID LIMIT PL - PLASTIC LIMIT	- SATURATED - (SAT.)	USUALLY LIQUID; VERY WET, USUALLY FROM BELOW THE GROUND WATER TABLE																																																																																																																									
	- WET - (W)	SEMISOLID; REQUIRES DRYING TO ATTAIN OPTIMUM MOISTURE																																																																																																																									
OM - OPTIMUM MOISTURE SL - SHRINKAGE LIMIT	- MOIST - (M)	SOLID; AT OR NEAR OPTIMUM MOISTURE																																																																																																																									
	- DRY - (D)	REQUIRES ADDITIONAL WATER TO ATTAIN OPTIMUM MOISTURE																																																																																																																									
DRILL UNITS: ☐ MOBILE B- ☐ BK-51 ☐ CME-45C ☐ CME-550 ☐ PORTABLE MOIST ☒ CME-45B	ADVANCING TOOLS: ☐ CLAY BITS ☐ 6" CONTINUOUS FLIGHT AUGER ☐ 8" HOLLOW AUGERS ☐ HARD FACED FINGER BITS ☐ TUNG.-CARBIDE INSERTS ☐ CASING ☐ W/ ADVANCER ☒ TRICONE 2 1/4" STEEL TEETH ☐ TRICONE " TUNG.-CARB. ☒ CORE BIT ☒ 3 1/4" HOLLOW AUGER	HAMMER TYPE: ☒ AUTOMATIC ☐ MANUAL CORE SIZE: ☐ -B ☒ -N NWD4 ☐ -H HAND TOOLS: ☐ POST HOLE DIGGER ☐ HAND AUGER ☐ SOUNDING ROD ☐ VANE SHEAR TEST																																																																																																																									
PLASTICITY			DRILL UNITS:																																																																																																																								
<table border="1" style="width: 100%; font-size: 8px;"> <tr> <th>NONPLASTIC</th> <th>PLASTICITY INDEX (PI)</th> <th>DRY STRENGTH</th> </tr> <tr> <td>LOW PLASTICITY</td> <td>0-5</td> <td>VERY LOW</td> </tr> <tr> <td>MED. PLASTICITY</td> <td>6-15</td> <td>SLIGHT</td> </tr> <tr> <td>HIGH PLASTICITY</td> <td>16-25</td> <td>MEDIUM</td> </tr> <tr> <td></td> <td>26 OR MORE</td> <td>HIGH</td> </tr> </table>			NONPLASTIC	PLASTICITY INDEX (PI)	DRY STRENGTH	LOW PLASTICITY	0-5	VERY LOW	MED. PLASTICITY	6-15	SLIGHT	HIGH PLASTICITY	16-25	MEDIUM		26 OR MORE	HIGH	ADVANCING TOOLS:																																																																																																									
NONPLASTIC	PLASTICITY INDEX (PI)	DRY STRENGTH																																																																																																																									
LOW PLASTICITY	0-5	VERY LOW																																																																																																																									
MED. PLASTICITY	6-15	SLIGHT																																																																																																																									
HIGH PLASTICITY	16-25	MEDIUM																																																																																																																									
	26 OR MORE	HIGH																																																																																																																									
COLOR			DRILL UNITS:																																																																																																																								
DESCRIPTIONS MAY INCLUDE COLOR OR COLOR COMBINATIONS (TAN, RED, YELLOW-BROWN, BLUE-GRAY). MODIFIERS SUCH AS LIGHT, DARK, STREAKED, ETC. ARE USED TO DESCRIBE APPEARANCE.			ADVANCING TOOLS:																																																																																																																								

NORTH CAROLINA DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
GEOTECHNICAL ENGINEERING UNIT
SOIL AND ROCK LEGEND, TERMS, SYMBOLS, AND ABBREVIATIONS

ROCK DESCRIPTION		TERMS AND DEFINITIONS	
HARD ROCK IS NON-COASTAL PLAIN MATERIAL THAT IF TESTED, WOULD YIELD SPT REFUSAL, AN INFERRED ROCK LINE INDICATES THE LEVEL AT WHICH NON-COASTAL PLAIN MATERIAL WOULD YIELD SPT REFUSAL. SPT REFUSAL IS PENETRATION BY A SPLIT SPOON SAMPLER EQUAL TO OR LESS THAN 0.1 FOOT PER 60 BLOWS. IN NON-COASTAL PLAIN MATERIAL, THE TRANSITION BETWEEN SOIL AND ROCK IS OFTEN REPRESENTED BY A ZONE OF WEATHERED ROCK. ROCK MATERIALS ARE TYPICALLY DIVIDED AS FOLLOWS:		ALLUVIUM (ALLUV.) - SOILS THAT HAVE BEEN TRANSPORTED BY WATER. AQUIFER - A WATER BEARING FORMATION OR STRATA. ARENACEOUS - APPLIED TO ROCKS THAT HAVE BEEN DERIVED FROM SAND OR THAT CONTAIN SAND. ARGILLACEOUS - APPLIED TO ALL ROCKS OR SUBSTANCES COMPOSED OF CLAY MINERALS, OR HAVING A NOTABLE PROPORTION OF CLAY IN THEIR COMPOSITION, AS SHALE, SLATE, ETC. ARTESIAN - GROUND WATER THAT IS UNDER SUFFICIENT PRESSURE TO RISE ABOVE THE LEVEL AT WHICH IT IS ENCOUNTERED, BUT WHICH DOES NOT NECESSARILY RISE TO OR ABOVE THE GROUND SURFACE. CALCAREOUS (CALC.) - SOILS THAT CONTAIN APPRECIABLE AMOUNTS OF CALCIUM CARBONATE. COLLUVIUM - ROCK FRAGMENTS MIXED WITH SOIL DEPOSITED BY GRAVITY ON SLOPE OR AT BOTTOM OF SLOPE. CORE RECOVERY (REC.) - TOTAL LENGTH OF ALL MATERIAL RECOVERED IN THE CORE BARREL DIVIDED BY TOTAL LENGTH OF CORE RUN AND EXPRESSED AS A PERCENTAGE. DIKE - A TABULAR BODY OF IGNEOUS ROCK THAT CUTS ACROSS THE STRUCTURE OF ADJACENT ROCKS OR CUTS MASSIVE ROCK. DIP - THE ANGLE AT WHICH A STRATUM OR ANY PLANAR FEATURE IS INCLINED FROM THE HORIZONTAL. DIP DIRECTION (DIP AZIMUTH) - THE DIRECTION OR BEARING OF THE HORIZONTAL TRACE OF THE LINE OF DIP, MEASURED CLOCKWISE FROM NORTH. FAULT - A FRACTURE OR FRACTURE ZONE ALONG WHICH THERE HAS BEEN DISPLACEMENT OF THE SIDES RELATIVE TO ONE ANOTHER PARALLEL TO THE FRACTURE. FISSILE - A PROPERTY OF SPLITTING ALONG CLOSELY SPACED PARALLEL PLANES. FLOAT - ROCK FRAGMENTS ON SURFACE NEAR THEIR ORIGINAL POSITION AND DISLODGED FROM PARENT MATERIAL. FLOOD PLAIN (FP) - LAND BORDERING A STREAM, BUILT OF SEDIMENTS DEPOSITED BY THE STREAM. FORMATION (FM.) - A MAPPABLE GEOLOGIC UNIT THAT CAN BE RECOGNIZED AND TRACED IN THE FIELD. JOINT - FRACTURE IN ROCK ALONG WHICH NO APPRECIABLE MOVEMENT HAS OCCURRED. LEDGE - A SHELF-LIKE RIDGE OR PROJECTION OF ROCK WHOSE THICKNESS IS SMALL COMPARED TO ITS LATERAL EXTENT. LENS - A BODY OF SOIL OR ROCK THAT THINS OUT IN ONE OR MORE DIRECTIONS. MOTTLED (MOT.) - IRREGULARLY MARKED WITH SPOTS OF DIFFERENT COLORS, MOTTLING IN SOILS USUALLY INDICATES POOR AERATION AND LACK OF GOOD DRAINAGE. PERCHED WATER - WATER MAINTAINED ABOVE THE NORMAL GROUND WATER LEVEL BY THE PRESENCE OF AN INTERVENING IMPERVIOUS STRATUM. RESIDUAL (RES.) SOIL - SOIL FORMED IN PLACE BY THE WEATHERING OF ROCK. ROCK QUALITY DESIGNATION (RQD) - A MEASURE OF ROCK QUALITY DESCRIBED BY TOTAL LENGTH OF ROCK SEGMENTS EQUAL TO OR GREATER THAN 4 INCHES DIVIDED BY THE TOTAL LENGTH OF CORE RUN AND EXPRESSED AS A PERCENTAGE. SAPROLITE (SAP.) - RESIDUAL SOIL THAT RETAINS THE RELIC STRUCTURE OR FABRIC OF THE PARENT ROCK. SILL - AN INTRUSIVE BODY OF IGNEOUS ROCK OF APPROXIMATELY UNIFORM THICKNESS AND RELATIVELY THIN COMPARED WITH ITS LATERAL EXTENT, THAT HAS BEEN EMPLACED PARALLEL TO THE BEDDING OR SCHISTOSITY OF THE INTRODUCED ROCKS. SLICKENSIDE - POLISHED AND STRIATED SURFACE THAT RESULTS FROM FRICTION ALONG A FAULT OR SLIP PLANE. STANDARD PENETRATION TEST (PENETRATION RESISTANCE) (SPT) - NUMBER OF BLOWS IN OR BPF OF A 140 LB. HAMMER FALLING 30 INCHES REQUIRED TO PRODUCE A PENETRATION OF 1 FOOT INTO SOIL WITH A 2 INCH OUTSIDE DIAMETER SPLIT SPOON SAMPLER. SPT REFUSAL IS PENETRATION EQUAL TO OR LESS THAN 0.1 FOOT PER 60 BLOWS. STRATA CORE RECOVERY (SREC.) - TOTAL LENGTH OF STRATA MATERIAL RECOVERED DIVIDED BY TOTAL LENGTH OF STRATUM AND EXPRESSED AS A PERCENTAGE. STRATA ROCK QUALITY DESIGNATION (SRQD) - A MEASURE OF ROCK QUALITY DESCRIBED BY TOTAL LENGTH OF ROCK SEGMENTS WITHIN A STRATUM EQUAL TO OR GREATER THAN 4 INCHES DIVIDED BY THE TOTAL LENGTH OF STRATA AND EXPRESSED AS A PERCENTAGE. TOPSOIL (TS.) - SURFACE SOILS USUALLY CONTAINING ORGANIC MATTER.	
WEATHERED ROCK (WRI)		NON-COASTAL PLAIN MATERIAL THAT WOULD YIELD SPT N VALUES > 100 BLOWS PER FOOT IF TESTED.	
CRYSTALLINE ROCK (CRI)		FINE TO COARSE GRAIN IGNEOUS AND METAMORPHIC ROCK THAT WOULD YIELD SPT REFUSAL IF TESTED. ROCK TYPE INCLUDES GRANITE, GNEISS, GABBRO, SCHIST, ETC.	
NON-CRYSTALLINE ROCK (NCRI)		FINE TO COARSE GRAIN METAMORPHIC AND NON-COASTAL PLAIN SEDIMENTARY ROCK THAT WOULD YIELD SPT REFUSAL IF TESTED. ROCK TYPE INCLUDES PHYLLITE, SLATE, SANDSTONE, ETC.	
COASTAL PLAIN SEDIMENTARY ROCK (CPI)		COASTAL PLAIN SEDIMENTS CEMENTED INTO ROCK, BUT MAY NOT YIELD SPT REFUSAL. ROCK TYPE INCLUDES LIMESTONE, SANDSTONE, CEMENTED SHELL BEDS, ETC.	
WEATHERING			
FRESH	ROCK FRESH, CRYSTALS BRIGHT, FEW JOINTS MAY SHOW SLIGHT STAINING, ROCK RINGS UNDER HAMMER IF CRYSTALLINE.		
VERY SLIGHT (V SLI.)	ROCK GENERALLY FRESH, JOINTS STAINED, SOME JOINTS MAY SHOW THIN CLAY COATINGS IF OPEN. CRYSTALS ON A BROKEN SPECIMEN FACE SHINE BRIGHTLY, ROCK RINGS UNDER HAMMER BLOWS IF OF A CRYSTALLINE NATURE.		
SLIGHT (SLI.)	ROCK GENERALLY FRESH, JOINTS STAINED AND DISCOLORATION EXTENDS INTO ROCK UP TO 1 INCH. OPEN JOINTS MAY CONTAIN CLAY. IN GRANITOID ROCKS SOME OCCASIONAL FELDSPAR CRYSTALS ARE DULL AND DISCOLORED, CRYSTALLINE ROCKS RING UNDER HAMMER BLOWS.		
MODERATE (MOD.)	SIGNIFICANT PORTIONS OF ROCK SHOW DISCOLORATION AND WEATHERING EFFECTS. IN GRANITOID ROCKS, MOST FELDSPARS ARE DULL AND DISCOLORED, SOME SHOW CLAY. ROCK HAS DULL SOUND UNDER HAMMER BLOWS AND SHOWS SIGNIFICANT LOSS OF STRENGTH AS COMPARED WITH FRESH ROCK.		
MODERATELY SEVERE (MOD. SEV.)	ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED. IN GRANITOID ROCKS, ALL FELDSPARS DULL AND DISCOLORED AND A MAJORITY SHOW KAOLINIZATION. ROCK SHOWS SEVERE LOSS OF STRENGTH AND CAN BE EXCAVATED WITH A GEOLOGIST'S PICK. ROCK GIVES "CLUNK" SOUND WHEN STRUCK. <u>IF TESTED, WOULD YIELD SPT REFUSAL</u>		
SEVERE (SEV.)	ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED. ROCK FABRIC CLEAR AND EVIDENT BUT REDUCED IN STRENGTH TO STRONG SOIL. IN GRANITOID ROCKS ALL FELDSPARS ARE KAOLINIZED TO SOME EXTENT. SOME FRAGMENTS OF STRONG ROCK USUALLY REMAIN. <u>IF TESTED, YIELDS SPT N VALUES > 100 BPF</u>		
VERY SEVERE (V SEV.)	ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED. ROCK FABRIC ELEMENTS ARE DISCERNIBLE BUT THE MASS IS EFFECTIVELY REDUCED TO SOIL STATUS, WITH ONLY FRAGMENTS OF STRONG ROCK REMAINING. SAPROLITE IS AN EXAMPLE OF ROCK WEATHERED TO A DEGREE SUCH THAT ONLY MINOR VESTIGES OF THE ORIGINAL ROCK FABRIC REMAIN. <u>IF TESTED, YIELDS SPT N VALUES < 100 BPF</u>		
COMPLETE	ROCK REDUCED TO SOIL. ROCK FABRIC NOT DISCERNIBLE, OR DISCERNIBLE ONLY IN SMALL AND SCATTERED CONCENTRATIONS. QUARTZ MAY BE PRESENT AS DIKES OR STRINGERS. SAPROLITE IS ALSO AN EXAMPLE.		
ROCK HARDNESS			
VERY HARD	CANNOT BE SCRATCHED BY KNIFE OR SHARP PICK. BREAKING OF HAND SPECIMENS REQUIRES SEVERAL HARD BLOWS OF THE GEOLOGIST'S PICK.		
HARD	CAN BE SCRATCHED BY KNIFE OR PICK ONLY WITH DIFFICULTY. HARD HAMMER BLOWS REQUIRED TO DETACH HAND SPECIMEN.		
MODERATELY HARD	CAN BE SCRATCHED BY KNIFE OR PICK. GOUGES OR GROOVES TO 0.25 INCHES DEEP CAN BE EXCAVATED BY HARD BLOW OF A GEOLOGIST'S PICK. HAND SPECIMENS CAN BE DETACHED BY MODERATE BLOWS.		
MEDIUM HARD	CAN BE GROOVED OR GOUGED 0.05 INCHES DEEP BY FIRM PRESSURE OF KNIFE OR PICK POINT. CAN BE EXCAVATED IN SMALL CHIPS TO PIECES 1 INCH MAXIMUM SIZE BY HARD BLOWS OF THE POINT OF A GEOLOGIST'S PICK.		
SOFT	CAN BE GROOVED OR GOUGED READILY BY KNIFE OR PICK. CAN BE EXCAVATED IN FRAGMENTS FROM CHIPS TO SEVERAL INCHES IN SIZE BY MODERATE BLOWS OF A PICK POINT. SMALL, THIN PIECES CAN BE BROKEN BY FINGER PRESSURE.		
VERY SOFT	CAN BE CARVED WITH KNIFE. CAN BE EXCAVATED READILY WITH POINT OF PICK. PIECES 1 INCH OR MORE IN THICKNESS CAN BE BROKEN BY FINGER PRESSURE. CAN BE SCRATCHED READILY BY FINGER NAIL.		
FRACTURE SPACING		BEDDING	
TERM	SPACING	TERM	THICKNESS
VERY WIDE	MORE THAN 10 FEET	VERY THICKLY BEDDED	> 4 FEET
WIDE	3 TO 10 FEET	THICKLY BEDDED	1.5 - 4 FEET
MODERATELY CLOSE	1 TO 3 FEET	THINLY BEDDED	0.16 - 1.5 FEET
CLOSE	0.16 TO 1 FEET	VERY THINLY BEDDED	0.03 - 0.16 FEET
VERY CLOSE	LESS THAN 0.16 FEET	THICKLY LAMINATED	0.008 - 0.03 FEET
		THINLY LAMINATED	< 0.008 FEET
INDURATION			
FOR SEDIMENTARY ROCKS, INDURATION IS THE HARDENING OF THE MATERIAL BY CEMENTING, HEAT, PRESSURE, ETC.			
FRIABLE	RUBBING WITH FINGER FREES NUMEROUS GRAINS; GENTLE BLOW BY HAMMER DISINTEGRATES SAMPLE.		
MODERATELY INDURATED	GRAINS CAN BE SEPARATED FROM SAMPLE WITH STEEL PROBE; BREAKS EASILY WHEN HIT WITH HAMMER.		
INDURATED	GRAINS ARE DIFFICULT TO SEPARATE WITH STEEL PROBE; DIFFICULT TO BREAK WITH HAMMER.		
EXTREMELY INDURATED	SHARP HAMMER BLOWS REQUIRED TO BREAK SAMPLE; SAMPLE BREAKS ACROSS GRAINS.		

BENCH MARK: REFERENCE "C" MARKED ON BRIDGE DECK IN N.E. CORNER	
ELEVATION: 100.00 FT.	

NOTES:

BM - BENCH MARK

BENCH MARK: REFERENCE 'C' MARKED ON BRIDGE DECK IN N.E. CORNER

ELEVATION: 100.00 FT.

NOTES:

 **BM - BENCH MARK**



0 40 80
 FEET

SCALE: 1" = 40'

DATE: JULY 2012

DRAWN BY: BTR

PROJECT NO:
 1051-12-0651



S&ME
WWW.SMEINC.COM

NC ENGINEER LICENSE #F-0176
 3201 SPRING FOREST RD, RALEIGH, NC 27616

BORING LOCATION MAP
 BRIDGE NO. 144
 OVER CREEK ON SR-1317
 STATE PROJ NO. 17BP.13.R.79
 YANCEY COUNTY, NORTH CAROLINA

FIGURE NO.

3



NCDOT GEOTECHNICAL ENGINEERING UNIT BORELOG REPORT

SHEET 4

WBS 17BP.13.R.79		TIP 17BP.13.R.79		COUNTY YANCEY		GEOLOGIST Brandsen, J.	
SITE DESCRIPTION Bridge No. 144 over Creek on SR. 1317							GROUND WTR (ft)
BORING NO. EB1-A		STATION N/A		OFFSET N/A		ALIGNMENT N/A	
COLLAR ELEV. 100.5 ft		TOTAL DEPTH 12.0 ft		NORTHING 830,843		EASTING 1,044,761	
DRILL RIG/HAMMER EFF./DATE SME CME-45B 77% 6/29/12		DRILL METHOD SPT Core Boring		HAMMER TYPE Automatic			
DRILLER Hardee, S.		START DATE 04/13/12		COMP. DATE 04/13/12		SURFACE WATER DEPTH N/A	

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION		
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				ELEV. (ft)	DEPTH (ft)	
105																
100	99.5	1.0	3	7	13										PAVEMENT	0.0
	97.9	2.6	60/0.0												Asphalt and CABC Stone	0.6
95															COLLUVIAL	2.6
															Tan-Brown Silty Fine SAND with Some Rock Fragments	
															Boulders	
90	91.9	8.6	100/0.4												WEATHERED ROCK	8.6
	88.5	12.0	60/0.0												Weathered Rock (Gneiss)	12.0
															Boring Terminated with Standard Penetration Test Refusal at Elevation 88.5 ft on Crystalline Rock (Gneiss) 1) Advanced 3-1/4" HSA to 2.6 feet. 2) Advanced NWD4 Core Barrel from 2.6 ft to 8.6 ft. 3) Advanced 2 15/16" Tricone to 12.0 ft. 4) Creek Water Used As Drilling Fluid. 5) Some Drilling Fluid Loss Observed. 6) Approximate Drilling Fluid Density 62.4 PCF.	



NCDOT GEOTECHNICAL ENGINEERING UNIT

CORE BORING REPORT

SHEET 5

WBS 17BP.13.R.79				TIP 17BP.13.R.79				COUNTY YANCEY				GEOLOGIST Brandsen, J.			
SITE DESCRIPTION Bridge No. 144 over Creek on SR. 1317												GROUND WTR (ft)			
BORING NO. EB1-A				STATION N/A				OFFSET N/A				ALIGNMENT N/A			
COLLAR ELEV. 100.5 ft				TOTAL DEPTH 12.0 ft				NORTHING 830,843				EASTING 1,044,761			
DRILL RIG/HAMMER EFF./DATE SME CME-45B 77% 6/29/12				DRILL METHOD SPT Core Boring				HAMMER TYPE Automatic				0 HR. N/A		24 HR. FIAD	
DRILLER Hardee, S.				START DATE 04/13/12				COMP. DATE 04/13/12				SURFACE WATER DEPTH N/A			
CORE SIZE NWD4				TOTAL RUN 6.0 ft											
ELEV (ft)	RUN ELEV (ft)	DEPTH (ft)	RUN (ft)	DRILL RATE (Min/ft)	RUN		SAMP. NO.	STRATA		LOG	DESCRIPTION AND REMARKS	DEPTH (ft)			
					REC. (ft) %	RQD (ft) %		REC. (ft) %	RQD (ft) %						
97.9	97.9	2.6	6.0	N=60/0.0 0:56/1.0 0:24/1.0 0:22/1.0 0:23/1.0 1:10/1.0 1:40/1.0	(2.5) 42%			(2.5) 42%		Begin Coring @ 2.6 ft					
95											Boulders	2.6			
	91.9	8.6													
90				N=100/0.4							WEATHERED ROCK (Gneiss)	8.6			
				N=60/0.0											
											Boring Terminated with Standard Penetration Test Refusal at Elevation 88.5 ft on Crystalline Rock (Gneiss)	12.0			
											1) Advanced 3-1/4" HSA to 2.6 feet. 2) Advanced NWD4 Core Barrel from 2.6 ft to 8.6 ft. 3) Advanced 2 15/16" Tricone to 12.0 ft. 4) Creek Water Used As Drilling Fluid. 5) Some Drilling Fluid Loss Observed. 6) Approximate Drilling Fluid Density 62.4 PCF.				

CORE PHOTOGRAPHS

EB1-A BOX 1: 2.6-8.6 FEET





NCDOT GEOTECHNICAL ENGINEERING UNIT

BORELOG REPORT

SHEET 7

WBS 17BP.13.R.79		TIP 17BP.13.R.79		COUNTY YANCEY		GEOLOGIST Brandsen, J.	
SITE DESCRIPTION Bridge No. 144 over Creek on SR. 1317							GROUND WTR (ft)
BORING NO. EB1-B		STATION N/A		OFFSET N/A		ALIGNMENT N/A	
COLLAR ELEV. 100.1 ft		TOTAL DEPTH 13.9 ft		NORTHING 830,860		EASTING 1,044,748	
DRILL RIG/HAMMER EFF/DATE SME CME-45B 77% 6/29/12		DRILL METHOD SPT Core Boring		HAMMER TYPE Automatic			
DRILLER Hardee, S.		START DATE 04/17/12		COMP. DATE 04/17/12		SURFACE WATER DEPTH N/A	

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION		
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				ELEV. (ft)	DEPTH (ft)	
105																
100	99.1	1.0	7	6	8										100.1	0.0
	96.6	3.5	24	24	14										99.4	0.7
95																
	91.4	8.7	60/0.0												94.1	6.0
90															91.4	8.7
															86.2	13.9
Boring Terminated at Elevation 86.2 ft in Crystalline Rock (Gneiss) 1) Advanced 3-1/4" HSA to 8.7 feet. 2) Advanced NWD4 Core from 8.7 feet to 13.9 feet. 3) Creek Water Used As Drilling Fluid. 4) Some Drilling Fluid Loss Observed. 5) Approximate Drilling Fluid Density 62.4 PCF.																



NCDOT GEOTECHNICAL ENGINEERING UNIT

CORE BORING REPORT

SHEET 8

WBS 17BP.13.R.79				TIP 17BP.13.R.79				COUNTY YANCEY				GEOLOGIST Brandsen, J.			
SITE DESCRIPTION Bridge No. 144 over Creek on SR. 1317												GROUND WTR (ft)			
BORING NO. EB1-B				STATION N/A				OFFSET N/A				ALIGNMENT N/A			
COLLAR ELEV. 100.1 ft				TOTAL DEPTH 13.9 ft				NORTHING 830,860				EASTING 1,044,748			
DRILL RIG/HAMMER EFF./DATE SME CME-45B 77% 6/29/12								DRILL METHOD SPT Core Boring				HAMMER TYPE Automatic			
DRILLER Hardee, S.				START DATE 04/17/12				COMP. DATE 04/17/12				SURFACE WATER DEPTH N/A			
CORE SIZE NWD4				TOTAL RUN 5.2 ft											
ELEV (ft)	RUN ELEV (ft)	DEPTH (ft)	RUN (ft)	DRILL RATE (Min/ft)	RUN		SAMP. NO.	STRATA		LOG	ELEV. (ft)	DESCRIPTION AND REMARKS	DEPTH (ft)		
					REC. (ft) %	RQD (ft) %		REC. (ft) %	RQD (ft) %						
91.4															
90	91.4	8.7	5.2	N=60/0.0 1:21/1.0 :05/0.3 :21/1.0 :22/1.0 :17/1.0 :47/0.9	(5.2) 100%	(4.7) 90%		(5.2) 100%	(4.7) 90%		91.4	Begin Coring @ 8.7 ft	8.7		
	86.2	13.9									86.2	CRYSTALLINE ROCK Fresh to Moderately Weathered Hard to Moderately Hard Black-Gray (Gneiss) With Wide to Close Fracture Spacing 3 Joints at 35° to 45° 1 Joint at 60°	13.9		
Boring Terminated at Elevation 86.2 ft in Crystalline Rock (Gneiss)															
1) Advanced 3-1/4" HSA to 8.7 feet. 2) Advanced NWD4 Core from 8.7 feet to 13.9 feet. 3) Creek Water Used As Drilling Fluid. 4) Some Drilling Fluid Loss Observed. 5) Approximate Drilling Fluid Density 62.4 PCF.															

CORE PHOTOGRAPHS

EB1-B

BOX 1: 8.7-13.9 FEET





WBS 17BP.13.R.79			TIP 17BP.13.R.79			COUNTY YANCEY			GEOLOGIST Brandsen, J.							
SITE DESCRIPTION Bridge No. 144 over Creek on SR. 1317									GROUND WTR (ft)							
BORING NO. EB2-A			STATION N/A			OFFSET N/A			ALIGNMENT N/A			0 HR. FIAD				
COLLAR ELEV. 100.0 ft			TOTAL DEPTH 7.4 ft			NORTHING 830,868			EASTING 1,044,663			24 HR. FIAD				
DRILL RIG/HAMMER EFF./DATE SME CME-45B 77% 6/29/12						DRILL METHOD H.S. Augers			HAMMER TYPE Automatic							
DRILLER Hardee, S.			START DATE 04/12/12			COMP. DATE 04/12/12			SURFACE WATER DEPTH N/A							
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION		DEPTH (ft)
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				ELEV. (ft)		
100														100.0	PAVEMENT	0.0
	99.0	1.0												99.4	Asphalt and CABC Stone	0.6
	96.5	3.5	1	2	3	5							M		ALLUVIAL	
95			2	2	2	4							W		Tan Silty Fine SAND	
	92.6	7.4												92.6		7.4
			60/0.0			60/0.0								Boring Terminated with Standard Penetration Test Refusal at Elevation 92.6 ft on Crystalline Rock (Gneiss)		
														1) Advanced 3-1/4" HSA to 7.4 feet.		



NCDOT GEOTECHNICAL ENGINEERING UNIT

BORELOG REPORT

SHEET 11

WBS 17BP.13.R.79		TIP 17BP.13.R.79		COUNTY YANCEY		GEOLOGIST Brandsen, J.	
SITE DESCRIPTION Bridge No. 144 over Creek on SR. 1317							GROUND WTR (ft)
BORING NO. EB2-B		STATION N/A		OFFSET N/A		ALIGNMENT N/A	
COLLAR ELEV. 100.2 ft		TOTAL DEPTH 16.9 ft		NORTHING 830,879		EASTING 1,044,668	
DRILL RIG/HAMMER EFF./DATE SME CME-45B 77% 6/29/12				DRILL METHOD SPT Core Boring		HAMMER TYPE Automatic	
DRILLER Hardee, S.		START DATE 04/12/12		COMP. DATE 04/12/12		SURFACE WATER DEPTH N/A	

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100						
105																
100	99.2	1.0	6	6	8										PAVEMENT	0.0
	96.7	3.5	1	3	3										ROADWAY EMBANKMENT	2.5
95	94.3	5.9	60/0.0												ALLUVIAL	
															COLLUVIAL	
90															Boulders	
85															CRYSTALLINE ROCK	
															(Gneiss)	16.9
															Boring Terminated at Elevation 83.3 ft in Crystalline Rock (Gneiss) 1) Advanced 3-1/4" HSA to 5.9 feet. 2) Advanced NWD4 Core Barrel from 5.9 feet to 16.9 feet. 3) Creek Water Used As Drilling Fluid. 4) Some Drilling Fluid Loss Observed. 5) Approximate Drilling Fluid Density 62.4 PCF.	



NCDOT GEOTECHNICAL ENGINEERING UNIT CORE BORING REPORT

SHEET 12

WBS 17BP.13.R.79		TIP 17BP.13.R.79		COUNTY YANCEY		GEOLOGIST Brandsen, J.						
SITE DESCRIPTION Bridge No. 144 over Creek on SR. 1317							GROUND WTR (ft)					
BORING NO. EB2-B		STATION N/A		OFFSET N/A		ALIGNMENT N/A						
COLLAR ELEV. 100.2 ft		TOTAL DEPTH 16.9 ft		NORTHING 830,879		EASTING 1,044,668						
DRILL RIG/HAMMER EFF./DATE SME CME-45B 77% 6/29/12		DRILL METHOD SPT Core Boring		HAMMER TYPE Automatic								
DRILLER Hardee, S.		START DATE 04/12/12		COMP. DATE 04/12/12		SURFACE WATER DEPTH N/A						
CORE SIZE NWD4		TOTAL RUN 11.0 ft										
ELEV (ft)	RUN ELEV (ft)	DEPTH (ft)	RUN (ft)	DRILL RATE (Min/ft)	RUN REC. (ft) %	RUN RQD (ft) %	SAMP. NO.	STRATA REC. (ft) %	STRATA RQD (ft) %	LOG	DESCRIPTION AND REMARKS	DEPTH (ft)
94.3	94.3	5.9	6.0	N=60/0.0 2:30/1.0 1:05/1.0 0:53/1.0 2:38/1.0 2:38/1.0 3:10/1.0	(3.3) 55%			(3.8) 47%		94.3	Begin Coring @ 5.9 ft	
90	88.3	11.9									COLLUVIAL Boulders	5.9
85			5.0	2:10/1.0 2:08/1.0 2:18/1.0 2:05/1.0 2:16/1.0	(3.4) 68%	(1.9) 38%		(2.2) 76%	(1.9) 66%	86.2	CRYSTALLINE ROCK Fresh to Severely Weathered Hard to Medium Hard Gray-Black (Gneiss) With Close Fracture Spacing 3 Joints at 45° 3 Joints at 90°	14.0
	83.3	16.9								83.3	Boring Terminated at Elevation 83.3 ft in Crystalline Rock (Gneiss)	16.9

1) Advanced 3-1/4" HSA to 5.9 feet.
2) Advanced NWD4 Core Barrel from 5.9 feet to 16.9 feet.
3) Creek Water Used As Drilling Fluid.
4) Some Drilling Fluid Loss Observed.
5) Approximate Drilling Fluid Density 62.4 PCF.

CORE PHOTOGRAPHS

EB2-B

BOX 1: 5.9-16.9 FEET

