

STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	17BP.12.R.41	1	5

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
GEOTECHNICAL ENGINEERING UNIT

STRUCTURE
SUBSURFACE INVESTIGATION

PROJ. REFERENCE NO. 17BP.12.R.41 F.A. PROJ. _____
COUNTY ALEXANDER
PROJECT DESCRIPTION BRIDGE 081 ON SR 1332 (SHEW RD.)
OVER LITTLE RIVER

SITE DESCRIPTION _____

CONTENTS

<u>SHEET</u>	<u>DESCRIPTION</u>
1	TITLE SHEET
2-2A	LEGEND
3	SITE PLAN
4-5	BORE LOGS

PERSONNEL

J.K. STICKNEY

C.L. SMITH

INVESTIGATED BY **C.B. LITTLE**

CHECKED BY **C.B. LITTLE**

SUBMITTED BY **C.B. LITTLE**

DATE **NOVEMBER 2013**

CAUTION NOTICE

THE SUBSURFACE INFORMATION AND THE SUBSURFACE INVESTIGATION ON WHICH IT IS BASED WERE MADE FOR THE PURPOSE OF PREPARING THE SCOPE OF WORK TO BE INCLUDED IN THE REQUEST FOR PROPOSAL. THE VARIOUS FIELD BORING LOGS, ROCK CORES, AND SOIL TEST DATA AVAILABLE MAY BE REVIEWED OR INSPECTED IN RALEIGH BY CONTACTING THE N.C. DEPARTMENT OF TRANSPORTATION, GEOTECHNICAL ENGINEERING UNIT AT (919) 250-4088. THE SUBSURFACE PLANS AND REPORTS, FIELD BORING LOGS, ROCK CORES, AND SOIL TEST DATA ARE NOT PART OF THE CONTRACT.


SOIL AND ROCK BOUNDARIES WITHIN A BOREHOLE ARE BASED ON GEOTECHNICAL INTERPRETATION UNLESS ENCOUNTERED IN A SAMPLE. INTERPRETED BOUNDARIES MAY NOT NECESSARILY REFLECT ACTUAL SUBSURFACE CONDITIONS BETWEEN SAMPLED STRATA, AND BOREHOLE INFORMATION MAY NOT NECESSARILY REFLECT ACTUAL SUBSURFACE CONDITIONS BETWEEN BORINGS. THE LABORATORY SAMPLE DATA AND THE IN SITU (IN-PLACE) TEST DATA CAN BE RELIED ON ONLY TO THE DEGREE OF RELIABILITY INHERENT IN THE STANDARD TEST METHOD. THE OBSERVED WATER LEVELS OR SOIL MOISTURE CONDITIONS INDICATED IN THE SUBSURFACE INVESTIGATIONS ARE AS RECORDED AT THE TIME OF THE INVESTIGATION. THESE WATER LEVELS OR SOIL MOISTURE CONDITIONS MAY VARY CONSIDERABLY WITH TIME ACCORDING TO CLIMATIC CONDITIONS INCLUDING TEMPERATURES, PRECIPITATION, AND WIND, AS WELL AS OTHER NON-CLIMATIC FACTORS.

THE DEPARTMENT DOES NOT WARRANT OR GUARANTEE THE SUFFICIENCY OR ACCURACY OF THE INVESTIGATION MADE, OR OPINION OF THE DEPARTMENT AS TO THE TYPE OF MATERIALS AND CONDITIONS TO BE ENCOUNTERED. THE BIDDER OR CONTRACTOR IS CAUTIONED TO MAKE SUCH INDEPENDENT SUBSURFACE INVESTIGATIONS AS HE DEEMS NECESSARY TO SATISFY HIMSELF AS TO CONDITIONS TO BE ENCOUNTERED ON THE PROJECT. THE CONTRACTOR SHALL HAVE NO CLAIM FOR ADDITIONAL COMPENSATION OR FOR AN EXTENSION OF TIME FOR ANY REASON RESULTING FROM THE ACTUAL CONDITIONS ENCOUNTERED AT THE SITE DIFFERING FROM THOSE INDICATED IN THE SUBSURFACE INFORMATION.

NOTE - THE INFORMATION CONTAINED HEREIN IS NOT IMPLIED OR GUARANTEED BY THE N.C. DEPARTMENT OF TRANSPORTATION AS BEING ACCURATE NOR IT IS CONSIDERED TO BE PART OF THE PLANS, SPECIFICATIONS, OR CONTRACT FOR THE PROJECT.

NOTE - BY HAVING REQUESTED THIS INFORMATION THE CONTRACTOR SPECIFICALLY WAIVES ANY CLAIMS FOR INCREASED COMPENSATION OR EXTENSION OF TIME BASED ON DIFFERENCES BETWEEN THE CONDITIONS INDICATED HEREIN AND THE ACTUAL CONDITIONS AT THE PROJECT SITE.

DRAWN BY: **J.K. McCLURE**



<table border="1" style="float: right; width: 100%;"> <tr> <td style="width: 60%; padding: 2px;">PROJECT REFERENCE NO. 17BP.12.R.41</td> <td style="width: 40%; padding: 2px;">SHEET NO. 2</td> </tr> </table>						PROJECT REFERENCE NO. 17BP.12.R.41	SHEET NO. 2																																																														
PROJECT REFERENCE NO. 17BP.12.R.41	SHEET NO. 2																																																																				
NORTH CAROLINA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS GEOTECHNICAL ENGINEERING UNIT SOIL AND ROCK LEGEND, TERMS, SYMBOLS, AND ABBREVIATIONS																																																																					
SOIL DESCRIPTION			GRADATION																																																																		
SOIL IS CONSIDERED TO BE THE UNCONSOLIDATED, SEMI-CONSOLIDATED, OR WEATHERED EARTH MATERIALS THAT CAN BE PENETRATED WITH A CONTINUOUS FLIGHT POWER AUGER, AND YIELD LESS THAN 100 BLOWS PER FOOT ACCORDING TO STANDARD PENETRATION TEST (AASHTO T206, ASTM D-1586). SOIL CLASSIFICATION IS BASED ON THE AASHTO SYSTEM. BASIC DESCRIPTIONS GENERALLY SHALL INCLUDE: CONSISTENCY, COLOR, TEXTURE, MOISTURE, AASHTO CLASSIFICATION, AND OTHER PERTINENT FACTORS SUCH AS MINERALOGICAL COMPOSITION, ANGULARITY, STRUCTURE, PLASTICITY, ETC. EXAMPLE: <i>VERY STIFF, GRN, SILTY CLAY, MOST WITH INTERBEDDED FINE SAND LAYERS, HIGH PLASTIC, A-7-6</i>			WELL GRADED - INDICATES A GOOD REPRESENTATION OF PARTICLE SIZES FROM FINE TO COARSE. UNIFORM - INDICATES THAT SOIL PARTICLES ARE ALL APPROXIMATELY THE SAME SIZE. (ALSO POORLY GRADED) GAP-GRADED - INDICATES A MIXTURE OF UNIFORM PARTICLES OF TWO OR MORE SIZES.																																																																		
SOIL LEGEND AND AASHTO CLASSIFICATION			MINERALOGICAL COMPOSITION																																																																		
<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th colspan="2">GENERAL CLASS.</th> <th colspan="2">GRANULAR MATERIALS (≤ 35% PASSING #200)</th> <th colspan="2">SILT-CLAY MATERIALS (> 35% PASSING #200)</th> <th colspan="2">ORGANIC MATERIALS</th> </tr> <tr> <td>GROUP CLASS.</td> <td>A-1, A-1-b, A-2, A-2-4, A-2-5, A-2-6, A-2-7</td> <td>A-3, A-4, A-5, A-6, A-7</td> <td>A-1, A-2, A-3, A-4, A-5, A-6, A-7</td> <td colspan="4"></td> </tr> <tr> <td>SYMBOL</td> <td colspan="7"> </td> </tr> <tr> <td>% PASSING</td> <td colspan="7"> 10: 50 MX, 30 MX, 50 MX, 51 MN, 15 MX, 25 MX, 10 MX, 35 MX, 35 MX, 35 MX, 35 MX, 36 MN, 36 MN, 36 MN, 36 MN, 36 MN, 36 MN 40: 30 MX, 50 MX, 51 MN, 15 MX, 25 MX, 10 MX, 35 MX, 35 MX, 35 MX, 35 MX, 36 MN, 36 MN, 36 MN, 36 MN, 36 MN, 36 MN 200: 15 MX, 25 MX, 10 MX, 35 MX, 35 MX, 35 MX, 35 MX, 36 MN, 36 MN, 36 MN, 36 MN, 36 MN, 36 MN, 36 MN, 36 MN, 36 MN, 36 MN </td> </tr> <tr> <td>LIQUID LIMIT PLASTIC INDEX</td> <td colspan="7"> 6 MX, NP, 40 MX, 41 MN, 40 MX, 41 MN, 40 MX, 41 MN, 40 MX, 41 MN, 40 MX, 41 MN, 40 MX, 41 MN, 40 MX, 41 MN </td> </tr> <tr> <td>GROUP INDEX</td> <td colspan="7">0, 8, 0, 4 MX, 8 MX, 12 MX, 16 MX, No MX</td> </tr> <tr> <td>USUAL TYPES OF MAJOR MATERIALS</td> <td colspan="7"> STONE FRAGS, GRAVEL, AND SAND; FINE SAND; SILTY OR CLAYEY GRAVEL AND SAND; SILTY SOILS; CLAYEY SOILS; SOILS WITH LITTLE OR MODERATE AMOUNTS OF ORGANIC MATTER; HIGHLY ORGANIC SOILS </td> </tr> <tr> <td>GEN. RATING AS A SUBGRADE</td> <td colspan="7">EXCELLENT TO GOOD; FAIR TO POOR; FAIR TO POOR; POOR; UNSUITABLE</td> </tr> </table>			GENERAL CLASS.		GRANULAR MATERIALS (≤ 35% PASSING #200)		SILT-CLAY MATERIALS (> 35% PASSING #200)		ORGANIC MATERIALS		GROUP CLASS.	A-1, A-1-b, A-2, A-2-4, A-2-5, A-2-6, A-2-7	A-3, A-4, A-5, A-6, A-7	A-1, A-2, A-3, A-4, A-5, A-6, A-7					SYMBOL								% PASSING	10: 50 MX, 30 MX, 50 MX, 51 MN, 15 MX, 25 MX, 10 MX, 35 MX, 35 MX, 35 MX, 35 MX, 36 MN, 36 MN, 36 MN, 36 MN, 36 MN, 36 MN 40: 30 MX, 50 MX, 51 MN, 15 MX, 25 MX, 10 MX, 35 MX, 35 MX, 35 MX, 35 MX, 36 MN, 36 MN, 36 MN, 36 MN, 36 MN, 36 MN 200: 15 MX, 25 MX, 10 MX, 35 MX, 35 MX, 35 MX, 35 MX, 36 MN, 36 MN, 36 MN, 36 MN, 36 MN, 36 MN, 36 MN, 36 MN, 36 MN, 36 MN							LIQUID LIMIT PLASTIC INDEX	6 MX, NP, 40 MX, 41 MN, 40 MX, 41 MN, 40 MX, 41 MN, 40 MX, 41 MN, 40 MX, 41 MN, 40 MX, 41 MN, 40 MX, 41 MN							GROUP INDEX	0, 8, 0, 4 MX, 8 MX, 12 MX, 16 MX, No MX							USUAL TYPES OF MAJOR MATERIALS	STONE FRAGS, GRAVEL, AND SAND; FINE SAND; SILTY OR CLAYEY GRAVEL AND SAND; SILTY SOILS; CLAYEY SOILS; SOILS WITH LITTLE OR MODERATE AMOUNTS OF ORGANIC MATTER; HIGHLY ORGANIC SOILS							GEN. RATING AS A SUBGRADE	EXCELLENT TO GOOD; FAIR TO POOR; FAIR TO POOR; POOR; UNSUITABLE							MINERAL NAMES SUCH AS QUARTZ, FELDSPAR, MICA, TALC, KAOLIN, ETC. ARE USED IN DESCRIPTIONS WHENEVER THEY ARE CONSIDERED OF SIGNIFICANCE.		
GENERAL CLASS.		GRANULAR MATERIALS (≤ 35% PASSING #200)		SILT-CLAY MATERIALS (> 35% PASSING #200)		ORGANIC MATERIALS																																																															
GROUP CLASS.	A-1, A-1-b, A-2, A-2-4, A-2-5, A-2-6, A-2-7	A-3, A-4, A-5, A-6, A-7	A-1, A-2, A-3, A-4, A-5, A-6, A-7																																																																		
SYMBOL																																																																					
% PASSING	10: 50 MX, 30 MX, 50 MX, 51 MN, 15 MX, 25 MX, 10 MX, 35 MX, 35 MX, 35 MX, 35 MX, 36 MN, 36 MN, 36 MN, 36 MN, 36 MN, 36 MN 40: 30 MX, 50 MX, 51 MN, 15 MX, 25 MX, 10 MX, 35 MX, 35 MX, 35 MX, 35 MX, 36 MN, 36 MN, 36 MN, 36 MN, 36 MN, 36 MN 200: 15 MX, 25 MX, 10 MX, 35 MX, 35 MX, 35 MX, 35 MX, 36 MN, 36 MN, 36 MN, 36 MN, 36 MN, 36 MN, 36 MN, 36 MN, 36 MN, 36 MN																																																																				
LIQUID LIMIT PLASTIC INDEX	6 MX, NP, 40 MX, 41 MN, 40 MX, 41 MN, 40 MX, 41 MN, 40 MX, 41 MN, 40 MX, 41 MN, 40 MX, 41 MN, 40 MX, 41 MN																																																																				
GROUP INDEX	0, 8, 0, 4 MX, 8 MX, 12 MX, 16 MX, No MX																																																																				
USUAL TYPES OF MAJOR MATERIALS	STONE FRAGS, GRAVEL, AND SAND; FINE SAND; SILTY OR CLAYEY GRAVEL AND SAND; SILTY SOILS; CLAYEY SOILS; SOILS WITH LITTLE OR MODERATE AMOUNTS OF ORGANIC MATTER; HIGHLY ORGANIC SOILS																																																																				
GEN. RATING AS A SUBGRADE	EXCELLENT TO GOOD; FAIR TO POOR; FAIR TO POOR; POOR; UNSUITABLE																																																																				
CONSISTENCY OR DENSENESS			COMPRESSION																																																																		
<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th>PRIMARY SOIL TYPE</th> <th>COMPACTNESS OR CONSISTENCY</th> <th>RANGE OF STANDARD PENETRATION RESISTANCE (N-VALUE)</th> <th>RANGE OF UNCONFINED COMPRESSIVE STRENGTH (TENS/FT²)</th> </tr> <tr> <td>GENERALLY GRANULAR MATERIAL (NON-COHESIVE)</td> <td>VERY LOOSE, LOOSE, MEDIUM DENSE, DENSE, VERY DENSE</td> <td><4, 4 TO 10, 10 TO 30, 30 TO 50, >50</td> <td>N/A</td> </tr> <tr> <td>GENERALLY SILT-CLAY MATERIAL (COHESIVE)</td> <td>VERY SOFT, SOFT, MEDIUM STIFF, STIFF, VERY STIFF, HARD</td> <td><2, 2 TO 4, 4 TO 8, 8 TO 15, 15 TO 30, >30</td> <td><0.25, 0.25 TO 0.50, 0.5 TO 1.0, 1 TO 2, 2 TO 4, >4</td> </tr> </table>			PRIMARY SOIL TYPE	COMPACTNESS OR CONSISTENCY	RANGE OF STANDARD PENETRATION RESISTANCE (N-VALUE)	RANGE OF UNCONFINED COMPRESSIVE STRENGTH (TENS/FT ²)	GENERALLY GRANULAR MATERIAL (NON-COHESIVE)	VERY LOOSE, LOOSE, MEDIUM DENSE, DENSE, VERY DENSE	<4, 4 TO 10, 10 TO 30, 30 TO 50, >50	N/A	GENERALLY SILT-CLAY MATERIAL (COHESIVE)	VERY SOFT, SOFT, MEDIUM STIFF, STIFF, VERY STIFF, HARD	<2, 2 TO 4, 4 TO 8, 8 TO 15, 15 TO 30, >30	<0.25, 0.25 TO 0.50, 0.5 TO 1.0, 1 TO 2, 2 TO 4, >4	SLIGHTLY COMPRESSIBLE, MODERATELY COMPRESSIBLE, HIGHLY COMPRESSIBLE LIQUID LIMIT LESS THAN 31, LIQUID LIMIT EQUAL TO 31-50, LIQUID LIMIT GREATER THAN 50																																																						
PRIMARY SOIL TYPE	COMPACTNESS OR CONSISTENCY	RANGE OF STANDARD PENETRATION RESISTANCE (N-VALUE)	RANGE OF UNCONFINED COMPRESSIVE STRENGTH (TENS/FT ²)																																																																		
GENERALLY GRANULAR MATERIAL (NON-COHESIVE)	VERY LOOSE, LOOSE, MEDIUM DENSE, DENSE, VERY DENSE	<4, 4 TO 10, 10 TO 30, 30 TO 50, >50	N/A																																																																		
GENERALLY SILT-CLAY MATERIAL (COHESIVE)	VERY SOFT, SOFT, MEDIUM STIFF, STIFF, VERY STIFF, HARD	<2, 2 TO 4, 4 TO 8, 8 TO 15, 15 TO 30, >30	<0.25, 0.25 TO 0.50, 0.5 TO 1.0, 1 TO 2, 2 TO 4, >4																																																																		
TEXTURE OR GRAIN SIZE			PERCENTAGE OF MATERIAL																																																																		
<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th>U.S. STD. SIEVE SIZE OPENING (MM)</th> <th>4</th> <th>10</th> <th>40</th> <th>60</th> <th>200</th> <th>270</th> </tr> <tr> <td></td> <td>4.75</td> <td>2.00</td> <td>0.42</td> <td>0.25</td> <td>0.075</td> <td>0.053</td> </tr> </table>			U.S. STD. SIEVE SIZE OPENING (MM)	4	10	40	60	200	270		4.75	2.00	0.42	0.25	0.075	0.053	<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th>BOULDER (BLDR.)</th> <th>COBBLE (COB.)</th> <th>GRAVEL (GR.)</th> <th>COARSE SAND (CSE. SD.)</th> <th>FINE SAND (F SD.)</th> <th>SILT (SL.)</th> <th>CLAY (CL.)</th> </tr> <tr> <td>GRAIN SIZE</td> <td>MM 305, IN. 12</td> <td>75, 3</td> <td>2.0</td> <td>0.25</td> <td>0.05</td> <td>0.005</td> </tr> </table>			BOULDER (BLDR.)	COBBLE (COB.)	GRAVEL (GR.)	COARSE SAND (CSE. SD.)	FINE SAND (F SD.)	SILT (SL.)	CLAY (CL.)	GRAIN SIZE	MM 305, IN. 12	75, 3	2.0	0.25	0.05	0.005																																				
U.S. STD. SIEVE SIZE OPENING (MM)	4	10	40	60	200	270																																																															
	4.75	2.00	0.42	0.25	0.075	0.053																																																															
BOULDER (BLDR.)	COBBLE (COB.)	GRAVEL (GR.)	COARSE SAND (CSE. SD.)	FINE SAND (F SD.)	SILT (SL.)	CLAY (CL.)																																																															
GRAIN SIZE	MM 305, IN. 12	75, 3	2.0	0.25	0.05	0.005																																																															
SOIL MOISTURE - CORRELATION OF TERMS			GROUND WATER																																																																		
<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th>SOIL MOISTURE SCALE (ATTERBERG LIMITS)</th> <th>FIELD MOISTURE DESCRIPTION</th> <th>GUIDE FOR FIELD MOISTURE DESCRIPTION</th> </tr> <tr> <td>LL - LIQUID LIMIT</td> <td>- SATURATED - (SAT.)</td> <td>USUALLY LIQUID; VERY WET, USUALLY FROM BELOW THE GROUND WATER TABLE</td> </tr> <tr> <td>PL - PLASTIC LIMIT</td> <td>- WET - (W)</td> <td>SEMISOLID; REQUIRES DRYING TO ATTAIN OPTIMUM MOISTURE</td> </tr> <tr> <td>OM - OPTIMUM MOISTURE</td> <td>- MOIST - (M)</td> <td>SOLID; AT OR NEAR OPTIMUM MOISTURE</td> </tr> <tr> <td>SL - SHRINKAGE LIMIT</td> <td>- DRY - (D)</td> <td>REQUIRES ADDITIONAL WATER TO ATTAIN OPTIMUM MOISTURE</td> </tr> </table>			SOIL MOISTURE SCALE (ATTERBERG LIMITS)	FIELD MOISTURE DESCRIPTION	GUIDE FOR FIELD MOISTURE DESCRIPTION	LL - LIQUID LIMIT	- SATURATED - (SAT.)	USUALLY LIQUID; VERY WET, USUALLY FROM BELOW THE GROUND WATER TABLE	PL - PLASTIC LIMIT	- WET - (W)	SEMISOLID; REQUIRES DRYING TO ATTAIN OPTIMUM MOISTURE	OM - OPTIMUM MOISTURE	- MOIST - (M)	SOLID; AT OR NEAR OPTIMUM MOISTURE	SL - SHRINKAGE LIMIT	- DRY - (D)	REQUIRES ADDITIONAL WATER TO ATTAIN OPTIMUM MOISTURE	WATER LEVEL IN BORE HOLE IMMEDIATELY AFTER DRILLING STATIC WATER LEVEL AFTER 24 HOURS PERCHED WATER, SATURATED ZONE, OR WATER BEARING STRATA SPRING OR SEEP																																																			
SOIL MOISTURE SCALE (ATTERBERG LIMITS)	FIELD MOISTURE DESCRIPTION	GUIDE FOR FIELD MOISTURE DESCRIPTION																																																																			
LL - LIQUID LIMIT	- SATURATED - (SAT.)	USUALLY LIQUID; VERY WET, USUALLY FROM BELOW THE GROUND WATER TABLE																																																																			
PL - PLASTIC LIMIT	- WET - (W)	SEMISOLID; REQUIRES DRYING TO ATTAIN OPTIMUM MOISTURE																																																																			
OM - OPTIMUM MOISTURE	- MOIST - (M)	SOLID; AT OR NEAR OPTIMUM MOISTURE																																																																			
SL - SHRINKAGE LIMIT	- DRY - (D)	REQUIRES ADDITIONAL WATER TO ATTAIN OPTIMUM MOISTURE																																																																			
PLASTICITY			MISCELLANEOUS SYMBOLS																																																																		
<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th>NONPLASTIC</th> <th>LOW PLASTICITY</th> <th>MED. PLASTICITY</th> <th>HIGH PLASTICITY</th> <th>DRY STRENGTH</th> </tr> <tr> <td>0-5</td> <td>6-15</td> <td>16-25</td> <td>26 OR MORE</td> <td>VERY LOW, SLIGHT, MEDIUM, HIGH</td> </tr> </table>			NONPLASTIC	LOW PLASTICITY	MED. PLASTICITY	HIGH PLASTICITY	DRY STRENGTH	0-5	6-15	16-25	26 OR MORE	VERY LOW, SLIGHT, MEDIUM, HIGH	ROADWAY EMBANKMENT (RE) WITH SOIL DESCRIPTION SOIL SYMBOL ARTIFICIAL FILL (AF) OTHER THAN ROADWAY EMBANKMENT INFERRED SOIL BOUNDARY INFERRED ROCK LINE ALLUVIAL SOIL BOUNDARY DIP & DIP DIRECTION OF ROCK STRUCTURES TEST BORING, AUGER BORING, CORE BORING, MONITORING WELL, PIEZOMETER INSTALLATION, SLOPE INDICATOR INSTALLATION, CONE PENETROMETER TEST, SOUNDING ROD																																																								
NONPLASTIC	LOW PLASTICITY	MED. PLASTICITY	HIGH PLASTICITY	DRY STRENGTH																																																																	
0-5	6-15	16-25	26 OR MORE	VERY LOW, SLIGHT, MEDIUM, HIGH																																																																	
COLOR			ABBREVIATIONS																																																																		
DESCRIPTIONS MAY INCLUDE COLOR OR COLOR COMBINATIONS (TAN, RED, YELLOW-BROWN, BLUE-GRAY). MODIFIERS SUCH AS LIGHT, DARK, STREAKED, ETC. ARE USED TO DESCRIBE APPEARANCE.			AR - AUGER REFUSAL, BT - BORING TERMINATED, CL - CLAY, CPT - CONE PENETRATION TEST, CSE - COARSE, DMT - DILATOMETER TEST, DPT - DYNAMIC PENETRATION TEST, e - VOID RATIO, F - FINE, FOSS. - FOSSILIFEROUS, FRAC. - FRACTURED, FRACTURES, FRAGS. - FRAGMENTS, HL - HIGHLY, MED. - MEDIUM, MICA. - MICACEOUS, MOD. - MODERATELY, NP - NON PLASTIC, ORG. - ORGANIC, PMT - PRESSUREMETER TEST, SAP. - SAPROLITIC, SD. - SAND, SANDY, SL. - SILT, SILTY, SLI. - SLIGHTLY, TCR - TRICONE REFUSAL, w - MOISTURE CONTENT, V - VERY, VST - VANE SHEAR TEST, WEA. - WEATHERED, γ - UNIT WEIGHT, γ _d - DRY UNIT WEIGHT																																																																		
EQUIPMENT USED ON SUBJECT PROJECT			SAMPLE ABBREVIATIONS																																																																		
DRILL UNITS: ☐ MOBILE B- ☐ BK-51 ☐ CME-45C ☒ CME-550 ☐ PORTABLE MOIST			ADVANCING TOOLS: ☐ CLAY BITS ☐ 6" CONTINUOUS FLIGHT AUGER ☒ 8" HOLLOW AUGERS ☐ HARD FACED FINGER BITS ☒ TUNG-CARBIDE INSERTS ☒ CASING ☒ W/ ADVANCER ☐ TRICONE _____ STEEL TEETH ☒ TRICONE 2 15/16" TUNG-CARB. ☐ CORE BIT																																																																		
			HAMMER TYPE: ☒ AUTOMATIC ☐ MANUAL CORE SIZE: ☐ -B ☐ -N ☐ -H HAND TOOLS: ☐ POST HOLE DIGGER ☐ HAND AUGER ☐ SOUNDING ROD ☐ VANE SHEAR TEST																																																																		

NORTH CAROLINA DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
GEOTECHNICAL ENGINEERING UNIT
SOIL AND ROCK LEGEND, TERMS, SYMBOLS, AND ABBREVIATIONS

ROCK DESCRIPTION		TERMS AND DEFINITIONS	
HARD ROCK IS NON-COASTAL PLAIN MATERIAL THAT IF TESTED, WOULD YIELD SPT REFUSAL. AN INFERRED ROCK LINE INDICATES THE LEVEL AT WHICH NON-COASTAL PLAIN MATERIAL WOULD YIELD SPT REFUSAL. SPT REFUSAL IS PENETRATION BY A SPLIT SPOON SAMPLER EQUAL TO OR LESS THAN 0.1 FOOT PER 60 BLOWS. IN NON-COASTAL PLAIN MATERIAL, THE TRANSITION BETWEEN SOIL AND ROCK IS OFTEN REPRESENTED BY A ZONE OF WEATHERED ROCK. ROCK MATERIALS ARE TYPICALLY DIVIDED AS FOLLOWS:		ALLUVIUM (ALLUV.) - SOILS THAT HAVE BEEN TRANSPORTED BY WATER. AQUIFER - A WATER BEARING FORMATION OR STRATA. ARENACEOUS - APPLIED TO ROCKS THAT HAVE BEEN DERIVED FROM SAND OR THAT CONTAIN SAND. ARGILLACEOUS - APPLIED TO ALL ROCKS OR SUBSTANCES COMPOSED OF CLAY MINERALS, OR HAVING A NOTABLE PROPORTION OF CLAY IN THEIR COMPOSITION, AS SHALE, SLATE, ETC. ARTESIAN - GROUND WATER THAT IS UNDER SUFFICIENT PRESSURE TO RISE ABOVE THE LEVEL AT WHICH IT IS ENCOUNTERED, BUT WHICH DOES NOT NECESSARILY RISE TO OR ABOVE THE GROUND SURFACE. CALCAREOUS (CALC.) - SOILS THAT CONTAIN APPRECIABLE AMOUNTS OF CALCIUM CARBONATE. COLLUVIUM - ROCK FRAGMENTS MIXED WITH SOIL DEPOSITED BY GRAVITY ON SLOPE OR AT BOTTOM OF SLOPE. CORE RECOVERY (REC.) - TOTAL LENGTH OF ALL MATERIAL RECOVERED IN THE CORE BARREL DIVIDED BY TOTAL LENGTH OF CORE RUN AND EXPRESSED AS A PERCENTAGE. DIKE - A TABULAR BODY OF IGNEOUS ROCK THAT CUTS ACROSS THE STRUCTURE OF ADJACENT ROCKS OR CUTS MASSIVE ROCK. DIP - THE ANGLE AT WHICH A STRATUM OR ANY PLANAR FEATURE IS INCLINED FROM THE HORIZONTAL. DIP DIRECTION (DIP AZIMUTH) - THE DIRECTION OR BEARING OF THE HORIZONTAL TRACE OF THE LINE OF DIP, MEASURED CLOCKWISE FROM NORTH. FAULT - A FRACTURE OR FRACTURE ZONE ALONG WHICH THERE HAS BEEN DISPLACEMENT OF THE SIDES RELATIVE TO ONE ANOTHER PARALLEL TO THE FRACTURE. FISSILE - A PROPERTY OF SPLITTING ALONG CLOSELY SPACED PARALLEL PLANES. FLOAT - ROCK FRAGMENTS ON SURFACE NEAR THEIR ORIGINAL POSITION AND DISLOOED FROM PARENT MATERIAL. FLOOD PLAIN (FP) - LAND BORDERING A STREAM, BUILT OF SEDIMENTS DEPOSITED BY THE STREAM. FORMATION (FM.) - A MAPPABLE GEOLOGIC UNIT THAT CAN BE RECOGNIZED AND TRACED IN THE FIELD. JOINT - FRACTURE IN ROCK ALONG WHICH NO APPRECIABLE MOVEMENT HAS OCCURRED. LEDGE - A SHELF-LIKE RIDGE OR PROJECTION OF ROCK WHOSE THICKNESS IS SMALL COMPARED TO ITS LATERAL EXTENT. LENS - A BODY OF SOIL OR ROCK THAT THINS OUT IN ONE OR MORE DIRECTIONS. MOTTLED (MOT.) - IRREGULARLY MARKED WITH SPOTS OF DIFFERENT COLORS. MOTTLING IN SOILS USUALLY INDICATES POOR AERATION AND LACK OF GOOD DRAINAGE. PERCHED WATER - WATER MAINTAINED ABOVE THE NORMAL GROUND WATER LEVEL BY THE PRESENCE OF AN INTERVENING IMPERVIOUS STRATUM. RESIDUAL (RES.) SOIL - SOIL FORMED IN PLACE BY THE WEATHERING OF ROCK. ROCK QUALITY DESIGNATION (RQD) - A MEASURE OF ROCK QUALITY DESCRIBED BY TOTAL LENGTH OF ROCK SEGMENTS EQUAL TO OR GREATER THAN 4 INCHES DIVIDED BY THE TOTAL LENGTH OF CORE RUN AND EXPRESSED AS A PERCENTAGE. SAPROLITE (SAP.) - RESIDUAL SOIL THAT RETAINS THE RELIC STRUCTURE OR FABRIC OF THE PARENT ROCK. SILL - AN INTRUSIVE BODY OF IGNEOUS ROCK OF APPROXIMATELY UNIFORM THICKNESS AND RELATIVELY THIN COMPARED WITH ITS LATERAL EXTENT, THAT HAS BEEN EMPLACED PARALLEL TO THE BEDDING OR SCHISTOSITY OF THE INTRUDED ROCKS. SLICKENSIDE - POLISHED AND STRIATED SURFACE THAT RESULTS FROM FRICTION ALONG A FAULT OR SLIP PLANE. STANDARD PENETRATION TEST (PENETRATION RESISTANCE) (SPT) - NUMBER OF BLOWS (N OR BPF) OF A 140 LB. HAMMER FALLING 30 INCHES REQUIRED TO PRODUCE A PENETRATION OF 1 FOOT INTO SOIL WITH A 2 INCH OUTSIDE DIAMETER SPLIT SPOON SAMPLER. SPT REFUSAL IS PENETRATION EQUAL TO OR LESS THAN 0.1 FOOT PER 60 BLOWS. STRATA CORE RECOVERY (SREC.) - TOTAL LENGTH OF STRATA MATERIAL RECOVERED DIVIDED BY TOTAL LENGTH OF STRATUM AND EXPRESSED AS A PERCENTAGE. STRATA ROCK QUALITY DESIGNATION (SRQD) - A MEASURE OF ROCK QUALITY DESCRIBED BY TOTAL LENGTH OF ROCK SEGMENTS WITHIN A STRATUM EQUAL TO OR GREATER THAN 4 INCHES DIVIDED BY THE TOTAL LENGTH OF STRATA AND EXPRESSED AS A PERCENTAGE. TOPSOIL (TS.) - SURFACE SOILS USUALLY CONTAINING ORGANIC MATTER.	
WEATHERED ROCK (WR)		NON-COASTAL PLAIN MATERIAL THAT WOULD YIELD SPT N VALUES > 100 BLOWS PER FOOT IF TESTED.	
CRYSTALLINE ROCK (CR)		FINE TO COARSE GRAIN (IGNEOUS AND METAMORPHIC ROCK THAT WOULD YIELD SPT REFUSAL IF TESTED. ROCK TYPE INCLUDES GRANITE, GNEISS, GABBRO, SCHIST, ETC.	
NON-CRYSTALLINE ROCK (NCR)		FINE TO COARSE GRAIN METAMORPHIC AND NON-COASTAL PLAIN SEDIMENTARY ROCK THAT WOULD YIELD SPT REFUSAL IF TESTED. ROCK TYPE INCLUDES PHYLLITE, SLATE, SANDSTONE, ETC.	
COASTAL PLAIN SEDIMENTARY ROCK (CP)		COASTAL PLAIN SEDIMENTS CEMENTED INTO ROCK, BUT MAY NOT YIELD SPT REFUSAL. ROCK TYPE INCLUDES LIMESTONE, SANDSTONE, CEMENTED SHELL BEDS, ETC.	
WEATHERING			
FRESH	ROCK FRESH, CRYSTALS BRIGHT, FEW JOINTS MAY SHOW SLIGHT STAINING, ROCK RINGS UNDER HAMMER IF CRYSTALLINE.		
VERY SLIGHT (V SL.)	ROCK GENERALLY FRESH, JOINTS STAINED, SOME JOINTS MAY SHOW THIN CLAY COATINGS IF OPEN, CRYSTALS ON A BROKEN SPECIMEN FACE SHINE BRIGHTLY. ROCK RINGS UNDER HAMMER BLOWS IF OF A CRYSTALLINE NATURE.		
SLIGHT (SL.)	ROCK GENERALLY FRESH, JOINTS STAINED AND DISCOLORATION EXTENDS INTO ROCK UP TO 1 INCH. OPEN JOINTS MAY CONTAIN CLAY. IN GRANITOID ROCKS SOME OCCASIONAL FELDSPAR CRYSTALS ARE DULL AND DISCOLORED. CRYSTALLINE ROCKS RING UNDER HAMMER BLOWS.		
MODERATE (MOD.)	SIGNIFICANT PORTIONS OF ROCK SHOW DISCOLORATION AND WEATHERING EFFECTS. IN GRANITOID ROCKS, MOST FELDSPARS ARE DULL AND DISCOLORED, SOME SHOW CLAY. ROCK HAS DULL SOUND UNDER HAMMER BLOWS AND SHOWS SIGNIFICANT LOSS OF STRENGTH AS COMPARED WITH FRESH ROCK.		
MODERATELY SEVERE (MOD. SEV.)	ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED. IN GRANITOID ROCKS, ALL FELDSPARS DULL AND DISCOLORED AND A MAJORITY SHOW KAOLINIZATION. ROCK SHOWS SEVERE LOSS OF STRENGTH AND CAN BE EXCAVATED WITH A GEOLOGIST'S PICK. ROCK GIVES 'CLUNK' SOUND WHEN STRUCK. <u>IF TESTED, WOULD YIELD SPT REFUSAL.</u>		
SEVERE (SEV.)	ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED. ROCK FABRIC CLEAR AND EVIDENT BUT REDUCED IN STRENGTH TO STRONG SOIL. IN GRANITOID ROCKS ALL FELDSPARS ARE KAOLINIZED TO SOME EXTENT. SOME FRAGMENTS OF STRONG ROCK USUALLY REMAIN. <u>IF TESTED, YIELDS SPT N VALUES > 100 BPF.</u>		
VERY SEVERE (V SEV.)	ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED. ROCK FABRIC ELEMENTS ARE DISCERNIBLE BUT THE MASS IS EFFECTIVELY REDUCED TO SOIL STATUS, WITH ONLY FRAGMENTS OF STRONG ROCK REMAINING. SAPROLITE IS AN EXAMPLE OF ROCK WEATHERED TO A DEGREE SUCH THAT ONLY MINOR VESTIGES OF THE ORIGINAL ROCK FABRIC REMAIN. <u>IF TESTED, YIELDS SPT N VALUES < 100 BPF.</u>		
COMPLETE	ROCK REDUCED TO SOIL. ROCK FABRIC NOT DISCERNIBLE, OR DISCERNIBLE ONLY IN SMALL AND SCATTERED CONCENTRATIONS. QUARTZ MAY BE PRESENT AS DIKES OR STRINGERS. SAPROLITE IS ALSO AN EXAMPLE.		
ROCK HARDNESS			
VERY HARD	CANNOT BE SCRATCHED BY KNIFE OR SHARP PICK. BREAKING OF HAND SPECIMENS REQUIRES SEVERAL HARD BLOWS OF THE GEOLOGIST'S PICK.		
HARD	CAN BE SCRATCHED BY KNIFE OR PICK ONLY WITH DIFFICULTY. HARD HAMMER BLOWS REQUIRED TO DETACH HAND SPECIMEN.		
MODERATELY HARD	CAN BE SCRATCHED BY KNIFE OR PICK. GOUGES OR GROOVES TO 0.25 INCHES DEEP CAN BE EXCAVATED BY HARD BLOW OF A GEOLOGIST'S PICK. HAND SPECIMENS CAN BE DETACHED BY MODERATE BLOWS.		
MEDIUM HARD	CAN BE GROOVED OR GOUGED 0.05 INCHES DEEP BY FIRM PRESSURE OF KNIFE OR PICK POINT. CAN BE EXCAVATED IN SMALL CHIPS TO PEICES 1 INCH MAXIMUM SIZE BY HARD BLOWS OF THE POINT OF A GEOLOGIST'S PICK.		
SOFT	CAN BE GROVED OR GOUGED READILY BY KNIFE OR PICK. CAN BE EXCAVATED IN FRAGMENTS FROM CHIPS TO SEVERAL INCHES IN SIZE BY MODERATE BLOWS OF A PICK POINT. SMALL, THIN PIECES CAN BE BROKEN BY FINGER PRESSURE.		
VERY SOFT	CAN BE CARVED WITH KNIFE. CAN BE EXCAVATED READILY WITH POINT OF PICK. PIECES 1 INCH OR MORE IN THICKNESS CAN BE BROKEN BY FINGER PRESSURE. CAN BE SCRATCHED READILY BY FINGERNAIL.		
FRACTURE SPACING		BEDDING	
TERM	SPACING	TERM	THICKNESS
VERY WIDE	MORE THAN 10 FEET	VERY THICKLY BEDDED	> 4 FEET
WIDE	3 TO 10 FEET	THICKLY BEDDED	1.5 - 4 FEET
MODERATELY CLOSE	1 TO 3 FEET	THINLY BEDDED	0.16 - 1.5 FEET
CLOSE	0.16 TO 1 FEET	VERY THINLY BEDDED	0.03 - 0.16 FEET
VERY CLOSE	LESS THAN 0.16 FEET	THICKLY LAMINATED	0.008 - 0.03 FEET
		THINLY LAMINATED	< 0.008 FEET
INDURATION			
FOR SEDIMENTARY ROCKS, INDURATION IS THE HARDENING OF THE MATERIAL BY CEMENTING, HEAT, PRESSURE, ETC.			
FRIABLE	RUBBING WITH FINGER FREES NUMEROUS GRAINS; GENTLE BLOW BY HAMMER DISINTEGRATES SAMPLE.		
MODERATELY INDURATED	GRAINS CAN BE SEPARATED FROM SAMPLE WITH STEEL PROBE; BREAKS EASILY WHEN HIT WITH HAMMER.		
INDURATED	GRAINS ARE DIFFICULT TO SEPARATE WITH STEEL PROBE; DIFFICULT TO BREAK WITH HAMMER.		
EXTREMELY INDURATED	SHARP HAMMER BLOWS REQUIRED TO BREAK SAMPLE; SAMPLE BREAKS ACROSS GRAINS.		

BENCH MARK: R.R. SPIKE IN TREE		(ASSUMED)
		ELEVATION: 100.00 FT.
NOTES: NO SURVEY DATA AVAILABLE AT THE TIME OF THIS REPORT.		

BENCH MARK: R.R. SPIKE IN TREE

(ASSUMED)

ELEVATION: 100.00 FT.

NOTES:

NO SURVEY DATA AVAILABLE AT THE TIME OF THIS REPORT.

PROJECT REFERENCE NO.	SHEET
17BP.12.R.41	3
SITE PLAN	
0 60 120 FEET	



TO SR 1331 LITTLE RIVER
CHURCH RD. →

SR 1333 CHILDRESS RD.

SR 1332 SHEW RD.

LITTLE RIVER

LITTLE RIVER

NORTH



NCDOT GEOTECHNICAL ENGINEERING UNIT

BORELOG REPORT

SHEET 4

WBS 17BP.12.R.41		TIP 17BP12R41		COUNTY ALEXANDER		GEOLOGIST Stickney, J. K.	
SITE DESCRIPTION BRIDGE 081 ON SR 1332 (SHEW RD.) OVER LITTLE RIVER							GROUND WTR (ft)
BORING NO. B-1		STATION N/A		OFFSET N/A		ALIGNMENT -EL-	
COLLAR ELEV. 102.1 ft		TOTAL DEPTH 43.7 ft		NORTHING 816,375		EASTING 1,336,514	
DRILL RIG/HAMMER EFF./DATE HFO0072 CME-550 86% 01/09/2013		DRILL METHOD H.S. Augers		HAMMER TYPE Automatic			
DRILLER Smith, C. L.		START DATE 08/26/13		COMP. DATE 08/26/13		SURFACE WATER DEPTH N/A	

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				
105														
														102.1 GROUND SURFACE 0.0
100	98.2	3.9	1	3	3								M	ROADWAY EMBANKMENT RED-BRN MED. STIFF MOIST SANDY SILTY CLAY (A-7)
95	93.2	8.9	3	4	4								M	ALLUVIAL RED-YELLOW-TAN MED. STIFF TO STIFF MOIST SANDY SILTY CLAY (A-7)
90	88.2	13.9	2	3	2								M	
85	83.2	18.9	1	2	1								M/W	RESIDUAL BRN-GOLD SOFT TO V. STIFF MOIST TO WET V. MICA. CLAYEY SANDY SILT (A-4) W/ LAYERS OF TAN-GRAY MED. STIFF MOIST MICA. CLAYEY SANDY SILT @ 14.4-18.9
80	78.2	23.9	12	10	11									
75	73.2	28.9	11	10	18								M	RESIDUAL RED-ORANGE V. STIFF TO HARD MOIST MICA. SILTY SANDY CLAY (A-7)
70	68.2	33.9	12	14	14								M	
65	63.2	38.9	13	18	50								M	
60														58.4 Boring Terminated BY AUGER REFUSAL at Elevation 58.4 ft ON CRYSTALLINE ROCK
														43.7

NOTE: NO SURVEY DATA AVAILABLE AT THE TIME OF THIS REPORT
ALL BORING ELEVATIONS ARE ASSUMED.
NORTHING & EASTINGS FOR ALL BORINGS CAME FROM MICROSTATION MAP FILE
(002&000_GEO_map_BRDG0081_ALEXANDER.dgn)
LOCATIONS BASED ON BORING LAYOUTS IN THE FIELD FROM THE EXISTING BRIDGE ENDBENTS.

NCDOT BORE SINGLE 002&000_GEO_BH_BRDG0081_ALEXANDER.GPJ NC_DOT.GDT 11/5/13



NCDOT GEOTECHNICAL ENGINEERING UNIT

BORELOG REPORT

SHEET 5

WBS 17BP.12.R.41		TIP 17BP12R41		COUNTY ALEXANDER		GEOLOGIST Stickney, J. K.						
SITE DESCRIPTION BRIDGE 081 ON SR 1332 (SHEW RD.) OVER LITTLE RIVER						GROUND WTR (ft)						
BORING NO. B-2		STATION N/A		OFFSET N/A		ALIGNMENT -EL-						
COLLAR ELEV. 101.9 ft		TOTAL DEPTH 29.8 ft		NORTHING 816,305		EASTING 1,336,430						
DRILL RIG/HAMMER EFF./DATE HFO0072 CME-550 86% 01/09/2013				DRILL METHOD NW Casing w/ Advancer		HAMMER TYPE Automatic						
DRILLER Smith, C. L.		START DATE 08/27/13		COMP. DATE 08/27/13		SURFACE WATER DEPTH N/A						
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT			SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100		ELEV. (ft) DEPTH (ft)
105												
												101.9 GROUND SURFACE 0.0
100												ROADWAY EMBANKMENT
	97.5	4.4	2	3	4							RED-ORANGE MED. STIFF MOIST SANDY SILTY CLAY (A-7)
95												
	92.5	9.4	1	1	1							92.9 9.0
90												ALLUVIAL
	87.5	14.4	1	2	1							BRN SOFT TO MED. STIFF MOIST CLAYEY SILT (A-4) W/ GRAVEL LAYER @ 17.4-18.5
85												
	82.5	19.4	1	2	2							
80												
	77.5	24.4	18	20	24							79.1 22.8
75												RESIDUAL
	72.5	29.4										BRN-GRAY HARD MOIST MICA. SANDY SILTY CLAY (A-7) W/ SMALL FRAGS. OF SEV. WEATH. CRYSTALLINE ROCK
												72.5 29.4
												72.1 29.8
												CRYSTALLINE ROCK
												Boring Terminated BY TRI-CONE REFUSAL at Elevation 72.1 ft IN CRYSTALLINE ROCK
												NOTE: NO SURVEY DATA AVAILABLE AT THE TIME OF THIS REPORT
												ALL BORING ELEVATIONS ARE ASSUMED.
												NORTHING & EASTINGS FOR ALL BORINGS CAME FROM MICROSTATION MAP FILE
												(002&000_GEO_map_BRDG0081_ALEXANDER.dgn)
												LOCATIONS BASED ON BORING LAYOUTS IN THE FIELD FROM THE EXISTING BRIDGE ENDBENTS.

NCDOT BORE SINGLE 002&000_GEO_BH_BRDG0081_ALEXANDER.GPJ NC_DOT_GDT 11/5/13