

REFERENCE: B-5555

PROJECT: 46313

STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	B-5555 46313	1	7

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
GEOTECHNICAL ENGINEERING UNIT

STRUCTURE
SUBSURFACE INVESTIGATION

COUNTY TRANSYLVANIA

PROJECT DESCRIPTION EXPRESS DESIGN-BUILD
BRIDGE REPLACEMENT

SITE DESCRIPTION BRIDGE NO. 46 ON NC-215

CONTENTS

<u>SHEET NO.</u>	<u>DESCRIPTION</u>
1	TITLE SHEET
2	LEGEND
3	PLAN VIEW
4-7	BORE LOGS

PERSONNEL

DC Elliott

CJ Coffey

DO Cheek

INVESTIGATED BY PQ Lockamy

DRAWN BY PQ Lockamy

CHECKED BY JC Kuhne

SUBMITTED BY JC Kuhne

DATE 12-12-2014

CAUTION NOTICE


THE SUBSURFACE INFORMATION AND THE SUBSURFACE INVESTIGATION ON WHICH IT IS BASED WERE MADE FOR THE PURPOSE OF PREPARING THE SCOPE OF WORK TO BE INCLUDED IN THE REQUEST FOR PROPOSAL. THE VARIOUS FIELD BORING LOGS, ROCK CORES AND SOIL TEST DATA AVAILABLE MAY BE REVIEWED OR INSPECTED IN RALEIGH BY CONTACTING THE N.C. DEPARTMENT OF TRANSPORTATION, GEOTECHNICAL ENGINEERING UNIT AT (919) 707-6850. THE SUBSURFACE PLANS AND REPORTS, FIELD BORING LOGS, ROCK CORES AND SOIL TEST DATA ARE NOT PART OF THE CONTRACT.

SOIL AND ROCK BOUNDARIES WITHIN A BOREHOLE ARE BASED ON GEOTECHNICAL INTERPRETATION UNLESS ENCOUNTERED IN A SAMPLE. INTERPRETED BOUNDARIES MAY NOT NECESSARILY REFLECT ACTUAL SUBSURFACE CONDITIONS BETWEEN SAMPLED STRATA AND BOREHOLE INFORMATION MAY NOT NECESSARILY REFLECT ACTUAL SUBSURFACE CONDITIONS BETWEEN BORINGS. THE LABORATORY SAMPLE DATA AND THE IN SITU (IN-PLACE) TEST DATA CAN BE RELIED ON ONLY TO THE DEGREE OF RELIABILITY INHERENT IN THE STANDARD TEST METHOD. THE OBSERVED WATER LEVELS OR SOIL MOISTURE CONDITIONS INDICATED IN THE SUBSURFACE INVESTIGATIONS ARE AS RECORDED AT THE TIME OF THE INVESTIGATION. THESE WATER LEVELS OR SOIL MOISTURE CONDITIONS MAY VARY CONSIDERABLY WITH TIME ACCORDING TO CLIMATIC CONDITIONS INCLUDING TEMPERATURES, PRECIPITATION AND WIND, AS WELL AS OTHER NON-CLIMATIC FACTORS.

THE BIDDER OR CONTRACTOR IS CAUTIONED THAT DETAILS SHOWN ON THE SUBSURFACE PLANS ARE PRELIMINARY ONLY AND IN MANY CASES THE FINAL DESIGN DETAILS ARE DIFFERENT. FOR BIDDING AND CONSTRUCTION PURPOSES, REFER TO THE CONSTRUCTION PLANS AND DOCUMENTS FOR FINAL DESIGN INFORMATION ON THIS PROJECT. THE DEPARTMENT DOES NOT WARRANT OR GUARANTEE THE SUFFICIENCY OR ACCURACY OF THE INVESTIGATION MADE, NOR THE INTERPRETATIONS MADE, OR OPINION OF THE DEPARTMENT AS TO THE TYPE OF MATERIALS AND CONDITIONS TO BE ENCOUNTERED. THE BIDDER OR CONTRACTOR IS CAUTIONED TO MAKE SUCH INDEPENDENT SUBSURFACE INVESTIGATIONS AS HE DEEMS NECESSARY TO SATISFY HIMSELF AS TO CONDITIONS TO BE ENCOUNTERED ON THE PROJECT. THE CONTRACTOR SHALL HAVE NO CLAIM FOR ADDITIONAL COMPENSATION OR FOR AN EXTENSION OF TIME FOR ANY REASON RESULTING FROM THE ACTUAL CONDITIONS ENCOUNTERED AT THE SITE DIFFERING FROM THOSE INDICATED IN THE SUBSURFACE INFORMATION.

NOTES:

- THE INFORMATION CONTAINED HEREIN IS NOT IMPLIED OR GUARANTEED BY THE N.C. DEPARTMENT OF TRANSPORTATION AS ACCURATE NOR IS IT CONSIDERED PART OF THE PLANS, SPECIFICATIONS OR CONTRACT FOR THE PROJECT.
- BY HAVING REQUESTED THIS INFORMATION, THE CONTRACTOR SPECIFICALLY WAIVES ANY CLAIMS FOR INCREASED COMPENSATION OR EXTENSION OF TIME BASED ON DIFFERENCES BETWEEN THE CONDITIONS INDICATED HEREIN AND THE ACTUAL CONDITIONS AT THE PROJECT SITE.



SIGNATURE

DATE

NORTH CAROLINA DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
GEOTECHNICAL ENGINEERING UNIT
SUBSURFACE INVESTIGATION
SOIL AND ROCK LEGEND, TERMS, SYMBOLS, AND ABBREVIATIONS
(PAGE 1 OF 2)

SOIL DESCRIPTION SOIL IS CONSIDERED UNCONSOLIDATED, SEMI-CONSOLIDATED, OR WEATHERED EARTH MATERIALS THAT CAN BE PENETRATED WITH A CONTINUOUS FLIGHT POWER AUGER AND YIELD LESS THAN 100 BLOWS PER FOOT ACCORDING TO THE STANDARD PENETRATION TEST (AASHTO T 206, ASTM D1586). SOIL CLASSIFICATION IS BASED ON THE AASHTO SYSTEM. BASIC DESCRIPTIONS GENERALLY INCLUDE THE FOLLOWING: CONSISTENCY, COLOR, TEXTURE, MOISTURE, AASHTO CLASSIFICATION, AND OTHER PERTINENT FACTORS SUCH AS MINERALOGICAL COMPOSITION, ANGULARITY, STRUCTURE, PLASTICITY, ETC. FOR EXAMPLE, VERY STIFF, GRAY, SILTY CLAY, MOIST WITH INTERBEDDED FINE SAND LAYERS, HIGHLY PLASTIC, A-7-6										GRADATION WELL GRADED - INDICATES A GOOD REPRESENTATION OF PARTICLE SIZES FROM FINE TO COARSE. UNIFORMLY GRADED - INDICATES THAT SOIL PARTICLES ARE ALL APPROXIMATELY THE SAME SIZE. GAP-GRADED - INDICATES A MIXTURE OF UNIFORM PARTICLE SIZES OF TWO OR MORE SIZES. ANGULARITY OF GRAINS THE ANGULARITY OR ROUNDNESS OF SOIL GRAINS IS DESIGNATED BY THE TERMS: ANGULAR, SUBANGULAR, SUBROUNDED, OR ROUNDED. MINERALOGICAL COMPOSITION MINERAL NAMES SUCH AS QUARTZ, FELDSPAR, MICA, TALC, KAOLIN, ETC. ARE USED IN DESCRIPTIONS WHEN THEY ARE CONSIDERED OF SIGNIFICANCE. COMPRESSIBILITY SLIGHTLY COMPRESSIBLE LL < 31 MODERATELY COMPRESSIBLE LL = 31 - 50 HIGHLY COMPRESSIBLE LL > 50 PERCENTAGE OF MATERIAL <table><tr><td>ORGANIC MATERIAL</td><td>GRANULAR SOILS</td><td>SILT - CLAY SOILS</td><td>OTHER MATERIAL</td></tr><tr><td>TRACE OF ORGANIC MATTER</td><td>2 - 3%</td><td>3 - 5%</td><td>TRACE 1 - 10%</td></tr><tr><td>LITTLE ORGANIC MATTER</td><td>3 - 5%</td><td>5 - 12%</td><td>LITTLE 10 - 20%</td></tr><tr><td>MODERATELY ORGANIC</td><td>5 - 10%</td><td>12 - 20%</td><td>SOME 20 - 35%</td></tr><tr><td>HIGHLY ORGANIC</td><td>> 10%</td><td>> 20%</td><td>HIGHLY 35% AND ABOVE</td></tr></table> GROUND WATER WATER LEVEL IN BORE HOLE IMMEDIATELY AFTER DRILLING STATIC WATER LEVEL AFTER 24 HOURS PERCHED WATER, SATURATED ZONE, OR WATER BEARING STRATA SPRING OR SEEP										ORGANIC MATERIAL	GRANULAR SOILS	SILT - CLAY SOILS	OTHER MATERIAL	TRACE OF ORGANIC MATTER	2 - 3%	3 - 5%	TRACE 1 - 10%	LITTLE ORGANIC MATTER	3 - 5%	5 - 12%	LITTLE 10 - 20%	MODERATELY ORGANIC	5 - 10%	12 - 20%	SOME 20 - 35%	HIGHLY ORGANIC	> 10%	> 20%	HIGHLY 35% AND ABOVE																																																																																																																																																																																												
ORGANIC MATERIAL	GRANULAR SOILS	SILT - CLAY SOILS	OTHER MATERIAL																																																																																																																																																																																																																																
TRACE OF ORGANIC MATTER	2 - 3%	3 - 5%	TRACE 1 - 10%																																																																																																																																																																																																																																
LITTLE ORGANIC MATTER	3 - 5%	5 - 12%	LITTLE 10 - 20%																																																																																																																																																																																																																																
MODERATELY ORGANIC	5 - 10%	12 - 20%	SOME 20 - 35%																																																																																																																																																																																																																																
HIGHLY ORGANIC	> 10%	> 20%	HIGHLY 35% AND ABOVE																																																																																																																																																																																																																																
SOIL LEGEND AND AASHTO CLASSIFICATION <table><tr><td>GENERAL CLASS.</td><td colspan="6">GRANULAR MATERIALS (≤ 35% PASSING #200)</td><td colspan="4">SILT-CLAY MATERIALS (> 35% PASSING #200)</td><td colspan="2">ORGANIC MATERIALS</td></tr><tr><td>GROUP CLASS.</td><td colspan="2">A-1</td><td colspan="2">A-3</td><td colspan="2">A-2</td><td colspan="2">A-4</td><td colspan="2">A-5</td><td colspan="2">A-6</td><td colspan="2">A-7</td><td colspan="2">A-1, A-2</td><td colspan="2">A-4, A-5</td></tr><tr><td>SYMBOL</td><td colspan="2">A-1-a</td><td colspan="2">A-1-b</td><td colspan="2">A-2-4</td><td colspan="2">A-2-5</td><td colspan="2">A-2-6</td><td colspan="2">A-2-7</td><td colspan="2">A-4-5</td><td colspan="2">A-6, A-7</td><td colspan="2">A-7-5, A-7-6</td></tr><tr><td>% PASSING</td><td colspan="2">#10</td><td colspan="2">#40</td><td colspan="2">#200</td><td colspan="2"></td><td colspan="2"></td><td colspan="2"></td><td colspan="2"></td><td colspan="2"></td><td colspan="2"></td></tr><tr><td>MATERIAL PASSING #40</td><td colspan="2">50 MX</td><td colspan="2">30 MX</td><td colspan="2">15 MX</td><td colspan="2">50 MX</td><td colspan="2">25 MX</td><td colspan="2">10 MX</td><td colspan="2">5 MN</td><td colspan="2">35 MX</td><td colspan="2">35 MN</td></tr><tr><td>LL</td><td colspan="2">-</td><td colspan="2">-</td><td colspan="2">40 MX</td><td colspan="2">41 MN</td><td colspan="2">40 MX</td><td colspan="2">41 MN</td><td colspan="2">40 MX</td><td colspan="2">41 MN</td><td colspan="2">40 MX</td></tr><tr><td>PI</td><td colspan="2">6 MX</td><td colspan="2">NP</td><td colspan="2">10 MX</td><td colspan="2">10 MN</td><td colspan="2">11 MN</td><td colspan="2">11 MN</td><td colspan="2">10 MX</td><td colspan="2">10 MN</td><td colspan="2">11 MN</td></tr><tr><td>GROUP INDEX</td><td colspan="2">0</td><td colspan="2">0</td><td colspan="2">0</td><td colspan="2">4 MX</td><td colspan="2">8 MX</td><td colspan="2">12 MX</td><td colspan="2">16 MX</td><td colspan="2">NO MX</td><td colspan="2"></td></tr><tr><td>USUAL TYPES OF MAJOR MATERIALS</td><td colspan="2">STONE FRAGS, GRAVEL, AND SAND</td><td colspan="2">FINE SAND</td><td colspan="2">SILTY OR CLAYEY GRAVEL AND SAND</td><td colspan="2">SILTY SOILS</td><td colspan="2">CLAYEY SOILS</td><td colspan="2"></td><td colspan="2"></td><td colspan="2"></td><td colspan="2">SOILS WITH LITTLE OR MODERATE AMOUNTS OF ORGANIC MATTER</td></tr><tr><td>GEN. RATING AS SUBGRADE</td><td colspan="6">EXCELLENT TO GOOD</td><td colspan="4">FAIR TO POOR</td><td colspan="2">FAIR TO POOR</td><td colspan="2">POOR</td><td colspan="2">UNSATURABLE</td><td colspan="2"></td></tr></table> PI OF A-7-5 SUBGROUP IS ≤ LL - 30 ; PI OF A-7-6 SUBGROUP IS > LL - 30										GENERAL CLASS.	GRANULAR MATERIALS (≤ 35% PASSING #200)						SILT-CLAY MATERIALS (> 35% PASSING #200)				ORGANIC MATERIALS		GROUP CLASS.	A-1		A-3		A-2		A-4		A-5		A-6		A-7		A-1, A-2		A-4, A-5		SYMBOL	A-1-a		A-1-b		A-2-4		A-2-5		A-2-6		A-2-7		A-4-5		A-6, A-7		A-7-5, A-7-6		% PASSING	#10		#40		#200														MATERIAL PASSING #40	50 MX		30 MX		15 MX		50 MX		25 MX		10 MX		5 MN		35 MX		35 MN		LL	-		-		40 MX		41 MN		40 MX		41 MN		40 MX		41 MN		40 MX		PI	6 MX		NP		10 MX		10 MN		11 MN		11 MN		10 MX		10 MN		11 MN		GROUP INDEX	0		0		0		4 MX		8 MX		12 MX		16 MX		NO MX				USUAL TYPES OF MAJOR MATERIALS	STONE FRAGS, GRAVEL, AND SAND		FINE SAND		SILTY OR CLAYEY GRAVEL AND SAND		SILTY SOILS		CLAYEY SOILS								SOILS WITH LITTLE OR MODERATE AMOUNTS OF ORGANIC MATTER		GEN. RATING AS SUBGRADE	EXCELLENT TO GOOD						FAIR TO POOR				FAIR TO POOR		POOR		UNSATURABLE				MISCELLANEOUS SYMBOLS <table><tr><td> ROADWAY EMBANKMENT (RE) WITH SOIL DESCRIPTION</td><td> DIP & DIP DIRECTION OF ROCK STRUCTURES</td><td> TEST BORING</td><td> SLOPE INDICATOR INSTALLATION</td></tr><tr><td> SOIL SYMBOL</td><td> AUGER BORING</td><td> CONE PENETROMETER TEST</td><td> SOUNDING ROD</td></tr><tr><td> ARTIFICIAL FILL (AF) OTHER THAN ROADWAY EMBANKMENT</td><td> CORE BORING</td><td> MONITORING WELL</td><td> TEST BORING WITH CORE</td></tr><tr><td> INFERRED SOIL BOUNDARY</td><td> PIEZOMETER INSTALLATION</td><td> SPT N-VALUE</td><td></td></tr><tr><td> INFERRED ROCK LINE</td><td></td><td></td><td></td></tr><tr><td> ALLUVIAL SOIL BOUNDARY</td><td></td><td></td><td></td></tr></table>										ROADWAY EMBANKMENT (RE) WITH SOIL DESCRIPTION	DIP & DIP DIRECTION OF ROCK STRUCTURES	TEST BORING	SLOPE INDICATOR INSTALLATION	SOIL SYMBOL	AUGER BORING	CONE PENETROMETER TEST	SOUNDING ROD	ARTIFICIAL FILL (AF) OTHER THAN ROADWAY EMBANKMENT	CORE BORING	MONITORING WELL	TEST BORING WITH CORE	INFERRED SOIL BOUNDARY	PIEZOMETER INSTALLATION	SPT N-VALUE		INFERRED ROCK LINE				ALLUVIAL SOIL BOUNDARY			
GENERAL CLASS.	GRANULAR MATERIALS (≤ 35% PASSING #200)						SILT-CLAY MATERIALS (> 35% PASSING #200)				ORGANIC MATERIALS																																																																																																																																																																																																																								
GROUP CLASS.	A-1		A-3		A-2		A-4		A-5		A-6		A-7		A-1, A-2		A-4, A-5																																																																																																																																																																																																																		
SYMBOL	A-1-a		A-1-b		A-2-4		A-2-5		A-2-6		A-2-7		A-4-5		A-6, A-7		A-7-5, A-7-6																																																																																																																																																																																																																		
% PASSING	#10		#40		#200																																																																																																																																																																																																																														
MATERIAL PASSING #40	50 MX		30 MX		15 MX		50 MX		25 MX		10 MX		5 MN		35 MX		35 MN																																																																																																																																																																																																																		
LL	-		-		40 MX		41 MN		40 MX		41 MN		40 MX		41 MN		40 MX																																																																																																																																																																																																																		
PI	6 MX		NP		10 MX		10 MN		11 MN		11 MN		10 MX		10 MN		11 MN																																																																																																																																																																																																																		
GROUP INDEX	0		0		0		4 MX		8 MX		12 MX		16 MX		NO MX																																																																																																																																																																																																																				
USUAL TYPES OF MAJOR MATERIALS	STONE FRAGS, GRAVEL, AND SAND		FINE SAND		SILTY OR CLAYEY GRAVEL AND SAND		SILTY SOILS		CLAYEY SOILS								SOILS WITH LITTLE OR MODERATE AMOUNTS OF ORGANIC MATTER																																																																																																																																																																																																																		
GEN. RATING AS SUBGRADE	EXCELLENT TO GOOD						FAIR TO POOR				FAIR TO POOR		POOR		UNSATURABLE																																																																																																																																																																																																																				
ROADWAY EMBANKMENT (RE) WITH SOIL DESCRIPTION	DIP & DIP DIRECTION OF ROCK STRUCTURES	TEST BORING	SLOPE INDICATOR INSTALLATION																																																																																																																																																																																																																																
SOIL SYMBOL	AUGER BORING	CONE PENETROMETER TEST	SOUNDING ROD																																																																																																																																																																																																																																
ARTIFICIAL FILL (AF) OTHER THAN ROADWAY EMBANKMENT	CORE BORING	MONITORING WELL	TEST BORING WITH CORE																																																																																																																																																																																																																																
INFERRED SOIL BOUNDARY	PIEZOMETER INSTALLATION	SPT N-VALUE																																																																																																																																																																																																																																	
INFERRED ROCK LINE																																																																																																																																																																																																																																			
ALLUVIAL SOIL BOUNDARY																																																																																																																																																																																																																																			
TEXTURE OR GRAIN SIZE <table><tr><td>U.S. STD. SIEVE SIZE</td><td>4</td><td>10</td><td>40</td><td>60</td><td>200</td><td>270</td></tr><tr><td>OPENING (MM)</td><td>4.76</td><td>2.00</td><td>0.42</td><td>0.25</td><td>0.075</td><td>0.053</td></tr><tr><td>BOULDER (BLDR.)</td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td>COBBLE (COB.)</td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td>GRAVEL (GR.)</td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td>COARSE SAND (CSE. SD.)</td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td>FINE SAND (F SD.)</td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td>SILT (SL.)</td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td>CLAY (CL.)</td><td></td><td></td><td></td><td></td><td></td><td></td></tr></table> <table><tr><td>GRAIN SIZE</td><td>MM</td><td>305</td><td>75</td><td>2.0</td><td>0.25</td><td>0.05</td><td>0.005</td></tr><tr><td></td><td>IN.</td><td>12</td><td>3</td><td></td><td></td><td></td><td></td></tr></table>										U.S. STD. SIEVE SIZE	4	10	40	60	200	270	OPENING (MM)	4.76	2.00	0.42	0.25	0.075	0.053	BOULDER (BLDR.)							COBBLE (COB.)							GRAVEL (GR.)							COARSE SAND (CSE. SD.)							FINE SAND (F SD.)							SILT (SL.)							CLAY (CL.)							GRAIN SIZE	MM	305	75	2.0	0.25	0.05	0.005		IN.	12	3					RECOMMENDATION SYMBOLS <table><tr><td> UNDERCUT EXCAVATION</td><td> UNCLASSIFIED EXCAVATION - UNSUITABLE WASTE</td><td> UNCLASSIFIED EXCAVATION - ACCEPTABLE, BUT NOT TO BE USED IN THE TOP 3 FEET OF EMBANKMENT OR BACKFILL</td></tr><tr><td> SHALLOW UNDERCUT</td><td> UNCLASSIFIED EXCAVATION - ACCEPTABLE DEGRADABLE ROCK</td><td></td></tr></table>										UNDERCUT EXCAVATION	UNCLASSIFIED EXCAVATION - UNSUITABLE WASTE	UNCLASSIFIED EXCAVATION - ACCEPTABLE, BUT NOT TO BE USED IN THE TOP 3 FEET OF EMBANKMENT OR BACKFILL	SHALLOW UNDERCUT	UNCLASSIFIED EXCAVATION - ACCEPTABLE DEGRADABLE ROCK																																																																																																																												
U.S. STD. SIEVE SIZE	4	10	40	60	200	270																																																																																																																																																																																																																													
OPENING (MM)	4.76	2.00	0.42	0.25	0.075	0.053																																																																																																																																																																																																																													
BOULDER (BLDR.)																																																																																																																																																																																																																																			
COBBLE (COB.)																																																																																																																																																																																																																																			
GRAVEL (GR.)																																																																																																																																																																																																																																			
COARSE SAND (CSE. SD.)																																																																																																																																																																																																																																			
FINE SAND (F SD.)																																																																																																																																																																																																																																			
SILT (SL.)																																																																																																																																																																																																																																			
CLAY (CL.)																																																																																																																																																																																																																																			
GRAIN SIZE	MM	305	75	2.0	0.25	0.05	0.005																																																																																																																																																																																																																												
	IN.	12	3																																																																																																																																																																																																																																
UNDERCUT EXCAVATION	UNCLASSIFIED EXCAVATION - UNSUITABLE WASTE	UNCLASSIFIED EXCAVATION - ACCEPTABLE, BUT NOT TO BE USED IN THE TOP 3 FEET OF EMBANKMENT OR BACKFILL																																																																																																																																																																																																																																	
SHALLOW UNDERCUT	UNCLASSIFIED EXCAVATION - ACCEPTABLE DEGRADABLE ROCK																																																																																																																																																																																																																																		
SOIL MOISTURE - CORRELATION OF TERMS <table><tr><td>SOIL MOISTURE SCALE (ATTERBERG LIMITS)</td><td>FIELD MOISTURE DESCRIPTION</td><td>GUIDE FOR FIELD MOISTURE DESCRIPTION</td></tr><tr><td rowspan="4">LL PLASTIC RANGE (PI) PL</td><td>- SATURATED - (SAT.)</td><td>USUALLY LIQUID; VERY WET, USUALLY FROM BELOW THE GROUND WATER TABLE</td></tr><tr><td>- WET - (W)</td><td>SEMISOLID; REQUIRES DRYING TO ATTAIN OPTIMUM MOISTURE</td></tr><tr><td>- MOIST - (M)</td><td>SOLID; AT OR NEAR OPTIMUM MOISTURE</td></tr><tr><td>- DRY - (D)</td><td>REQUIRES ADDITIONAL WATER TO ATTAIN OPTIMUM MOISTURE</td></tr></table>										SOIL MOISTURE SCALE (ATTERBERG LIMITS)	FIELD MOISTURE DESCRIPTION	GUIDE FOR FIELD MOISTURE DESCRIPTION	LL PLASTIC RANGE (PI) PL	- SATURATED - (SAT.)	USUALLY LIQUID; VERY WET, USUALLY FROM BELOW THE GROUND WATER TABLE	- WET - (W)	SEMISOLID; REQUIRES DRYING TO ATTAIN OPTIMUM MOISTURE	- MOIST - (M)	SOLID; AT OR NEAR OPTIMUM MOISTURE	- DRY - (D)	REQUIRES ADDITIONAL WATER TO ATTAIN OPTIMUM MOISTURE	ABBREVIATIONS <table><tr><td>AR - AUGER REFUSAL</td><td>MED. - MEDIUM</td><td>VST - VANE SHEAR TEST</td></tr><tr><td>BT - BORING TERMINATED</td><td>MICA - MICACEOUS</td><td>WEA. - WEATHERED</td></tr><tr><td>CL - CLAY</td><td>MOD. - MODERATELY</td><td>γ - UNIT WEIGHT</td></tr><tr><td>CPT - CONE PENETRATION TEST</td><td>NP - NON PLASTIC</td><td>γ_d - DRY UNIT WEIGHT</td></tr><tr><td>CSE. - COARSE</td><td>ORG. - ORGANIC</td><td></td></tr><tr><td>DMT - DILATOMETER TEST</td><td>PMT - PRESSUREMETER TEST</td><td>SAMPLE ABBREVIATIONS</td></tr><tr><td>DPT - DYNAMIC PENETRATION TEST</td><td>SAP. - SAPROLITIC</td><td>S - BULK</td></tr><tr><td>e - VOID RATIO</td><td>SD. - SAND, SANDY</td><td>SS - SPLIT SPOON</td></tr><tr><td>F - FINE</td><td>SL. - SILT, SILTY</td><td>ST - SHELBY TUBE</td></tr><tr><td>FOSS. - FOSSILIFEROUS</td><td>SLI. - SLIGHTLY</td><td>RS - ROCK</td></tr><tr><td>FRAC. - FRACTURED, FRACTURES</td><td>TCR - TRICONE REFUSAL</td><td>RT - RECOMPACTED TRIAXIAL</td></tr><tr><td>FRAGS. - FRAGMENTS</td><td>w - MOISTURE CONTENT</td><td>CBR - CALIFORNIA BEARING RATIO</td></tr><tr><td>HI. - HIGHLY</td><td>V - VERY</td><td></td></tr></table>										AR - AUGER REFUSAL	MED. - MEDIUM	VST - VANE SHEAR TEST	BT - BORING TERMINATED	MICA - MICACEOUS	WEA. - WEATHERED	CL - CLAY	MOD. - MODERATELY	γ - UNIT WEIGHT	CPT - CONE PENETRATION TEST	NP - NON PLASTIC	γ _d - DRY UNIT WEIGHT	CSE. - COARSE	ORG. - ORGANIC		DMT - DILATOMETER TEST	PMT - PRESSUREMETER TEST	SAMPLE ABBREVIATIONS	DPT - DYNAMIC PENETRATION TEST	SAP. - SAPROLITIC	S - BULK	e - VOID RATIO	SD. - SAND, SANDY	SS - SPLIT SPOON	F - FINE	SL. - SILT, SILTY	ST - SHELBY TUBE	FOSS. - FOSSILIFEROUS	SLI. - SLIGHTLY	RS - ROCK	FRAC. - FRACTURED, FRACTURES	TCR - TRICONE REFUSAL	RT - RECOMPACTED TRIAXIAL	FRAGS. - FRAGMENTS	w - MOISTURE CONTENT	CBR - CALIFORNIA BEARING RATIO	HI. - HIGHLY	V - VERY																																																																																																																																																														
SOIL MOISTURE SCALE (ATTERBERG LIMITS)	FIELD MOISTURE DESCRIPTION	GUIDE FOR FIELD MOISTURE DESCRIPTION																																																																																																																																																																																																																																	
LL PLASTIC RANGE (PI) PL	- SATURATED - (SAT.)	USUALLY LIQUID; VERY WET, USUALLY FROM BELOW THE GROUND WATER TABLE																																																																																																																																																																																																																																	
	- WET - (W)	SEMISOLID; REQUIRES DRYING TO ATTAIN OPTIMUM MOISTURE																																																																																																																																																																																																																																	
	- MOIST - (M)	SOLID; AT OR NEAR OPTIMUM MOISTURE																																																																																																																																																																																																																																	
	- DRY - (D)	REQUIRES ADDITIONAL WATER TO ATTAIN OPTIMUM MOISTURE																																																																																																																																																																																																																																	
AR - AUGER REFUSAL	MED. - MEDIUM	VST - VANE SHEAR TEST																																																																																																																																																																																																																																	
BT - BORING TERMINATED	MICA - MICACEOUS	WEA. - WEATHERED																																																																																																																																																																																																																																	
CL - CLAY	MOD. - MODERATELY	γ - UNIT WEIGHT																																																																																																																																																																																																																																	
CPT - CONE PENETRATION TEST	NP - NON PLASTIC	γ _d - DRY UNIT WEIGHT																																																																																																																																																																																																																																	
CSE. - COARSE	ORG. - ORGANIC																																																																																																																																																																																																																																		
DMT - DILATOMETER TEST	PMT - PRESSUREMETER TEST	SAMPLE ABBREVIATIONS																																																																																																																																																																																																																																	
DPT - DYNAMIC PENETRATION TEST	SAP. - SAPROLITIC	S - BULK																																																																																																																																																																																																																																	
e - VOID RATIO	SD. - SAND, SANDY	SS - SPLIT SPOON																																																																																																																																																																																																																																	
F - FINE	SL. - SILT, SILTY	ST - SHELBY TUBE																																																																																																																																																																																																																																	
FOSS. - FOSSILIFEROUS	SLI. - SLIGHTLY	RS - ROCK																																																																																																																																																																																																																																	
FRAC. - FRACTURED, FRACTURES	TCR - TRICONE REFUSAL	RT - RECOMPACTED TRIAXIAL																																																																																																																																																																																																																																	
FRAGS. - FRAGMENTS	w - MOISTURE CONTENT	CBR - CALIFORNIA BEARING RATIO																																																																																																																																																																																																																																	
HI. - HIGHLY	V - VERY																																																																																																																																																																																																																																		
PLASTICITY <table><tr><td>NON PLASTIC</td><td>0-5</td><td>VERY LOW</td></tr><tr><td>SLIGHTLY PLASTIC</td><td>6-15</td><td>SLIGHT</td></tr><tr><td>MODERATELY PLASTIC</td><td>16-25</td><td>MEDIUM</td></tr><tr><td>HIGHLY PLASTIC</td><td>26 OR MORE</td><td>HIGH</td></tr></table>										NON PLASTIC	0-5	VERY LOW	SLIGHTLY PLASTIC	6-15	SLIGHT	MODERATELY PLASTIC	16-25	MEDIUM	HIGHLY PLASTIC	26 OR MORE	HIGH	EQUIPMENT USED ON SUBJECT PROJECT <table><tr><td>DRILL UNITS: ☒ CME-45C ☐ CME-55 ☐ CME-550 ☐ VANE SHEAR TEST ☐ PORTABLE HOIST ☐ _____ ☐ _____</td><td>ADVANCING TOOLS: ☐ CLAY BITS ☐ 6" CONTINUOUS FLIGHT AUGER ☐ 8" HOLLOW AUGERS ☐ HARD FACED FINGER BITS ☐ TUNG-CARBIDE INSERTS ☒ CASING ☒ W/ ADVANCER ☐ TRICONE _____ * STEEL TEETH ☐ TRICONE _____ * TUNG.-CARB. ☐ CORE BIT ☐ _____</td><td>HAMMER TYPE: ☒ AUTOMATIC ☐ MANUAL CORE SIZE: ☐ -B _____ ☐ -H _____ ☐ -N _____ HAND TOOLS: ☐ POST HOLE DIGGER ☐ HAND AUGER ☐ SOUNDING ROD ☐ VANE SHEAR TEST ☐ _____</td></tr></table>										DRILL UNITS: ☒ CME-45C ☐ CME-55 ☐ CME-550 ☐ VANE SHEAR TEST ☐ PORTABLE HOIST ☐ _____ ☐ _____	ADVANCING TOOLS: ☐ CLAY BITS ☐ 6" CONTINUOUS FLIGHT AUGER ☐ 8" HOLLOW AUGERS ☐ HARD FACED FINGER BITS ☐ TUNG-CARBIDE INSERTS ☒ CASING ☒ W/ ADVANCER ☐ TRICONE _____ * STEEL TEETH ☐ TRICONE _____ * TUNG.-CARB. ☐ CORE BIT ☐ _____	HAMMER TYPE: ☒ AUTOMATIC ☐ MANUAL CORE SIZE: ☐ -B _____ ☐ -H _____ ☐ -N _____ HAND TOOLS: ☐ POST HOLE DIGGER ☐ HAND AUGER ☐ SOUNDING ROD ☐ VANE SHEAR TEST ☐ _____																																																																																																																																																																																																	
NON PLASTIC	0-5	VERY LOW																																																																																																																																																																																																																																	
SLIGHTLY PLASTIC	6-15	SLIGHT																																																																																																																																																																																																																																	
MODERATELY PLASTIC	16-25	MEDIUM																																																																																																																																																																																																																																	
HIGHLY PLASTIC	26 OR MORE	HIGH																																																																																																																																																																																																																																	
DRILL UNITS: ☒ CME-45C ☐ CME-55 ☐ CME-550 ☐ VANE SHEAR TEST ☐ PORTABLE HOIST ☐ _____ ☐ _____	ADVANCING TOOLS: ☐ CLAY BITS ☐ 6" CONTINUOUS FLIGHT AUGER ☐ 8" HOLLOW AUGERS ☐ HARD FACED FINGER BITS ☐ TUNG-CARBIDE INSERTS ☒ CASING ☒ W/ ADVANCER ☐ TRICONE _____ * STEEL TEETH ☐ TRICONE _____ * TUNG.-CARB. ☐ CORE BIT ☐ _____	HAMMER TYPE: ☒ AUTOMATIC ☐ MANUAL CORE SIZE: ☐ -B _____ ☐ -H _____ ☐ -N _____ HAND TOOLS: ☐ POST HOLE DIGGER ☐ HAND AUGER ☐ SOUNDING ROD ☐ VANE SHEAR TEST ☐ _____																																																																																																																																																																																																																																	
COLOR DESCRIPTIONS MAY INCLUDE COLOR OR COLOR COMBINATIONS (TAN, RED, YELLOW-BROWN, BLUE-GRAY). MODIFIERS SUCH AS LIGHT, DARK, STREAKED, ETC. ARE USED TO DESCRIBE APPEARANCE.																																																																																																																																																																																																																																			

B-5555 46313

2A

**NORTH CAROLINA DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
GEOTECHNICAL ENGINEERING UNIT**


SUBSURFACE INVESTIGATION

SOIL AND ROCK LEGEND, TERMS, SYMBOLS, AND ABBREVIATIONS (PAGE 2 OF 2)

ROCK DESCRIPTION			TERMS AND DEFINITIONS	
HARD ROCK IS NON-COASTAL PLAIN MATERIAL THAT WOULD YIELD SPT REFUSAL IF TESTED. AN INFERRED ROCK LINE INDICATES THE LEVEL AT WHICH NON-COASTAL PLAIN MATERIAL WOULD YIELD SPT REFUSAL. SPT REFUSAL IS PENETRATION BY A SPLIT SPOON SAMPLER EQUAL TO OR LESS THAN 0.1 FOOT PER 60 BLOWS IN NON-COASTAL PLAIN MATERIAL. THE TRANSITION BETWEEN SOIL AND ROCK IS OFTEN REPRESENTED BY A ZONE OF WEATHERED ROCK. ROCK MATERIALS ARE TYPICALLY DIVIDED AS FOLLOWS:			ALLUVIUM (ALLUV.) - SOILS THAT HAVE BEEN TRANSPORTED BY WATER. AQUIFER - A WATER BEARING FORMATION OR STRATA. ARENACEOUS - APPLIED TO ROCKS THAT HAVE BEEN DERIVED FROM SAND OR THAT CONTAIN SAND. ARGILLACEOUS - APPLIED TO ALL ROCKS OR SUBSTANCES COMPOSED OF CLAY MINERALS, OR HAVING A NOTABLE PROPORTION OF CLAY IN THEIR COMPOSITION, SUCH AS SHALE, SLATE, ETC. ARTESIAN - GROUND WATER THAT IS UNDER SUFFICIENT PRESSURE TO RISE ABOVE THE LEVEL AT WHICH IT IS ENCOUNTERED, BUT WHICH DOES NOT NECESSARILY RISE TO OR ABOVE THE GROUND SURFACE. CALCAREOUS (CALC.) - SOILS THAT CONTAIN APPRECIABLE AMOUNTS OF CALCIUM CARBONATE. COLLUVIUM - ROCK FRAGMENTS MIXED WITH SOIL DEPOSITED BY GRAVITY ON SLOPE OR AT BOTTOM OF SLOPE. CORE RECOVERY (REC.) - TOTAL LENGTH OF ALL MATERIAL RECOVERED IN THE CORE BARREL DIVIDED BY TOTAL LENGTH OF CORE RUN AND EXPRESSED AS A PERCENTAGE. DIKE - A TABULAR BODY OF IGNEOUS ROCK THAT CUTS ACROSS THE STRUCTURE OF ADJACENT ROCKS OR CUTS MASSIVE ROCK. DIP - THE ANGLE AT WHICH A STRATUM OR ANY PLANAR FEATURE IS INCLINED FROM THE HORIZONTAL. DIP DIRECTION (DIP AZIMUTH) - THE DIRECTION OR BEARING OF THE HORIZONTAL TRACE OF THE LINE OF DIP, MEASURED CLOCKWISE FROM NORTH. FAULT - A FRACTURE OR FRACTURE ZONE ALONG WHICH THERE HAS BEEN DISPLACEMENT OF THE SIDES RELATIVE TO ONE ANOTHER PARALLEL TO THE FRACTURE. FISSILE - A PROPERTY OF SPLITTING ALONG CLOSELY SPACED PARALLEL PLANES. FLOAT - ROCK FRAGMENTS ON SURFACE NEAR THEIR ORIGINAL POSITION AND DISLODGED FROM PARENT MATERIAL. FLOOD PLAIN (FP) - LAND BORDERING A STREAM, BUILT OF SEDIMENTS DEPOSITED BY THE STREAM. FORMATION (FM.) - A MAPPABLE GEOLOGIC UNIT THAT CAN BE RECOGNIZED AND TRACED IN THE FIELD. JOINT - FRACTURE IN ROCK ALONG WHICH NO APPRECIABLE MOVEMENT HAS OCCURRED. LEDGE - A SHELF-LIKE RIDGE OR PROJECTION OF ROCK WHOSE THICKNESS IS SMALL COMPARED TO ITS LATERAL EXTENT. LENS - A BODY OF SOIL OR ROCK THAT THINS OUT IN ONE OR MORE DIRECTIONS. MOTTLED (MOT.) - IRREGULARLY MARKED WITH SPOTS OF DIFFERENT COLORS. MOTTILING IN SOILS USUALLY INDICATES POOR AERATION AND LACK OF GOOD DRAINAGE. PERCHED WATER - WATER MAINTAINED ABOVE THE NORMAL GROUND WATER LEVEL BY THE PRESENCE OF AN INTERVENING IMPERVIOUS STRATUM. RESIDUAL (RES.) SOIL - SOIL FORMED IN PLACE BY THE WEATHERING OF ROCK. ROCK QUALITY DESIGNATION (RQD) - A MEASURE OF ROCK QUALITY DESCRIBED BY TOTAL LENGTH OF ROCK SEGMENTS EQUAL TO OR GREATER THAN 4 INCHES DIVIDED BY THE TOTAL LENGTH OF CORE RUN AND EXPRESSED AS A PERCENTAGE. SAPROLITE (SAP.) - RESIDUAL SOIL THAT RETAINS THE RELIC STRUCTURE OR FABRIC OF THE PARENT ROCK. SILL - AN INTRUSIVE BODY OF IGNEOUS ROCK OF APPROXIMATELY UNIFORM THICKNESS AND RELATIVELY THIN COMPARED WITH ITS LATERAL EXTENT, THAT HAS BEEN EMPLACED PARALLEL TO THE BEDDING OR SCHISTOSITY OF THE INTRUDED ROCKS. SLICKENSIDE - POLISHED AND STRIATED SURFACE THAT RESULTS FROM FRICTION ALONG A FAULT OR SLIP PLANE. STANDARD PENETRATION TEST (PENETRATION RESISTANCE) (SPT) - NUMBER OF BLOWS (N OR BPF) OF A 140 LB. HAMMER FALLING 30 INCHES REQUIRED TO PRODUCE A PENETRATION OF 1 FOOT INTO SOIL WITH A 2 INCH OUTSIDE DIAMETER SPLIT SPOON SAMPLER. SPT REFUSAL IS PENETRATION EQUAL TO OR LESS THAN 0.1 FOOT PER 60 BLOWS. STRATA CORE RECOVERY (SREC.) - TOTAL LENGTH OF STRATA MATERIAL RECOVERED DIVIDED BY TOTAL LENGTH OF STRATUM AND EXPRESSED AS A PERCENTAGE. STRATA ROCK QUALITY DESIGNATION (SRQD) - A MEASURE OF ROCK QUALITY DESCRIBED BY TOTAL LENGTH OF ROCK SEGMENTS WITHIN A STRATUM EQUAL TO OR GREATER THAN 4 INCHES DIVIDED BY THE TOTAL LENGTH OF STRATA AND EXPRESSED AS A PERCENTAGE. TOPSOIL (TS.) - SURFACE SOILS USUALLY CONTAINING ORGANIC MATTER.	
WEATHERED ROCK (WR)		NON-COASTAL PLAIN MATERIAL THAT WOULD YIELD SPT N VALUES > 100 BLOWS PER FOOT IF TESTED.		
CRYSTALLINE ROCK (CR)		FINE TO COARSE GRAIN IGNEOUS AND METAMORPHIC ROCK THAT WOULD YIELD SPT REFUSAL IF TESTED. ROCK TYPE INCLUDES GRANITE, GNEISS, GABBRO, SCHIST, ETC.		
NON-CRYSTALLINE ROCK (NCR)		FINE TO COARSE GRAIN METAMORPHIC AND NON-COASTAL PLAIN SEDIMENTARY ROCK THAT WOULD YIELD SPT REFUSAL IF TESTED. ROCK TYPE INCLUDES PHYLLITE, SLATE, SANDSTONE, ETC.		
COASTAL PLAIN SEDIMENTARY ROCK (CP)		COASTAL PLAIN SEDIMENTS CEMENTED INTO ROCK, BUT MAY NOT YIELD SPT REFUSAL. ROCK TYPE INCLUDES LIMESTONE, SANDSTONE, CEMENTED SHELL BEDS, ETC.		
WEATHERING				
FRESH	ROCK FRESH, CRYSTALS BRIGHT, FEW JOINTS MAY SHOW SLIGHT STAINING. ROCK RINGS UNDER HAMMER IF CRYSTALLINE.			
VERY SLIGHT (V SL.)	ROCK GENERALLY FRESH, JOINTS STAINED, SOME JOINTS MAY SHOW THIN CLAY COATINGS IF OPEN. CRYSTALS ON A BROKEN SPECIMEN FACE SHINE BRIGHTLY. ROCK RINGS UNDER HAMMER BLOWS IF OF A CRYSTALLINE NATURE.			
SLIGHT (SL.)	ROCK GENERALLY FRESH, JOINTS STAINED AND DISCOLORATION EXTENDS INTO ROCK UP TO 1 INCH. OPEN JOINTS MAY CONTAIN CLAY. IN GRANITOID ROCKS SOME OCCASIONAL FELDSPAR CRYSTALS ARE DULL AND DISCOLORED. CRYSTALLINE ROCKS RING UNDER HAMMER BLOWS.			
MODERATE (MOD.)	SIGNIFICANT PORTIONS OF ROCK SHOW DISCOLORATION AND WEATHERING EFFECTS. IN GRANITOID ROCKS, MOST FELDSPARS ARE DULL AND DISCOLORED, SOME SHOW CLAY. ROCK HAS DULL SOUND UNDER HAMMER BLOWS AND SHOWS SIGNIFICANT LOSS OF STRENGTH AS COMPARED WITH FRESH ROCK.			
MODERATELY SEVERE (MOD. SEV.)	ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED. IN GRANITOID ROCKS, ALL FELDSPARS DULL AND DISCOLORED AND A MAJORITY SHOW KAOLINIZATION. ROCK SHOWS SEVERE LOSS OF STRENGTH AND CAN BE EXCAVATED WITH A GEOLOGIST'S PICK. ROCK GIVES "CLUNK" SOUND WHEN STRUCK. <u>IF TESTED, WOULD YIELD SPT REFUSAL</u>			
SEVERE (SEV.)	ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED. ROCK FABRIC CLEAR AND EVIDENT BUT REDUCED IN STRENGTH TO STRONG SOIL. IN GRANITOID ROCKS ALL FELDSPARS ARE KAOLINIZED TO SOME EXTENT. SOME FRAGMENTS OF STRONG ROCK USUALLY REMAIN. <u>IF TESTED, WOULD YIELD SPT N VALUES > 100 BPF</u>			
VERY SEVERE (V SEV.)	ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED. ROCK FABRIC ELEMENTS ARE DISCERNIBLE BUT MASS IS EFFECTIVELY REDUCED TO SOIL STATUS, WITH ONLY FRAGMENTS OF STRONG ROCK REMAINING. SAPROLITE IS AN EXAMPLE OF ROCK WEATHERED TO A DEGREE THAT ONLY MINOR VESTIGES OF ORIGINAL ROCK FABRIC REMAIN. <u>IF TESTED, WOULD YIELD SPT N VALUES < 100 BPF</u>			
COMPLETE	ROCK REDUCED TO SOIL. ROCK FABRIC NOT DISCERNIBLE, OR DISCERNIBLE ONLY IN SMALL AND SCATTERED CONCENTRATIONS. QUARTZ MAY BE PRESENT AS DIKES OR STRINGERS. SAPROLITE IS ALSO AN EXAMPLE.			
ROCK HARDNESS				
VERY HARD	CANNOT BE SCRATCHED BY KNIFE OR SHARP PICK. BREAKING OF HAND SPECIMENS REQUIRES SEVERAL HARD BLOWS OF THE GEOLOGIST'S PICK.			
HARD	CAN BE SCRATCHED BY KNIFE OR PICK ONLY WITH DIFFICULTY. HARD HAMMER BLOWS REQUIRED TO DETACH HAND SPECIMEN.			
MODERATELY HARD	CAN BE SCRATCHED BY KNIFE OR PICK. GOUGES OR GROOVES TO 0.25 INCHES DEEP CAN BE EXCAVATED BY HARD BLOW OF A GEOLOGIST'S PICK. HAND SPECIMENS CAN BE DETACHED BY MODERATE BLOWS.			
MEDIUM HARD	CAN BE GROOVED OR GOUGED 0.05 INCHES DEEP BY FIRM PRESSURE OF KNIFE OR PICK POINT. CAN BE EXCAVATED IN SMALL CHIPS TO PIECES 1 INCH MAXIMUM SIZE BY HARD BLOWS OF THE POINT OF A GEOLOGIST'S PICK.			
SOFT	CAN BE GROVED OR GOUGED READILY BY KNIFE OR PICK. CAN BE EXCAVATED IN FRAGMENTS FROM CHIPS TO SEVERAL INCHES IN SIZE BY MODERATE BLOWS OF A PICK POINT. SMALL, THIN PIECES CAN BE BROKEN BY FINGER PRESSURE.			
VERY SOFT	CAN BE CARVED WITH KNIFE. CAN BE EXCAVATED READILY WITH POINT OF PICK. PIECES 1 INCH OR MORE IN THICKNESS CAN BE BROKEN BY FINGER PRESSURE. CAN BE SCRATCHED READILY BY FINGERNAIL.			
FRACTURE SPACING		BEDDING		
TERM	SPACING	TERM	THICKNESS	
VERY WIDE	MORE THAN 10 FEET	VERY THICKLY BEDDED	4 FEET	
WIDE	3 TO 10 FEET	THICKLY BEDDED	1.5 - 4 FEET	
MODERATELY CLOSE	1 TO 3 FEET	THINLY BEDDED	0.16 - 1.5 FEET	
CLOSE	0.16 TO 1 FOOT	VERY THINLY BEDDED	0.03 - 0.16 FEET	
VERY CLOSE	LESS THAN 0.16 FEET	THICKLY LAMINATED	0.008 - 0.03 FEET	
		THINLY LAMINATED	< 0.008 FEET	
INDURATION				
FOR SEDIMENTARY ROCKS, INDURATION IS THE HARDENING OF MATERIAL BY CEMENTING, HEAT, PRESSURE, ETC.				
FRIABLE	RUBBING WITH FINGER FREES NUMEROUS GRAINS; GENTLE BLOW BY HAMMER DISINTEGRATES SAMPLE.			
MODERATELY INDURATED	GRAINS CAN BE SEPARATED FROM SAMPLE WITH STEEL PROBE; BREAKS EASILY WHEN HIT WITH HAMMER.			
INDURATED	GRAINS ARE DIFFICULT TO SEPARATE WITH STEEL PROBE; DIFFICULT TO BREAK WITH HAMMER.			
EXTREMELY INDURATED	SHARP HAMMER BLOWS REQUIRED TO BREAK SAMPLE; SAMPLE BREAKS ACROSS GRAINS.			
BENCH MARK: EXISTING DISK STAMPED TVA LOCATED ON THE SE CORNER OF THE BRIDGE. ASSUMED ELE. 100.00			ELEVATION:	FEET
NOTES:				
-				

DATE: 8-15-19

PROJECT REFERENCE NO.	SHEET NO.
B-5555 46313	3
SITE PLAN	
0 20 40  FEET	



BI
B2
BR 46
TBM
B3
B4

NC-215
To Balsam Grove

TBM
DISK STAMPED TVA
AT THE SE CORNER
OF EXISTING BRIDGE
ASSUMED ELEVATION
100.00



NCDOT GEOTECHNICAL ENGINEERING UNIT

BORELOG REPORT

SHEET OF 1

417

WBS 46313.3.F1		TIP B-5555		COUNTY TRANSYLVANIA		GEOLOGIST Elliott, D. C.	
SITE DESCRIPTION Bridge NO. 46 on NC-215 over Courthouse Creek							GROUND WTR (ft)
BORING NO. B-1		STATION N/A		OFFSET N/A		ALIGNMENT EXISTING	
COLLAR ELEV. 100.3 ft		TOTAL DEPTH 35.7 ft		NORTHING 567,878		EASTING 839,368	
DRILL RIG/HAMMER EFF./DATE N/A				DRILL METHOD NW Casing w/ SPT		HAMMER TYPE Automatic	
DRILLER Cheek, D. O.		START DATE 12/02/14		COMP. DATE 12/02/14		SURFACE WATER DEPTH N/A	

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100						
105																
100																
95	95.3	5.0	9	11	8											
90	90.3	10.0	6	8	8											
85	85.3	15.0	17	68	32/0.2											
80	80.3	20.0	27	21	16											
75	75.3	25.0	21	28	36											
70	70.3	30.0	38	62/0.4												
65	65.3	35.0	69	31/0.2												

GROUND SURFACE 0.0

ASPHALT 0.0

EMBANKMENT: DARK BROWN/GRAY/DARK GRAY SILTY SAND W/ GRAVELS, AND MANY COBBLES & BOULDERS THROUGHOUT, TRACE MICA.

CONCRETE: LIGHT GRAY FINES & MATRIX W/ DARK GRAY ANGULAR AGGREGATES (CONCRETE)

ALLUVIUM

SAPROLITE: DARK BROWN/DARK GRAY/DARK ORANGE SILTY FINE-TO-COURSE SAND, SLIGHTLY MICACEOUS.

WEATHERED ROCK: DARK BROWN/DARK GRAY/BLACK, SLIGHTLY MICACEOUS W/ A TRACE OF MANGANESE OXIDE.

Boring Terminated at Elevation 64.6 ft IN WEATHERED ROCK

100.3

98.9

85.2

82.8

81.1

73.5

64.6

NCDOT BORE SINGLE B5555 GEO BRDG46 INV BORINGS GPJ NC DOT GDT 12/11/14



NCDOT GEOTECHNICAL ENGINEERING UNIT

BORELOG REPORT

SHEET OF 1

5/7

WBS 46313.3.F1		TIP B-5555		COUNTY TRANSYLVANIA		GEOLOGIST Elliott, D. C.									
SITE DESCRIPTION Bridge NO. 46 on NC-215 over Courthouse Creek							GROUND WTR (ft)								
BORING NO. B-2		STATION N/A		OFFSET N/A		ALIGNMENT EXISTING	0 HR. N/A								
COLLAR ELEV. 100.3 ft		TOTAL DEPTH 35.3 ft		NORTHING 567,871		EASTING 839,366	24 HR. 13.6								
DRILL RIG/HAMMER EFF./DATE N/A				DRILL METHOD NW Casing w/ SPT		HAMMER TYPE Automatic									
DRILLER Cheek, D. O.		START DATE 12/02/14		COMP. DATE 12/02/14		SURFACE WATER DEPTH N/A									
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100					
105															
100															
95	95.3	5.0	6	6	5									GROUND SURFACE	0.0
														ASPHALT	0.0
														EMBANKMENT: DARK BROWN/GRAY SANDY SILT W/ GRAVELS, COBBLES & BOULDERS, TRACE MICA.	
90	90.3	10.0	4	5	4										
85	85.3	15.0	6	84	16/02									CONCRETE: LIGHT GRAY FINES & MATRIX W/ DARK GRAY ANGULAR AGGREGATES (CONCRETE); VERY HARD 15.6'-17.0'	13.4
80	80.3	20.0	1	2	3									SAPROLITE: DARK BROWN/BLACK/DARK ORANGE CLAYEY SANDY SILT, SLIGHTLY MICACEOUS & W/ A TRACE OF MANGANESE OXIDE.	17.0
75	75.3	25.0	73	27/01										WEATHERED ROCK: DARK BROWN/DARK GRAY/BLACK, W/ A TRACE MANGANESE OXIDE.	23.7
70	70.3	30.0	49	51/05											
	65.3	35.0	100/0.3												
														Boring Terminated at Elevation 65.0 ft IN WEATHERED ROCK	35.0



WCDOT BORE SINGLE B5555 GEO BRDG46 INV BORINGS.GPJ NC_DOT.GDT 12/11/14

