

FLOODING SOURCE		FLOODWAY			BASE FLOOD WATER-SURFACE ELEVATION (FEET NAVD 88)			
CROSS SECTION	DISTANCE ¹	WIDTH (FEET)	SECTION AREA (SQUARE FEET)	MEAN VELOCITY (FEET PER SECOND)	REGULATORY	WITHOUT FLOODWAY	WITH FLOODWAY	INCREASE
Swift Creek (continued)								
910	91,008	799	10,271	1.2	174.6	174.6	175.5	0.9
940	93,951	775	10,321	1.2	176.1	176.1	176.9	0.8
966	96,628	663	8,597	1.4	177.2	177.2	178.0	0.8
995	99,542	930	14,535	0.8	177.7	177.7	178.7	1.0
1031	103,116	1,483	15,728	0.7	178.3	178.3	179.3	1.0
1059	105,871	2,250	20,001	0.6	178.8	178.8	179.8	1.0
1097	109,730	1,081	7,499	1.6	179.6	179.6	180.6	1.0
1131	113,089	567	3,666	3.2	182.7	182.7	183.4	0.7
1160	116,011	327	3,053	3.8	185.5	185.5	186.3	0.8
1189	118,897	559	6,004	1.6	187.9	187.9	188.7	0.8
1236	123,628	332	3,935	2.4	189.2	189.2	189.9	0.7
1272	127,159	951	11,011	0.9	189.8	189.8	190.7	0.9
1326	132,630	900	7,829	1.2	192.1	192.1	192.9	0.8
1359	135,894	901	6,222	1.5	193.6	193.6	194.4	0.8
1384	138,418	618	5,547	1.7	195.0	195.0	195.8	0.8
1407	140,722	821	5,813	2.0	197.1	197.1	197.7	0.6
1421	142,050	416	4,451	2.7	201.0	201.0	201.5	0.5
1445	144,485	1,090	9,478	1.3	202.1	202.1	202.7	0.6

¹Feet above mouth

TABLE 13

FEDERAL EMERGENCY MANAGEMENT AGENCY

**JOHNSTON COUNTY, NC
AND INCORPORATED AREAS**

FLOODWAY DATA

SWIFT CREEK