

TO ALBEMARLE

WOODS

EXISTING STRUCTURE

STANLY COUNTY

MONTGOMERY COUNTY

BRIDGE ID
STA. 339+86.39 -L-

EXISTING R/W

BRIDGE CONTROL LINE
NC 24/27/73
WESTBOUND
-L-LT-

EXISTING R/W

NC 24/27/73
EASTBOUND
-L-RT-

TO TROY

WOODS

WOODS

PEE DEE RIVER

NAD 83 / 95

FOR UTILITY INFORMATION, SEE UTILITY
PLANS AND SPECIAL PROVISIONS.

FOR UTILITY INFORMATION, SEE UTILITY
PLANS AND SPECIAL PROVISIONS.

DRAWN BY : M. TOM DATE : 7/2017
 CHECKED BY : J. SLOAN DATE : 10/2017
 DESIGNED BY : M. TOM DATE : 7/2017
 DESIGN CHECKED BY : J. SLOAN DATE : 10/2017

TABLE 1			
WORK POINT	PIER	PIER CONTROL LINE AND WORKPOINT PROPOSED STATION -L-LT-	AS SURVEYED EXISTING STATION -L-LT-
3	2	336+57.07	336+57.07
4	3	338+67.07	338+66.99
5	4	340+77.07	340+77.14
6	5	342+87.07	342+87.11
7	6	344+97.07	344+97.07

AECOM
AECOM TECHNICAL SERVICES, INC.
701 CORPORATE CENTER DRIVE, SUITE 475
PALEIGH, NC 27957
(919) 854-6200 www.aecom.com
AECOM License No. F-0342

REVISIONS						SHEET NO. S-5
NO.	BY:	DATE:	NO.	BY:	DATE:	
1			3			TOTAL SHEETS 148
2			4			

DOCUMENT NOT CONSIDERED
FINAL UNLESS ALL
SIGNATURES COMPLETED