

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
GEOTECHNICAL ENGINEERING UNIT

STRUCTURE SUBSURFACE INVESTIGATION

PROJ. REFERENCE NO. 45358.1.22 (480183) F.A. PROJ. _____

COUNTY IREDELL

PROJECT DESCRIPTION BRIDGE NO. 183 OVER FOURTH CREEK
ON SR 1907 (CHIPLEY FORD RD.)

SITE DESCRIPTION _____

CONTENTS

<u>SHEET</u>	<u>DESCRIPTION</u>
1	TITLE SHEET
2	LEGEND
3	SITE PLAN
4-7	BORE LOGS

PERSONNEL

C.C. MURRAY

J.E. ESTEP

M.R. MOORE

INVESTIGATED BY **C.B. LITTLE**

CHECKED BY **C.B. LITTLE**

SUBMITTED BY **C.B. LITTLE**

DATE **JUNE 2012**

CAUTION NOTICE

THE SUBSURFACE INFORMATION AND THE SUBSURFACE INVESTIGATION ON WHICH IT IS BASED WERE MADE FOR THE PURPOSE OF PREPARING THE SCOPE OF WORK TO BE INCLUDED IN THE REQUEST FOR PROPOSAL. THE VARIOUS FIELD BORING LOGS, ROCK CORES, AND SOIL TEST DATA AVAILABLE MAY BE REVIEWED OR INSPECTED IN RALEIGH BY CONTACTING THE N.C. DEPARTMENT OF TRANSPORTATION, GEOTECHNICAL ENGINEERING UNIT AT (919) 250-4088. THE SUBSURFACE PLANS AND REPORTS, FIELD BORING LOGS, ROCK CORES, AND SOIL TEST DATA ARE NOT PART OF THE CONTRACT.


SOIL AND ROCK BOUNDARIES WITHIN A BOREHOLE ARE BASED ON GEOTECHNICAL INTERPRETATION UNLESS ENCOUNTERED IN A SAMPLE. INTERPRETED BOUNDARIES MAY NOT NECESSARILY REFLECT ACTUAL SUBSURFACE CONDITIONS BETWEEN SAMPLED STRATA, AND BOREHOLE INFORMATION MAY NOT NECESSARILY REFLECT ACTUAL SUBSURFACE CONDITIONS BETWEEN BORINGS. THE LABORATORY SAMPLE DATA AND THE IN SITU (IN-PLACE) TEST DATA CAN BE RELIED ON ONLY TO THE DEGREE OF RELIABILITY INHERENT IN THE STANDARD TEST METHOD. THE OBSERVED WATER LEVELS OR SOIL MOISTURE CONDITIONS INDICATED IN THE SUBSURFACE INVESTIGATIONS ARE AS RECORDED AT THE TIME OF THE INVESTIGATION. THESE WATER LEVELS OR SOIL MOISTURE CONDITIONS MAY VARY CONSIDERABLY WITH TIME ACCORDING TO CLIMATIC CONDITIONS INCLUDING TEMPERATURES, PRECIPITATION, AND WIND, AS WELL AS OTHER NON-CLIMATIC FACTORS.

THE DEPARTMENT DOES NOT WARRANT OR GUARANTEE THE SUFFICIENCY OR ACCURACY OF THE INVESTIGATION MADE, OR OPINION OF THE DEPARTMENT AS TO THE TYPE OF MATERIALS AND CONDITIONS TO BE ENCOUNTERED. THE BIDDER OR CONTRACTOR IS CAUTIONED TO MAKE SUCH INDEPENDENT SUBSURFACE INVESTIGATIONS AS HE DEEMS NECESSARY TO SATISFY HIMSELF AS TO CONDITIONS TO BE ENCOUNTERED ON THE PROJECT. THE CONTRACTOR SHALL HAVE NO CLAIM FOR ADDITIONAL COMPENSATION OR FOR AN EXTENSION OF TIME FOR ANY REASON RESULTING FROM THE ACTUAL CONDITIONS ENCOUNTERED AT THE SITE DIFFERING FROM THOSE INDICATED IN THE SUBSURFACE INFORMATION.

NOTE - THE INFORMATION CONTAINED HEREIN IS NOT IMPLIED OR GUARANTEED BY THE N.C. DEPARTMENT OF TRANSPORTATION AS BEING ACCURATE NOR IT IS CONSIDERED TO BE PART OF THE PLANS, SPECIFICATIONS, OR CONTRACT FOR THE PROJECT.

NOTE - BY HAVING REQUESTED THIS INFORMATION THE CONTRACTOR SPECIFICALLY WAIVES ANY CLAIMS FOR INCREASED COMPENSATION OR EXTENSION OF TIME BASED ON DIFFERENCES BETWEEN THE CONDITIONS INDICATED HEREIN AND THE ACTUAL CONDITIONS AT THE PROJECT SITE.

DRAWN BY: J.K. McCLURE



NORTH CAROLINA DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
GEOTECHNICAL ENGINEERING UNIT
SOIL AND ROCK LEGEND, TERMS, SYMBOLS, AND ABBREVIATIONS

SOIL DESCRIPTION												GRADATION																																																																																																																																																																																			
SOIL IS CONSIDERED TO BE THE UNCONSOLIDATED, SEMI-CONSOLIDATED, OR WEATHERED EARTH MATERIALS THAT CAN BE PENETRATED WITH A CONTINUOUS FLIGHT POWER AUGER, AND YIELD LESS THAN 100 BLOWS PER FOOT ACCORDING TO STANDARD PENETRATION TEST (AASHTO T206, ASTM D-1586). SOIL CLASSIFICATION IS BASED ON THE AASHTO SYSTEM. BASIC DESCRIPTIONS GENERALLY SHALL INCLUDE: CONSISTENCY, COLOR, TEXTURE, MOISTURE, AASHTO CLASSIFICATION, AND OTHER PERTINENT FACTORS SUCH AS MINERALOGICAL COMPOSITION, ANGULARITY, STRUCTURE, PLASTICITY, ETC. EXAMPLE: <i>VERY STIFF, GRAY, SILTY CLAY, MOST WITH INTERBEDDED FINE SAND LAYERS, HIGH PLASTIC, A-7-6</i>												WELL GRADED - INDICATES A GOOD REPRESENTATION OF PARTICLE SIZES FROM FINE TO COARSE. UNIFORM - INDICATES THAT SOIL PARTICLES ARE ALL APPROXIMATELY THE SAME SIZE. (ALSO POORLY GRADED) GAP-GRADED - INDICATES A MIXTURE OF UNIFORM PARTICLES OF TWO OR MORE SIZES.																																																																																																																																																																																			
												ANGULARITY OF GRAINS THE ANGULARITY OR ROUNDNESS OF SOIL GRAINS IS DESIGNATED BY THE TERMS <u>ANGULAR</u>, <u>SUBANGULAR</u>, <u>SUBROUNDED</u>, OR <u>ROUNDED</u>.																																																																																																																																																																																			
												MINERALOGICAL COMPOSITION MINERAL NAMES SUCH AS QUARTZ, FELDSPAR, MICA, TALC, KAOLIN, ETC. ARE USED IN DESCRIPTIONS WHENEVER THEY ARE CONSIDERED OF SIGNIFICANCE.																																																																																																																																																																																			
SOIL LEGEND AND AASHTO CLASSIFICATION												COMPRESSION																																																																																																																																																																																			
GENERAL CLASS. <table border="1" style="width: 100%; text-align: center;"><thead><tr><th colspan="6">GRANULAR MATERIALS (≤ 35% PASSING #200)</th><th colspan="6">SILT-CLAY MATERIALS (> 35% PASSING #200)</th><th colspan="6">ORGANIC MATERIALS</th></tr><tr><th colspan="2">A-1</th><th colspan="2">A-1-b</th><th colspan="2">A-2</th><th colspan="2">A-2-4</th><th colspan="2">A-2-5</th><th colspan="2">A-2-6</th><th colspan="2">A-2-7</th><th colspan="2">A-4</th><th colspan="2">A-5</th><th colspan="2">A-6</th><th colspan="2">A-7</th><th colspan="2">A-7-5</th><th colspan="2">A-7-6</th><th colspan="2">A-1, A-2</th><th colspan="2">A-3</th><th colspan="2">A-4, A-5</th><th colspan="2">A-6, A-7</th></tr></thead><tbody><tr><td colspan="2">A-1-a</td><td colspan="2">A-1-b</td><td colspan="2">A-2</td><td colspan="2">A-2-4</td><td colspan="2">A-2-5</td><td colspan="2">A-2-6</td><td colspan="2">A-2-7</td><td colspan="2">A-4</td><td colspan="2">A-5</td><td colspan="2">A-6</td><td colspan="2">A-7</td><td colspan="2">A-7-5</td><td colspan="2">A-7-6</td><td colspan="2">A-1, A-2</td><td colspan="2">A-3</td><td colspan="2">A-4, A-5</td><td colspan="2">A-6, A-7</td></tr><tr><td colspan="2">A-1-a</td><td colspan="2">A-1-b</td><td colspan="2">A-2</td><td colspan="2">A-2-4</td><td colspan="2">A-2-5</td><td colspan="2">A-2-6</td><td colspan="2">A-2-7</td><td colspan="2">A-4</td><td colspan="2">A-5</td><td colspan="2">A-6</td><td colspan="2">A-7</td><td colspan="2">A-7-5</td><td colspan="2">A-7-6</td><td colspan="2">A-1, A-2</td><td colspan="2">A-3</td><td colspan="2">A-4, A-5</td><td colspan="2">A-6, A-7</td></tr></tbody></table>												GRANULAR MATERIALS (≤ 35% PASSING #200)						SILT-CLAY MATERIALS (> 35% PASSING #200)						ORGANIC MATERIALS						A-1		A-1-b		A-2		A-2-4		A-2-5		A-2-6		A-2-7		A-4		A-5		A-6		A-7		A-7-5		A-7-6		A-1, A-2		A-3		A-4, A-5		A-6, A-7		A-1-a		A-1-b		A-2		A-2-4		A-2-5		A-2-6		A-2-7		A-4		A-5		A-6		A-7		A-7-5		A-7-6		A-1, A-2		A-3		A-4, A-5		A-6, A-7		A-1-a		A-1-b		A-2		A-2-4		A-2-5		A-2-6		A-2-7		A-4		A-5		A-6		A-7		A-7-5		A-7-6		A-1, A-2		A-3		A-4, A-5		A-6, A-7		PERCENTAGE OF MATERIAL <table border="1" style="width: 100%; text-align: center;"><thead><tr><th colspan="2">ORGANIC MATERIAL</th><th colspan="2">GRANULAR SOILS</th><th colspan="2">SILT - CLAY SOILS</th><th colspan="2">OTHER MATERIAL</th></tr></thead><tbody><tr><td colspan="2">TRACE OF ORGANIC MATTER</td><td colspan="2">2 - 3%</td><td colspan="2">3 - 5%</td><td colspan="2">TRACE</td><td colspan="2">1 - 10%</td></tr><tr><td colspan="2">LITTLE ORGANIC MATTER</td><td colspan="2">3 - 5%</td><td colspan="2">5 - 12%</td><td colspan="2">LITTLE</td><td colspan="2">10 - 20%</td></tr><tr><td colspan="2">MODERATELY ORGANIC</td><td colspan="2">5 - 10%</td><td colspan="2">12 - 20%</td><td colspan="2">SOME</td><td colspan="2">20 - 35%</td></tr><tr><td colspan="2">HIGHLY ORGANIC</td><td colspan="2">>10%</td><td colspan="2">>20%</td><td colspan="2">HIGHLY</td><td colspan="2">35% AND ABOVE</td></tr></tbody></table>												ORGANIC MATERIAL		GRANULAR SOILS		SILT - CLAY SOILS		OTHER MATERIAL		TRACE OF ORGANIC MATTER		2 - 3%		3 - 5%		TRACE		1 - 10%		LITTLE ORGANIC MATTER		3 - 5%		5 - 12%		LITTLE		10 - 20%		MODERATELY ORGANIC		5 - 10%		12 - 20%		SOME		20 - 35%		HIGHLY ORGANIC		>10%		>20%		HIGHLY		35% AND ABOVE	
GRANULAR MATERIALS (≤ 35% PASSING #200)						SILT-CLAY MATERIALS (> 35% PASSING #200)						ORGANIC MATERIALS																																																																																																																																																																																			
A-1		A-1-b		A-2		A-2-4		A-2-5		A-2-6		A-2-7		A-4		A-5		A-6		A-7		A-7-5		A-7-6		A-1, A-2		A-3		A-4, A-5		A-6, A-7																																																																																																																																																															
A-1-a		A-1-b		A-2		A-2-4		A-2-5		A-2-6		A-2-7		A-4		A-5		A-6		A-7		A-7-5		A-7-6		A-1, A-2		A-3		A-4, A-5		A-6, A-7																																																																																																																																																															
A-1-a		A-1-b		A-2		A-2-4		A-2-5		A-2-6		A-2-7		A-4		A-5		A-6		A-7		A-7-5		A-7-6		A-1, A-2		A-3		A-4, A-5		A-6, A-7																																																																																																																																																															
ORGANIC MATERIAL		GRANULAR SOILS		SILT - CLAY SOILS		OTHER MATERIAL																																																																																																																																																																																									
TRACE OF ORGANIC MATTER		2 - 3%		3 - 5%		TRACE		1 - 10%																																																																																																																																																																																							
LITTLE ORGANIC MATTER		3 - 5%		5 - 12%		LITTLE		10 - 20%																																																																																																																																																																																							
MODERATELY ORGANIC		5 - 10%		12 - 20%		SOME		20 - 35%																																																																																																																																																																																							
HIGHLY ORGANIC		>10%		>20%		HIGHLY		35% AND ABOVE																																																																																																																																																																																							
LIQUID LIMIT PLASTIC INDEX <table border="1" style="width: 100%; text-align: center;"><thead><tr><th colspan="2">GROUP CLASS.</th><th colspan="2">SYMBOL</th><th colspan="2">% PASSING</th><th colspan="2">LIQUID LIMIT</th><th colspan="2">PLASTIC INDEX</th><th colspan="2">GROUP INDEX</th><th colspan="2">USUAL TYPES OF MAJOR MATERIALS</th><th colspan="2">GEN. RATING AS A SUBGRADE</th></tr></thead><tbody><tr><td colspan="2">A-1</td><td colspan="2">A-1-b</td><td colspan="2">A-2</td><td colspan="2">A-2-4</td><td colspan="2">A-2-5</td><td colspan="2">A-2-6</td><td colspan="2">A-2-7</td><td colspan="2">A-4</td><td colspan="2">A-5</td><td colspan="2">A-6</td><td colspan="2">A-7</td><td colspan="2">A-7-5</td><td colspan="2">A-7-6</td><td colspan="2">A-1, A-2</td><td colspan="2">A-3</td><td colspan="2">A-4, A-5</td><td colspan="2">A-6, A-7</td></tr><tr><td colspan="2">A-1</td><td colspan="2">A-1-b</td><td colspan="2">A-2</td><td colspan="2">A-2-4</td><td colspan="2">A-2-5</td><td colspan="2">A-2-6</td><td colspan="2">A-2-7</td><td colspan="2">A-4</td><td colspan="2">A-5</td><td colspan="2">A-6</td><td colspan="2">A-7</td><td colspan="2">A-7-5</td><td colspan="2">A-7-6</td><td colspan="2">A-1, A-2</td><td colspan="2">A-3</td><td colspan="2">A-4, A-5</td><td colspan="2">A-6, A-7</td></tr><tr><td colspan="2">A-1</td><td colspan="2">A-1-b</td><td colspan="2">A-2</td><td colspan="2">A-2-4</td><td colspan="2">A-2-5</td><td colspan="2">A-2-6</td><td colspan="2">A-2-7</td><td colspan="2">A-4</td><td colspan="2">A-5</td><td colspan="2">A-6</td><td colspan="2">A-7</td><td colspan="2">A-7-5</td><td colspan="2">A-7-6</td><td colspan="2">A-1, A-2</td><td colspan="2">A-3</td><td colspan="2">A-4, A-5</td><td colspan="2">A-6, A-7</td></tr></tbody></table>												GROUP CLASS.		SYMBOL		% PASSING		LIQUID LIMIT		PLASTIC INDEX		GROUP INDEX		USUAL TYPES OF MAJOR MATERIALS		GEN. RATING AS A SUBGRADE		A-1		A-1-b		A-2		A-2-4		A-2-5		A-2-6		A-2-7		A-4		A-5		A-6		A-7		A-7-5		A-7-6		A-1, A-2		A-3		A-4, A-5		A-6, A-7		A-1		A-1-b		A-2		A-2-4		A-2-5		A-2-6		A-2-7		A-4		A-5		A-6		A-7		A-7-5		A-7-6		A-1, A-2		A-3		A-4, A-5		A-6, A-7		A-1		A-1-b		A-2		A-2-4		A-2-5		A-2-6		A-2-7		A-4		A-5		A-6		A-7		A-7-5		A-7-6		A-1, A-2		A-3		A-4, A-5		A-6, A-7		GROUND WATER ▽ WATER LEVEL IN BORE HOLE IMMEDIATELY AFTER DRILLING ▽ STATIC WATER LEVEL AFTER 24 HOURS ▽ PW PERCHED WATER, SATURATED ZONE, OR WATER BEARING STRATA ○ SPRING OR SEEP																																																													
GROUP CLASS.		SYMBOL		% PASSING		LIQUID LIMIT		PLASTIC INDEX		GROUP INDEX		USUAL TYPES OF MAJOR MATERIALS		GEN. RATING AS A SUBGRADE																																																																																																																																																																																	
A-1		A-1-b		A-2		A-2-4		A-2-5		A-2-6		A-2-7		A-4		A-5		A-6		A-7		A-7-5		A-7-6		A-1, A-2		A-3		A-4, A-5		A-6, A-7																																																																																																																																																															
A-1		A-1-b		A-2		A-2-4		A-2-5		A-2-6		A-2-7		A-4		A-5		A-6		A-7		A-7-5		A-7-6		A-1, A-2		A-3		A-4, A-5		A-6, A-7																																																																																																																																																															
A-1		A-1-b		A-2		A-2-4		A-2-5		A-2-6		A-2-7		A-4		A-5		A-6		A-7		A-7-5		A-7-6		A-1, A-2		A-3		A-4, A-5		A-6, A-7																																																																																																																																																															
CONSISTENCY OR DENSENESS <table border="1" style="width: 100%; text-align: center;"><thead><tr><th>PRIMARY SOIL TYPE</th><th>COMPACTNESS OR CONSISTENCY</th><th>RANGE OF STANDARD PENETRATION RESISTANCE (N-VALUE)</th><th>RANGE OF UNCONFINED COMPRESSIVE STRENGTH (TENS/F²)</th></tr></thead><tbody><tr><td rowspan="4">GENERALLY GRANULAR MATERIAL (NON-COHESIVE)</td><td>VERY LOOSE</td><td><4</td><td>N/A</td></tr><tr><td>LOOSE</td><td>4 TO 10</td><td></td></tr><tr><td>MEDIUM DENSE</td><td>10 TO 30</td><td></td></tr><tr><td>DENSE</td><td>30 TO 50</td><td></td></tr><tr><td rowspan="4">GENERALLY SILT-CLAY MATERIAL (COHESIVE)</td><td>VERY SOFT</td><td><2</td><td><0.25</td></tr><tr><td>SOFT</td><td>2 TO 4</td><td>0.25 TO 0.50</td></tr><tr><td>MEDIUM STIFF</td><td>4 TO 8</td><td>0.5 TO 1.0</td></tr><tr><td>STIFF</td><td>8 TO 15</td><td>1 TO 2</td></tr><tr><td rowspan="2">VERY STIFF</td><td>15 TO 30</td><td>2 TO 4</td><td></td></tr><tr><td>HARD</td><td>>30</td><td>>4</td><td></td></tr></tbody></table>												PRIMARY SOIL TYPE	COMPACTNESS OR CONSISTENCY	RANGE OF STANDARD PENETRATION RESISTANCE (N-VALUE)	RANGE OF UNCONFINED COMPRESSIVE STRENGTH (TENS/F ²)	GENERALLY GRANULAR MATERIAL (NON-COHESIVE)	VERY LOOSE	<4	N/A	LOOSE	4 TO 10		MEDIUM DENSE	10 TO 30		DENSE	30 TO 50		GENERALLY SILT-CLAY MATERIAL (COHESIVE)	VERY SOFT	<2	<0.25	SOFT	2 TO 4	0.25 TO 0.50	MEDIUM STIFF	4 TO 8	0.5 TO 1.0	STIFF	8 TO 15	1 TO 2	VERY STIFF	15 TO 30	2 TO 4		HARD	>30	>4		MISCELLANEOUS SYMBOLS <table border="1" style="width: 100%; text-align: center;"><thead><tr><th>SYMBOL</th><th>DESCRIPTION</th><th>SYMBOL</th><th>DESCRIPTION</th><th>SYMBOL</th><th>DESCRIPTION</th></tr></thead><tbody><tr><td></td><td>ROADWAY EMBANKMENT (RE) WITH SOIL DESCRIPTION</td><td></td><td>TEST BORING</td><td></td><td>TEST BORING W/ CORE</td></tr><tr><td></td><td>SOIL SYMBOL</td><td></td><td>AUGER BORING</td><td></td><td>SPT N-VALUE</td></tr><tr><td></td><td>ARTIFICIAL FILL (AF) OTHER THAN ROADWAY EMBANKMENT</td><td></td><td>CORE BORING</td><td></td><td>SPT REFUSAL</td></tr><tr><td></td><td>INFERRED SOIL BOUNDARY</td><td></td><td>MONITORING WELL</td><td></td><td></td></tr><tr><td></td><td>INFERRED ROCK LINE</td><td></td><td>PIEZOMETER INSTALLATION</td><td></td><td></td></tr><tr><td></td><td>ALLUVIAL SOIL BOUNDARY</td><td></td><td>SLOPE INDICATOR INSTALLATION</td><td></td><td></td></tr><tr><td></td><td>DIP & DIP DIRECTION OF ROCK STRUCTURES</td><td></td><td>CONE PENETROMETER TEST</td><td></td><td></td></tr><tr><td></td><td></td><td></td><td>SOUNDING ROD</td><td></td><td></td></tr></tbody></table>												SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION		ROADWAY EMBANKMENT (RE) WITH SOIL DESCRIPTION		TEST BORING		TEST BORING W/ CORE		SOIL SYMBOL		AUGER BORING		SPT N-VALUE		ARTIFICIAL FILL (AF) OTHER THAN ROADWAY EMBANKMENT		CORE BORING		SPT REFUSAL		INFERRED SOIL BOUNDARY		MONITORING WELL				INFERRED ROCK LINE		PIEZOMETER INSTALLATION				ALLUVIAL SOIL BOUNDARY		SLOPE INDICATOR INSTALLATION				DIP & DIP DIRECTION OF ROCK STRUCTURES		CONE PENETROMETER TEST						SOUNDING ROD																																																																														
PRIMARY SOIL TYPE	COMPACTNESS OR CONSISTENCY	RANGE OF STANDARD PENETRATION RESISTANCE (N-VALUE)	RANGE OF UNCONFINED COMPRESSIVE STRENGTH (TENS/F ²)																																																																																																																																																																																												
GENERALLY GRANULAR MATERIAL (NON-COHESIVE)	VERY LOOSE	<4	N/A																																																																																																																																																																																												
	LOOSE	4 TO 10																																																																																																																																																																																													
	MEDIUM DENSE	10 TO 30																																																																																																																																																																																													
	DENSE	30 TO 50																																																																																																																																																																																													
GENERALLY SILT-CLAY MATERIAL (COHESIVE)	VERY SOFT	<2	<0.25																																																																																																																																																																																												
	SOFT	2 TO 4	0.25 TO 0.50																																																																																																																																																																																												
	MEDIUM STIFF	4 TO 8	0.5 TO 1.0																																																																																																																																																																																												
	STIFF	8 TO 15	1 TO 2																																																																																																																																																																																												
VERY STIFF	15 TO 30	2 TO 4																																																																																																																																																																																													
	HARD	>30	>4																																																																																																																																																																																												
SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION																																																																																																																																																																																										
	ROADWAY EMBANKMENT (RE) WITH SOIL DESCRIPTION		TEST BORING		TEST BORING W/ CORE																																																																																																																																																																																										
	SOIL SYMBOL		AUGER BORING		SPT N-VALUE																																																																																																																																																																																										
	ARTIFICIAL FILL (AF) OTHER THAN ROADWAY EMBANKMENT		CORE BORING		SPT REFUSAL																																																																																																																																																																																										
	INFERRED SOIL BOUNDARY		MONITORING WELL																																																																																																																																																																																												
	INFERRED ROCK LINE		PIEZOMETER INSTALLATION																																																																																																																																																																																												
	ALLUVIAL SOIL BOUNDARY		SLOPE INDICATOR INSTALLATION																																																																																																																																																																																												
	DIP & DIP DIRECTION OF ROCK STRUCTURES		CONE PENETROMETER TEST																																																																																																																																																																																												
			SOUNDING ROD																																																																																																																																																																																												
TEXTURE OR GRAIN SIZE <table border="1" style="width: 100%; text-align: center;"><thead><tr><th>U.S. STD. SIEVE SIZE</th><th>4</th><th>10</th><th>40</th><th>60</th><th>200</th><th>270</th></tr><tr><th>OPENING (MM)</th><th>4.75</th><th>2.00</th><th>0.42</th><th>0.25</th><th>0.075</th><th>0.053</th></tr></thead><tbody><tr><td>BOULDER (BLDR.)</td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td>COBBLE (COB.)</td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td>GRAVEL (GR.)</td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td>COARSE SAND (CSE. SD.)</td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td>FINE SAND (F SD.)</td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td>SILT (SL.)</td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td>CLAY (CL.)</td><td></td><td></td><td></td><td></td><td></td><td></td></tr></tbody></table>												U.S. STD. SIEVE SIZE	4	10	40	60	200	270	OPENING (MM)	4.75	2.00	0.42	0.25	0.075	0.053	BOULDER (BLDR.)							COBBLE (COB.)							GRAVEL (GR.)							COARSE SAND (CSE. SD.)							FINE SAND (F SD.)							SILT (SL.)							CLAY (CL.)							ABBREVIATIONS <table border="1" style="width: 100%; text-align: left;"><tbody><tr><td>AR - AUGER REFUSAL</td><td>MED. - MEDIUM</td><td>VST - VANE SHEAR TEST</td></tr><tr><td>BT - BORING TERMINATED</td><td>MICA - MICACEOUS</td><td>WEA. - WEATHERED</td></tr><tr><td>CL - CLAY</td><td>MOD. - MODERATELY</td><td>γ - UNIT WEIGHT</td></tr><tr><td>CPT - CONE PENETRATION TEST</td><td>NP - NON PLASTIC</td><td>γ_d - DRY UNIT WEIGHT</td></tr><tr><td>CSE. - COARSE</td><td>ORG. - ORGANIC</td><td></td></tr><tr><td>DMT - DILATOMETER TEST</td><td>PMT - PRESSUREMETER TEST</td><td></td></tr><tr><td>DPT - DYNAMIC PENETRATION TEST</td><td>SAP. - SAPROLITIC</td><td></td></tr><tr><td>e - VOID RATIO</td><td>SD. - SAND, SANDY</td><td></td></tr><tr><td>F - FINE</td><td>SL. - SILT, SILTY</td><td></td></tr><tr><td>FOSS. - FOSSILIFEROUS</td><td>SLT. - SLIGHTLY</td><td></td></tr><tr><td>FRAC. - FRACTURED, FRACTURES</td><td>TCR - TRICONE REFUSAL</td><td></td></tr><tr><td>FRAGS. - FRAGMENTS</td><td>μ - MOISTURE CONTENT</td><td></td></tr><tr><td>HL. - HIGHLY</td><td>V - VERY</td><td></td></tr></tbody></table>												AR - AUGER REFUSAL	MED. - MEDIUM	VST - VANE SHEAR TEST	BT - BORING TERMINATED	MICA - MICACEOUS	WEA. - WEATHERED	CL - CLAY	MOD. - MODERATELY	γ - UNIT WEIGHT	CPT - CONE PENETRATION TEST	NP - NON PLASTIC	γ _d - DRY UNIT WEIGHT	CSE. - COARSE	ORG. - ORGANIC		DMT - DILATOMETER TEST	PMT - PRESSUREMETER TEST		DPT - DYNAMIC PENETRATION TEST	SAP. - SAPROLITIC		e - VOID RATIO	SD. - SAND, SANDY		F - FINE	SL. - SILT, SILTY		FOSS. - FOSSILIFEROUS	SLT. - SLIGHTLY		FRAC. - FRACTURED, FRACTURES	TCR - TRICONE REFUSAL		FRAGS. - FRAGMENTS	μ - MOISTURE CONTENT		HL. - HIGHLY	V - VERY																																																																			
U.S. STD. SIEVE SIZE	4	10	40	60	200	270																																																																																																																																																																																									
OPENING (MM)	4.75	2.00	0.42	0.25	0.075	0.053																																																																																																																																																																																									
BOULDER (BLDR.)																																																																																																																																																																																															
COBBLE (COB.)																																																																																																																																																																																															
GRAVEL (GR.)																																																																																																																																																																																															
COARSE SAND (CSE. SD.)																																																																																																																																																																																															
FINE SAND (F SD.)																																																																																																																																																																																															
SILT (SL.)																																																																																																																																																																																															
CLAY (CL.)																																																																																																																																																																																															
AR - AUGER REFUSAL	MED. - MEDIUM	VST - VANE SHEAR TEST																																																																																																																																																																																													
BT - BORING TERMINATED	MICA - MICACEOUS	WEA. - WEATHERED																																																																																																																																																																																													
CL - CLAY	MOD. - MODERATELY	γ - UNIT WEIGHT																																																																																																																																																																																													
CPT - CONE PENETRATION TEST	NP - NON PLASTIC	γ _d - DRY UNIT WEIGHT																																																																																																																																																																																													
CSE. - COARSE	ORG. - ORGANIC																																																																																																																																																																																														
DMT - DILATOMETER TEST	PMT - PRESSUREMETER TEST																																																																																																																																																																																														
DPT - DYNAMIC PENETRATION TEST	SAP. - SAPROLITIC																																																																																																																																																																																														
e - VOID RATIO	SD. - SAND, SANDY																																																																																																																																																																																														
F - FINE	SL. - SILT, SILTY																																																																																																																																																																																														
FOSS. - FOSSILIFEROUS	SLT. - SLIGHTLY																																																																																																																																																																																														
FRAC. - FRACTURED, FRACTURES	TCR - TRICONE REFUSAL																																																																																																																																																																																														
FRAGS. - FRAGMENTS	μ - MOISTURE CONTENT																																																																																																																																																																																														
HL. - HIGHLY	V - VERY																																																																																																																																																																																														
SOIL MOISTURE - CORRELATION OF TERMS <table border="1" style="width: 100%; text-align: center;"><thead><tr><th>SOIL MOISTURE SCALE (ATTERBERG LIMITS)</th><th>FIELD MOISTURE DESCRIPTION</th><th>GUIDE FOR FIELD MOISTURE DESCRIPTION</th></tr></thead><tbody><tr><td rowspan="3">LL - LIQUID LIMIT PL - PLASTIC LIMIT OM - OPTIMUM MOISTURE SL - SHRINKAGE LIMIT</td><td>- SATURATED - (SAT.)</td><td>USUALLY LIQUID; VERY WET, USUALLY FROM BELOW THE GROUND WATER TABLE</td></tr><tr><td>- WET - (W)</td><td>SEMISOLID; REQUIRES DRYING TO ATTAIN OPTIMUM MOISTURE</td></tr><tr><td>- MOIST - (M)</td><td>SOLID; AT OR NEAR OPTIMUM MOISTURE</td></tr><tr><td></td><td>- DRY - (D)</td><td>REQUIRES ADDITIONAL WATER TO ATTAIN OPTIMUM MOISTURE</td></tr></tbody></table>												SOIL MOISTURE SCALE (ATTERBERG LIMITS)	FIELD MOISTURE DESCRIPTION	GUIDE FOR FIELD MOISTURE DESCRIPTION	LL - LIQUID LIMIT PL - PLASTIC LIMIT OM - OPTIMUM MOISTURE SL - SHRINKAGE LIMIT	- SATURATED - (SAT.)	USUALLY LIQUID; VERY WET, USUALLY FROM BELOW THE GROUND WATER TABLE	- WET - (W)	SEMISOLID; REQUIRES DRYING TO ATTAIN OPTIMUM MOISTURE	- MOIST - (M)	SOLID; AT OR NEAR OPTIMUM MOISTURE		- DRY - (D)	REQUIRES ADDITIONAL WATER TO ATTAIN OPTIMUM MOISTURE	EQUIPMENT USED ON SUBJECT PROJECT <table border="1" style="width: 100%; text-align: left;"><tbody><tr><td>DRILL UNITS:</td><td>ADVANCING TOOLS:</td><td>HAMMER TYPE:</td></tr><tr><td>☐ MOBILE B-___</td><td>☐ CLAY BITS</td><td>☒ AUTOMATIC ☐ MANUAL</td></tr><tr><td>☐ BK-51</td><td>☐ 6" CONTINUOUS FLIGHT AUGER</td><td>CORE SIZE:</td></tr><tr><td>☐ CME-45C</td><td>☐ 8" HOLLOW AUGERS</td><td>☐ -B-___</td></tr><tr><td>☒ CME-550</td><td>☐ HARD FACED FINGER BITS</td><td>☐ -N-___</td></tr><tr><td>☐ PORTABLE HOIST</td><td>☐ TUNG.-CARBIDE INSERTS</td><td>☐ -H-___</td></tr><tr><td></td><td>☒ CASING ☒ W/ ADVANCER</td><td>HAND TOOLS:</td></tr><tr><td></td><td>☐ TRICONE ___ * STEEL TEETH</td><td>☐ POST HOLE DIGGER</td></tr><tr><td></td><td>☒ TRICONE 2 1/16" * TUNG.-CARB.</td><td>☐ HAND AUGER</td></tr><tr><td></td><td>☐ CORE BIT</td><td>☐ SOUNDING ROD</td></tr><tr><td></td><td></td><td>☐ VANE SHEAR TEST</td></tr></tbody></table>												DRILL UNITS:	ADVANCING TOOLS:	HAMMER TYPE:	☐ MOBILE B-___	☐ CLAY BITS	☒ AUTOMATIC ☐ MANUAL	☐ BK-51	☐ 6" CONTINUOUS FLIGHT AUGER	CORE SIZE:	☐ CME-45C	☐ 8" HOLLOW AUGERS	☐ -B-___	☒ CME-550	☐ HARD FACED FINGER BITS	☐ -N-___	☐ PORTABLE HOIST	☐ TUNG.-CARBIDE INSERTS	☐ -H-___		☒ CASING ☒ W/ ADVANCER	HAND TOOLS:		☐ TRICONE ___ * STEEL TEETH	☐ POST HOLE DIGGER		☒ TRICONE 2 1/16" * TUNG.-CARB.	☐ HAND AUGER		☐ CORE BIT	☐ SOUNDING ROD			☐ VANE SHEAR TEST																																																																																																																										
SOIL MOISTURE SCALE (ATTERBERG LIMITS)	FIELD MOISTURE DESCRIPTION	GUIDE FOR FIELD MOISTURE DESCRIPTION																																																																																																																																																																																													
LL - LIQUID LIMIT PL - PLASTIC LIMIT OM - OPTIMUM MOISTURE SL - SHRINKAGE LIMIT	- SATURATED - (SAT.)	USUALLY LIQUID; VERY WET, USUALLY FROM BELOW THE GROUND WATER TABLE																																																																																																																																																																																													
	- WET - (W)	SEMISOLID; REQUIRES DRYING TO ATTAIN OPTIMUM MOISTURE																																																																																																																																																																																													
	- MOIST - (M)	SOLID; AT OR NEAR OPTIMUM MOISTURE																																																																																																																																																																																													
	- DRY - (D)	REQUIRES ADDITIONAL WATER TO ATTAIN OPTIMUM MOISTURE																																																																																																																																																																																													
DRILL UNITS:	ADVANCING TOOLS:	HAMMER TYPE:																																																																																																																																																																																													
☐ MOBILE B-___	☐ CLAY BITS	☒ AUTOMATIC ☐ MANUAL																																																																																																																																																																																													
☐ BK-51	☐ 6" CONTINUOUS FLIGHT AUGER	CORE SIZE:																																																																																																																																																																																													
☐ CME-45C	☐ 8" HOLLOW AUGERS	☐ -B-___																																																																																																																																																																																													
☒ CME-550	☐ HARD FACED FINGER BITS	☐ -N-___																																																																																																																																																																																													
☐ PORTABLE HOIST	☐ TUNG.-CARBIDE INSERTS	☐ -H-___																																																																																																																																																																																													
	☒ CASING ☒ W/ ADVANCER	HAND TOOLS:																																																																																																																																																																																													
	☐ TRICONE ___ * STEEL TEETH	☐ POST HOLE DIGGER																																																																																																																																																																																													
	☒ TRICONE 2 1/16" * TUNG.-CARB.	☐ HAND AUGER																																																																																																																																																																																													
	☐ CORE BIT	☐ SOUNDING ROD																																																																																																																																																																																													
		☐ VANE SHEAR TEST																																																																																																																																																																																													
PLASTICITY <table border="1" style="width: 100%; text-align: center;"><thead><tr><th>NONPLASTIC</th><th>LOW PLASTICITY</th><th>MED. PLASTICITY</th><th>HIGH PLASTICITY</th></tr></thead><tbody><tr><td>0-5</td><td>6-15</td><td>16-25</td><td>26 OR MORE</td></tr></tbody></table>												NONPLASTIC	LOW PLASTICITY	MED. PLASTICITY	HIGH PLASTICITY	0-5	6-15	16-25	26 OR MORE	COLOR DESCRIPTIONS MAY INCLUDE COLOR OR COLOR COMBINATIONS (TAN, RED, YELLOW-BROWN, BLUE-GRAY). MODIFIERS SUCH AS LIGHT, DARK, STREAKED, ETC. ARE USED TO DESCRIBE APPEARANCE.																																																																																																																																																																											
NONPLASTIC	LOW PLASTICITY	MED. PLASTICITY	HIGH PLASTICITY																																																																																																																																																																																												
0-5	6-15	16-25	26 OR MORE																																																																																																																																																																																												

NORTH CAROLINA DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
GEOTECHNICAL ENGINEERING UNIT
SOIL AND ROCK LEGEND, TERMS, SYMBOLS, AND ABBREVIATIONS

ROCK DESCRIPTION		TERMS AND DEFINITIONS	
HARD ROCK IS NON-COASTAL PLAIN MATERIAL THAT IF TESTED, WOULD YIELD SPT REFUSAL. AN INFERRED ROCK LINE INDICATES THE LEVEL AT WHICH NON-COASTAL PLAIN MATERIAL WOULD YIELD SPT REFUSAL. SPT REFUSAL IS PENETRATION BY A SPLIT SPOON SAMPLER EQUAL TO OR LESS THAN 60 BLOWS PER 60 BLOWS. IN NON-COASTAL PLAIN MATERIAL, THE TRANSITION BETWEEN SOIL AND ROCK IS OFTEN REPRESENTED BY A ZONE OF WEATHERED ROCK. ROCK MATERIALS ARE TYPICALLY DIVIDED AS FOLLOWS:		ALLUVIUM (ALLUV.) - SOILS THAT HAVE BEEN TRANSPORTED BY WATER. AQUIFER - A WATER BEARING FORMATION OR STRATA. ARENACEOUS - APPLIED TO ROCKS THAT HAVE BEEN DERIVED FROM SAND OR THAT CONTAIN SAND. ARGILLACEOUS - APPLIED TO ALL ROCKS OR SUBSTANCES COMPOSED OF CLAY MINERALS, OR HAVING A NOTABLE PROPORTION OF CLAY IN THEIR COMPOSITION, AS SHALE, SLATE, ETC. ARTESIAN - GROUND WATER THAT IS UNDER SUFFICIENT PRESSURE TO RISE ABOVE THE LEVEL AT WHICH IT IS ENCOUNTERED, BUT WHICH DOES NOT NECESSARILY RISE TO OR ABOVE THE GROUND SURFACE. CALCAREOUS (CALC.) - SOILS THAT CONTAIN APPRECIABLE AMOUNTS OF CALCIUM CARBONATE. COLLUVIUM - ROCK FRAGMENTS MIXED WITH SOIL DEPOSITED BY GRAVITY ON SLOPE OR AT BOTTOM OF SLOPE. CORE RECOVERY (REC) - TOTAL LENGTH OF ALL MATERIAL RECOVERED IN THE CORE BARREL DIVIDED BY TOTAL LENGTH OF CORE RUN AND EXPRESSED AS A PERCENTAGE. DIKE - A TABULAR BODY OF IGNEOUS ROCK THAT CUTS ACROSS THE STRUCTURE OF ADJACENT ROCKS OR CUTS MASSIVE ROCK. DIP - THE ANGLE AT WHICH A STRATUM OR ANY PLANAR FEATURE IS INCLINED FROM THE HORIZONTAL. DIP DIRECTION (DIP AZIMUTH) - THE DIRECTION OR BEARING OF THE HORIZONTAL TRACE OF THE LINE OF DIP, MEASURED CLOCKWISE FROM NORTH. FAULT - A FRACTURE OR FRACTURE ZONE ALONG WHICH THERE HAS BEEN DISPLACEMENT OF THE SIDES RELATIVE TO ONE ANOTHER PARALLEL TO THE FRACTURE. FISSILE - A PROPERTY OF SPLITTING ALONG CLOSELY SPACED PARALLEL PLANES. FLOAT - ROCK FRAGMENTS ON SURFACE NEAR THEIR ORIGINAL POSITION AND DISLODGED FROM PARENT MATERIAL. FLOOD PLAIN (FP) - LAND BORDERING A STREAM, BUILT OF SEDIMENTS DEPOSITED BY THE STREAM. FORMATION (FM) - A MAPPABLE GEOLOGIC UNIT THAT CAN BE RECOGNIZED AND TRACED IN THE FIELD. JOINT - FRACTURE IN ROCK ALONG WHICH NO APPRECIABLE MOVEMENT HAS OCCURRED. LEDGE - A SHELF-LIKE RIDGE OR PROJECTION OF ROCK WHOSE THICKNESS IS SMALL COMPARED TO ITS LATERAL EXTENT. LENS - A BODY OF SOIL OR ROCK THAT THINS OUT IN ONE OR MORE DIRECTIONS. MOTTLED (MOT.) - IRREGULARLY MARKED WITH SPOTS OF DIFFERENT COLORS. MOTTLING IN SOILS USUALLY INDICATES POOR AERATION AND LACK OF GOOD DRAINAGE. PERCHED WATER - WATER MAINTAINED ABOVE THE NORMAL GROUND WATER LEVEL BY THE PRESENCE OF AN INTERVENING IMPERVIOUS STRATUM. RESIDUAL (RES.) SOIL - SOIL FORMED IN PLACE BY THE WEATHERING OF ROCK. ROCK QUALITY DESIGNATION (ROD) - A MEASURE OF ROCK QUALITY DESCRIBED BY TOTAL LENGTH OF ROCK SEGMENTS EQUAL TO OR GREATER THAN 4 INCHES DIVIDED BY THE TOTAL LENGTH OF CORE RUN AND EXPRESSED AS A PERCENTAGE. SAPROLITE (SAP.) - RESIDUAL SOIL THAT RETAINS THE RELIC STRUCTURE OR FABRIC OF THE PARENT ROCK. SILL - AN INTRUSIVE BODY OF IGNEOUS ROCK OF APPROXIMATELY UNIFORM THICKNESS AND RELATIVELY THIN COMPARED WITH ITS LATERAL EXTENT, THAT HAS BEEN EMPLACED PARALLEL TO THE BEDDING OR SCHISTOSITY OF THE INTRUDED ROCKS. SLICKENSIDE - POLISHED AND STRIATED SURFACE THAT RESULTS FROM FRICTION ALONG A FAULT OR SLIP PLANE. STANDARD PENETRATION TEST (PENETRATION RESISTANCE) (SPT) - NUMBER OF BLOWS (N OR BPF) OF A 140 LB. HAMMER FALLING 30 INCHES REQUIRED TO PRODUCE A PENETRATION OF 1 FOOT INTO SOIL WITH A 2 INCH OUTSIDE DIAMETER SPLIT SPOON SAMPLER. SPT REFUSAL IS PENETRATION EQUAL TO OR LESS THAN 60 BLOWS PER 60 BLOWS. STRATA CORE RECOVERY (SREC) - TOTAL LENGTH OF STRATA MATERIAL RECOVERED DIVIDED BY TOTAL LENGTH OF STRATUM AND EXPRESSED AS A PERCENTAGE. STRATA ROCK QUALITY DESIGNATION (SROD) - A MEASURE OF ROCK QUALITY DESCRIBED BY TOTAL LENGTH OF ROCK SEGMENTS WITHIN A STRATUM EQUAL TO OR GREATER THAN 4 INCHES DIVIDED BY THE TOTAL LENGTH OF STRATA AND EXPRESSED AS A PERCENTAGE. TOPSOIL (TS) - SURFACE SOILS USUALLY CONTAINING ORGANIC MATTER.	
WEATHERED ROCK (WR)		NON-COASTAL PLAIN MATERIAL THAT WOULD YIELD SPT N VALUES > 100 BLOWS PER FOOT IF TESTED.	
CRYSTALLINE ROCK (CR)		FINE TO COARSE GRAIN IGNEOUS AND METAMORPHIC ROCK THAT WOULD YIELD SPT REFUSAL IF TESTED. ROCK TYPE INCLUDES GRANITE, GNEISS, GABBRO, SCHIST, ETC.	
NON-CRYSTALLINE ROCK (NCR)		FINE TO COARSE GRAIN METAMORPHIC AND NON-COASTAL PLAIN SEDIMENTARY ROCK THAT WOULD YIELD SPT REFUSAL IF TESTED. ROCK TYPE INCLUDES PHYLLITE, SLATE, SANDSTONE, ETC.	
COASTAL PLAIN SEDIMENTARY ROCK (CP)		COASTAL PLAIN SEDIMENTS CEMENTED INTO ROCK, BUT MAY NOT YIELD SPT REFUSAL. ROCK TYPE INCLUDES LIMESTONE, SANDSTONE, CEMENTED SHELL BEDS, ETC.	
WEATHERING			
FRESH		ROCK FRESH, CRYSTALS BRIGHT, FEW JOINTS MAY SHOW SLIGHT STAINING. ROCK RINGS UNDER HAMMER IF CRYSTALLINE.	
VERY SLIGHT (V SL.)		ROCK GENERALLY FRESH, JOINTS STAINED, SOME JOINTS MAY SHOW THIN CLAY COATINGS IF OPEN. CRYSTALS ON A BROKEN SPECIMEN FACE SHINE BRIGHTLY. ROCK RINGS UNDER HAMMER BLOWS IF OF A CRYSTALLINE NATURE.	
SLIGHT (SL.)		ROCK GENERALLY FRESH, JOINTS STAINED AND DISCOLORATION EXTENDS INTO ROCK UP TO 1 INCH. OPEN JOINTS MAY CONTAIN CLAY. IN GRANITOID ROCKS SOME OCCASIONAL FELDSPAR CRYSTALS ARE DULL AND DISCOLORED. CRYSTALLINE ROCKS RING UNDER HAMMER BLOWS.	
MODERATE (MOD.)		SIGNIFICANT PORTIONS OF ROCK SHOW DISCOLORATION AND WEATHERING EFFECTS. IN GRANITOID ROCKS, MOST FELDSPARS ARE DULL AND DISCOLORED, SOME SHOW CLAY. ROCK HAS DULL SOUND UNDER HAMMER BLOWS AND SHOWS SIGNIFICANT LOSS OF STRENGTH AS COMPARED WITH FRESH ROCK.	
MODERATELY SEVERE (MOD. SEV.)		ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED. IN GRANITOID ROCKS, ALL FELDSPARS DULL AND DISCOLORED AND A MAJORITY SHOW KAOLINIZATION. ROCK SHOWS SEVERE LOSS OF STRENGTH AND CAN BE EXCAVATED WITH A GEOLOGIST'S PICK. ROCK GIVES "CLUNK" SOUND WHEN STRUCK. IF TESTED, WOULD YIELD SPT REFUSAL.	
SEVERE (SEV.)		ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED. ROCK FABRIC CLEAR AND EVIDENT BUT REDUCED IN STRENGTH TO STRONG SOIL. IN GRANITOID ROCKS ALL FELDSPARS ARE KAOLINIZED TO SOME EXTENT. SOME FRAGMENTS OF STRONG ROCK USUALLY REMAIN. IF TESTED, YIELDS SPT N VALUES > 100 BPF.	
VERY SEVERE (V SEV.)		ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED. ROCK FABRIC ELEMENTS ARE DISCERNIBLE BUT THE MASS IS EFFECTIVELY REDUCED TO SOIL STATUS, WITH ONLY FRAGMENTS OF STRONG ROCK REMAINING. SAPROLITE IS AN EXAMPLE OF ROCK WEATHERED TO A DEGREE SUCH THAT ONLY MINOR VESTIGES OF THE ORIGINAL ROCK FABRIC REMAIN. IF TESTED, YIELDS SPT N VALUES < 100 BPF.	
COMPLETE		ROCK REDUCED TO SOIL. ROCK FABRIC NOT DISCERNIBLE, OR DISCERNIBLE ONLY IN SMALL AND SCATTERED CONCENTRATIONS. QUARTZ MAY BE PRESENT AS DIKES OR STRINGERS. SAPROLITE IS ALSO AN EXAMPLE.	
ROCK HARDNESS			
VERY HARD		CANNOT BE SCRATCHED BY KNIFE OR SHARP PICK. BREAKING OF HAND SPECIMENS REQUIRES SEVERAL HARD BLOWS OF THE GEOLOGIST'S PICK.	
HARD		CAN BE SCRATCHED BY KNIFE OR PICK ONLY WITH DIFFICULTY. HARD HAMMER BLOWS REQUIRED TO DETACH HAND SPECIMEN.	
MODERATELY HARD		CAN BE SCRATCHED BY KNIFE OR PICK. GOUGES OR GROOVES TO 0.25 INCHES DEEP CAN BE EXCAVATED BY HARD BLOW OF A GEOLOGIST'S PICK. HAND SPECIMENS CAN BE DETACHED BY MODERATE BLOWS.	
MEDIUM HARD		CAN BE GROOVED OR GOUGED 0.05 INCHES DEEP BY FIRM PRESSURE OF KNIFE OR PICK POINT. CAN BE EXCAVATED IN SMALL CHIPS TO PEICES 1 INCH MAXIMUM SIZE BY HARD BLOWS OF THE POINT OF A GEOLOGIST'S PICK.	
SOFT		CAN BE GROVED OR GOUGED READILY BY KNIFE OR PICK. CAN BE EXCAVATED IN FRAGMENTS FROM CHIPS TO SEVERAL INCHES IN SIZE BY MODERATE BLOWS OF A PICK POINT. SMALL, THIN PIECES CAN BE BROKEN BY FINGER PRESSURE.	
VERY SOFT		CAN BE CARVED WITH KNIFE. CAN BE EXCAVATED READILY WITH POINT OF PICK. PIECES 1 INCH OR MORE IN THICKNESS CAN BE BROKEN BY FINGER PRESSURE. CAN BE SCRATCHED READILY BY FINGERNAIL.	
FRACTURE SPACING		BEDDING	
TERM	SPACING	TERM	THICKNESS
VERY WIDE	MORE THAN 10 FEET	VERY THICKLY BEDDED	> 4 FEET
WIDE	3 TO 10 FEET	THICKLY BEDDED	1.5 - 4 FEET
MODERATELY CLOSE	1 TO 3 FEET	THINLY BEDDED	0.16 - 1.5 FEET
CLOSE	0.16 TO 1 FEET	VERY THINLY BEDDED	0.03 - 0.16 FEET
VERY CLOSE	LESS THAN 0.16 FEET	THICKLY LAMINATED	0.008 - 0.03 FEET
		THINLY LAMINATED	< 0.008 FEET
INDURATION			
FOR SEDIMENTARY ROCKS, INDURATION IS THE HARDENING OF THE MATERIAL BY CEMENTING, HEAT, PRESSURE, ETC.			
FRIABLE		RUBBING WITH FINGER FREES NUMEROUS GRAINS; GENTLE BLOW BY HAMMER DISINTEGRATES SAMPLE.	
MODERATELY INDURATED		GRAINS CAN BE SEPARATED FROM SAMPLE WITH STEEL PROBE; BREAKS EASILY WHEN HIT WITH HAMMER.	
INDURATED		GRAINS ARE DIFFICULT TO SEPARATE WITH STEEL PROBE; DIFFICULT TO BREAK WITH HAMMER.	
EXTREMELY INDURATED		SHARP HAMMER BLOWS REQUIRED TO BREAK SAMPLE; SAMPLE BREAKS ACROSS GRAINS.	
BENCH MARK: TBM: WHITE PAINTED DOT ON TOP OF STEEL BEAM ON THE NORTH EAST CORNER OF BRIDGE		(ASSUMED)	
		ELEVATION: 100.00 FT.	
NOTES: THIS REPORT PRESENTS PRELIMINARY TEST BORING DATA. NO SURVEY ALIGNMENT, ELEVATION, OR PROPOSED DESIGN DATA WERE AVAILABLE AT THE TIME OF THE INVESTIGATION.			

PROJECT REFERENCE NO.

480183

SHEET

3

SITE PLAN

050100

FEET






NCDOT GEOTECHNICAL ENGINEERING UNIT

BORELOG REPORT

SHEET 4

WBS 45358.1.22		TIP 480183		COUNTY IREDELL		GEOLOGIST Murray, C. C.					
SITE DESCRIPTION BRIDGE 183 OVER FOURTH CREEK ON SR 1907 (CHIPLEY FORD RD.)						GROUND WTR (ft)					
BORING NO. B-1		STATION N/A		OFFSET N/A		ALIGNMENT N/A					
COLLAR ELEV. 101.1 ft		TOTAL DEPTH 37.5 ft		NORTHING 763,975		EASTING 1,434,707					
DRILL RIG/HAMMER EFF./DATE HFO0066 CME-550 81% 09/02/2009				DRILL METHOD NW Casing w/ Advancer & Tri-Comp		HAMMER TYPE Automatic					
DRILLER Estep, J. E.		START DATE 06/20/12		COMP. DATE 06/20/12		SURFACE WATER DEPTH N/A					
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT		SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100	ELEV. (ft) DEPTH (ft)
105											
100											101.1 GROUND SURFACE 0.0
95	94.2	6.9	3	2	9						ROADWAY EMBANKMENT RED SOFT MOIST SANDY SILTY CLAY W/ ASPHALT & BASE 0.0-2.5
90	89.2	11.9	13	3	2						93.6 7.5
85	84.2	16.9	2	4	6						ALLUVIAL GRAY SOFT TO STIFF WET SANDY SILTY CLAY W/ WOOD 11.0
80	79.2	21.9	14	25	25						90.1 11.0
75	74.2	26.9	14	30	70/0.4						ALLUVIAL GRAY & WHITE LOOSE WET CLAYEY SAND & SAND, TRACE MICA
70	69.2	31.9	50	60	40/0.4						80.1 21.0
65	64.2	36.9	70	30/0.1							RESIDUAL GRAY & WHITE DENSE WET SILTY SAND
											74.2 26.9
											WEATHERED ROCK BLACK & GRAY & WHITE SEV. WEATH. CRYSTALLINE ROCK (AMPHIBOLITE GNEISS)
											63.6 37.5
											Boring Terminated at Elevation 63.6 ft IN SEV. WEATH. CRYSTALLINE ROCK (AMPHIBOLITE GNEISS)

NCDOT BORE SINGLE 049&000_GEO_BH_BRDG0183_IREDLL.GPJ NC_DOT.GDT 7/31/12






NCDOT GEOTECHNICAL ENGINEERING UNIT

BORELOG REPORT

SHEET 6

WBS 45358.1.22		TIP 480183		COUNTY IREDELL		GEOLOGIST Murray, C. C.						
SITE DESCRIPTION BRIDGE 183 OVER FOURTH CREEK ON SR 1907 (CHIPLEY FORD RD.)						GROUND WTR (ft)						
BORING NO. B-3		STATION N/A		OFFSET N/A		ALIGNMENT N/A						
COLLAR ELEV. 101.1 ft		TOTAL DEPTH 31.4 ft		NORTHING 763,887		EASTING 1,434,642						
DRILL RIG/HAMMER EFF./DATE HFO0066 CME-550 81% 09/02/2009				DRILL METHOD NW Casing w/ Advancer & Tri-Cone		HAMMER TYPE Automatic						
DRILLER Estep, J. E.		START DATE 06/21/12		COMP. DATE 06/21/12		SURFACE WATER DEPTH N/A						
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT		SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100		ELEV. (ft) DEPTH (ft)
105												
100												101.1 GROUND SURFACE 0.0
95	94.2	6.9	3	2	4							ROADWAY EMBANKMENT TAN & BLACK LOOSE WET SILTY SAND W/ ASPHALT & BASE 0.0-2.0
90	89.2	11.9	0	0	1							90.1 11.0
85	84.2	16.9	1	3	2							ALLUVIAL GRAY V. SOFT WET SANDY SILTY CLAY 86.1 15.0
80	79.2	21.9	12	19	20							ALLUVIAL GRAY & TAN LOOSE WET SILTY SAND 82.6 18.5
75	74.2	26.9	100/0.4									RESIDUAL GRAY-WHITE-TAN DENSE MOIST SILTY SAND 74.2 26.9
70												WEATHERED ROCK GRAY & WHITE & BLACK SEV. WEATH. CRYSTALLINE ROCK (BIOTITE GNEISS) 69.7 31.4
												Boring Terminated TRI-CONE REFUSAL at Elevation 69.7 ft ON CRYSTALLINE ROCK (BIOTITE GNEISS)

NCDOT BORE SINGLE 049&000_GEO_BH_BRD0183_IREDELL.GPJ NC_DOT_GDT 7/31/12

[illegible]