



January 16, 2017

Mr. Larry Absher
North Carolina Department of Transportation
Division 11 - Location & Surveys Office
P. O. Box 250
801 Statesville Road
North Wilkesboro, 28659

Description: Structure Number 02-0142, Alleghany County

Dear Larry:

Outlined below is a summary of the Survey that was conducted on the aforementioned Bridge Number:

- WBS Number 17bp.11.R.133, Bridge 02-0142 over Potato Creek on SR 1319 in Alleghany County, North Carolina.
- Field Surveyed between the dates of 01/02/17 thru 01/06/17.
- Worked performed for Division 9 – Location & Surveys Office.
- The Localized coordinate system developed for this project is based on the State Plain Coordinates established by NCDOT for monument "GPS-2" with NAD 83/NA 2011 State Plain Grid Coordinates of Northing: 1026872.0195 (ft), Easting: 1334985.6787 (ft), and having an elevation of 2588.071 (ft). The average combined grid factor used on this project (ground to grid) is: 1.00001044. The Vertical Datum used is NAVD 88.
- The geographical coordinates for the center of the bridge are N 36°33'01.55"W 81°15'50.26"
- There are no Utilities attached to the Bridge.
- CALYX called in 811 tickets for this site (Ticket # A170030694-00A). Underground utilities were mark by 811 at the time of the Survey. Below are the listed utilities in the area along with 811's comments:

Member Code	Description	Response
SKY01	SKYLINE TELEPHONE/SKYBEST COMMUNICATIONS PHONE AND CABLE Marked	01/05/17 12:49 PM 20

- See Attachment "A" for pictures of Site.
- Right of Way was established using the Right of Way abstract information provided to CALYX by NCDOT.
- This is a two lane bridge, one span with wood and asphalt deck. The bridge has wood head walls and wing walls. The beams are steel and the guardrail is wood.

- The parameters used to develop the .tin file are as follows: side dissolve option was used with a side length of 100 feet, the curve stroke tolerances was set at 0.15 and a minimum length of 30 feet.
- Deliverables are as listed below:
 - FS file to include control information normally shown on survey control sheet.
 - DTL File.
 - TIN File.
 - GPK File with ELN & BLN.
 - Baseline Text.
 - Survey report in Word Document format.
 - Survey Certification letter.
 - Deed Index book in .pdf format.
 - Propcon Data Base

Attachment "A"

Looking up station



Looking Down Station



Looking up stream



Looking down stream



Please contact CALYX Engineers + Consultants, Inc. if you have any comments or questions.

Yours truly,

A handwritten signature in blue ink, appearing to read "J. David Lee, II".

Mr. J. David Lee, II, PLS
Principal
Charlotte Survey Manager

H:\Project\2016\2016025.60\SUR\02-0142\Submit\11edb-con-ca_02-0142_Survey Report_170113.docx