

STATE OF NORTH CAROLINA SUMMARY OF QUANTITIES

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C200826

ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description
000100000-N	800	Lump Sum		MOBILIZATION	205500000-E	815	15	EA	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	444500000-E	1145	120	LF	BARRICADES (TYPE III)
002900000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (20+15.00)	206600000-N	815	1	EA	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	481000000-E	1205	8,400	LF	PAINT PAVEMENT MARKING LINES (4")
004300000-N	226	Lump Sum		GRADING	207700000-E	815	6	LF	6" OUTLET PIPE (SUBDRAINS)	600000000-E	1605	700	LF	TEMPORARY SILT FENCE
005000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUBBING	220900000-E	838	12	CY	ENDWALLS	600600000-E	1610	120	TON	STONE FOR EROSION CONTROL, CLASS A
005700000-E	226	300	CY	UNDERCUT EXCAVATION	228600000-N	840	2	EA	MASONRY DRAINAGE STRUCTURES	600900000-E	1610	530	TON	STONE FOR EROSION CONTROL, CLASS B
013400000-E	240	25	CY	DRAINAGE DITCH EXCAVATION	236700000-N	840	2	EA	FRAME WITH TWO GRATES, STD #40.29	601200000-E	1610	520	TON	SEDIMENT CONTROL STONE
019500000-E	265	700	CY	SELECT GRANULAR MATERIAL	255600000-E	846	50	LF	SHOULDER BERM GUTTER	601500000-E	1615	3	ACR	TEMPORARY MULCHING
019600000-E	270	500	SY	FABRIC FOR SOIL STABILIZATION	303000000-E	862	275	LF	STEEL BM GUARDRAIL	601800000-E	1620	100	LB	SEED FOR TEMPORARY SEEDING
031200000-E	300	1,000	TON	SELECT MATERIAL, CLASS IV	304500000-E	862	287.5	LF	STEEL BM GUARDRAIL, SHOP CURVED	602100000-E	1620	0.5	TON	FERTILIZER FOR TEMPORARY SEEDING
031800000-E	300	35	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	319500000-N	862	1	EA	GUARDRAIL ANCHOR UNITS, TYPE AT-1	603000000-E	1630	775	CY	SILT EXCAVATION
036600000-E	310	76	LF	15" RC PIPE CULVERTS, CLASS III	321500000-N	862	2	EA	GUARDRAIL ANCHOR UNITS, TYPE III	603600000-E	1631	1,240	SY	MATting FOR EROSION CONTROL
037200000-E	310	64	LF	18" RC PIPE CULVERTS, CLASS III	327000000-N	SP	3	EA	GUARDRAIL ANCHOR UNITS, TYPE 350	603800000-E	SP	360	SY	PERMANENT SOIL REINFORCEMENT MAT
038400000-E	310	64	LF	30" RC PIPE CULVERTS, CLASS III	336000000-E	863	160	LF	REMOVE EXISTING GUARDRAIL	604200000-E	1632	40	LF	1/4" HARDWARE CLOTH
040200000-E	310	80	LF	48" RC PIPE CULVERTS, CLASS III	343500000-N	SP	2	EA	GENERIC GUARDRAIL ITEM GUARDRAIL ANCHOR UNITS, TYPE III, SHOP CURVED	607000000-N	SP	16	EA	SPECIAL STILLING BASINS
099500000-E	340	67	LF	PIPE REMOVAL	364900000-E	876	20	TON	PLAIN RIP RAP, CLASS B	608400000-E	1660	3.5	ACR	SEEDING & MULCHING
112100000-E	520	1,100	TON	AGGREGATE BASE COURSE	365600000-E	876	1,050	SY	FILTER FABRIC FOR DRAINAGE	608700000-E	1660	2	ACR	MOWING
122000000-E	545	50	TON	INCIDENTAL STONE BASE	402500000-E	901	17	SF	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	609000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
149800000-E	610	600	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE 119.0B	407200000-E	903	31	LF	SUPPORTS, 3-LB STEEL U-CHANNEL	609300000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
151400000-E	610	300	TON	ASPHALT CONC SURFACE COURSE, TYPE 89.5A	410200000-N	904	4	EA	SIGN ERECTION, TYPE E	609600000-E	1662	75	LB	SEED FOR SUPPLEMENTAL SEEDING
156000000-E	620	100	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	415500000-N	907	4	EA	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	610800000-E	1665	2.5	TON	FERTILIZER TOPDRESSING
200000000-N	806	23	EA	RIGHT OF WAY MARKERS	415800000-N	907	2	EA	DISPOSAL OF SIGN SYSTEM, WOOD	611400000-N	SP	2	HR	SPECIALIZED HAND MOWING
202200000-E	815	120	CY	SUBDRAIN EXCAVATION	440000000-E	1110	307	SF	WORK ZONE SIGNS (STATIONARY)	611700000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL
203300000-E	815	90	CY	SUBDRAIN FINE AGGREGATE	441000000-E	1110	94	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)					
204400000-E	815	500	LF	6" PERFORATED SUBDRAIN PIPE	442500000-N	1125	4	EA	WARNING FLAG SETS					