

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (20+15.00)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	300 CY		
0006	0134000000-E	240	DRAINAGE DITCH EXCAVATION	25 CY		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	700 CY		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0009	0312000000-E	300	SELECT MATERIAL, CLASS IV	1,000 TON		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	35 TON		
0011	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	76 LF		
0012	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	64 LF		
0013	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	64 LF		
0014	0402000000-E	310	48" RC PIPE CULVERTS, CLASS III	80 LF		
0015	0995000000-E	340	PIPE REMOVAL	67 LF		
0016	1121000000-E	520	AGGREGATE BASE COURSE	1,100 TON		
0017	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		
0018	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	600 TON		

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1514000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5A	300 TON		
0020	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	100 TON		
0021	2000000000-N	806	RIGHT OF WAY MARKERS	23 EA		
0022	2022000000-E	815	SUBDRAIN EXCAVATION	120 CY		
0023	2033000000-E	815	SUBDRAIN FINE AGGREGATE	90 CY		
0024	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	500 LF		
0025	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	15 EA		
0026	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0027	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0028	2209000000-E	838	ENDWALLS	12 CY		
0029	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0030	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0031	2556000000-E	846	SHOULDER BERM GUTTER	50 LF		
0032	3030000000-E	862	STEEL BM GUARDRAIL	275 LF		
0033	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	287.5 LF		
0034	3180000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** (III, SHOP CURVED)	2 EA		
0035	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
0036	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	2 EA		

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	3 EA		
0038	3360000000-E	863	REMOVE EXISTING GUARDRAIL	160 LF		
0039	3649000000-E	876	PLAIN RIP RAP, CLASS B	20 TON		
0040	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,050 SY		
0041	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	17 SF		
0042	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	31 LF		
0043	4102000000-N	904	SIGN ERECTION, TYPE E	4 EA		
0044	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	4 EA		
0045	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	2 EA		
0046	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	307 SF		
0047	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94 SF		
0048	4425000000-N	1125	WARNING FLAG SETS	4 EA		
0049	4445000000-E	1145	BARRICADES (TYPE III)	120 LF		
0050	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	8,400 LF		
0051	6000000000-E	1605	TEMPORARY SILT FENCE	700 LF		
0052	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	120 TON		
0053	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	530 TON		
0054	6012000000-E	1610	SEDIMENT CONTROL STONE	520 TON		
0055	6015000000-E	1615	TEMPORARY MULCHING	3 ACR		

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0057	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.5 TON		
0058	6030000000-E	1630	SILT EXCAVATION	775 CY		
0059	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,240 SY		
0060	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	360 SY		
0061	6042000000-E	1632	1/4" HARDWARE CLOTH	40 LF		
0062	6070000000-N	SP	SPECIAL STILLING BASINS	16 EA		
0063	6084000000-E	1660	SEEDING & MULCHING	3.5 ACR		
0064	6087000000-E	1660	MOWING	2 ACR		
0065	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0066	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0067	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75 LB		
0068	6108000000-E	1665	FERTILIZER TOPDRESSING	2.5 TON		
0069	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0070	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	8 EA		
0071	6147000000-E	SP	GENERIC EROSION CONTROL ITEM SAFETY FENCE	500 LF		

STRUCTURE ITEMS

0072	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (20+15.00 -L-)	Lump Sum	L.S.	
0073	8096000000-E	SP	PILE EXCAVATION IN SOIL	20 LF		

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	8097000000-E	SP	PILE EXCAVATION NOT IN SOIL	20 LF		
0075	8105540000-E	SP	3'-6" DIA DRILLED PIERS IN SOIL	35.45 LF		
0076	8105640000-E	SP	3'-6" DIA DRILLED PIERS NOT IN SOIL	56 LF		
0077	8115000000-N	SP	CROSSHOLE SONIC LOGGING	1 EA		
0078	8116000000-E	SP	CSL TUBES	445.75 LF		
0079	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVATION	707 CY		
0080	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	7,649 SF		
0081	8161000000-E	420	GROOVING BRIDGE FLOORS	8,422 SF		
0082	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	145.7 CY		
0083	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (20+15.00 -L-)	Lump Sum	L.S.	
0084	8217000000-E	425	REINFORCING STEEL (BRIDGE)	31,127 LB		
0085	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	2,140 LB		
0086	8280000000-E	440	APPROX LBS STRUCTURAL STEEL	392,000 LS		
0087	8364000000-E	450	HP12X53 STEEL PILES	51 LF		
0088	8503000000-E	460	CONCRETE BARRIER RAIL	355.09 LF		
0089	8608000000-E	876	PLAIN RIP RAP CLASS II (2'-0" THICK)	161 TON		
0090	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	179 SY		
0091	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0092	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

1404/Sep08/Q465236.24/D407986280000/E92

Total Amount Of Bid For Entire Project :

C200826
BURKE COUNTY

2/16/99

Contract No: C200826

Counties: Burke

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General