

**INDEX OF SHEETS**

1	TITLE SHEET
1A	INDEX OF SHEETS, GENERAL NOTES & LIST OF STANDARDS
1B	CONVENTIONAL SYMBOLS
2, 2-A, 2-B	TYPICAL SECTIONS
2-C	INTERSECTION / BRIDGE DETAILS
2-D	GUIDE FOR GRADING SUBGRADE
2-E	REINFORCED BRIDGE APPROACH FILLS
2-F	REINFORCED BRIDGE APPROACH FILLS
2-G	CONVERT EXISTING OPEN THROAT CATCH BASIN TO MEDIAN DROP INLET
2-H	DROP INLET INSTALLATION IN EXPRESSWAY GUTTER
2-I	DETAIL FOR CONCRETE BRIDGE APPROACH DROP INLET
2-J	DRIVEWAY TURNOUT
2-K	RETROFITTING DETECTABLE WARNING DOMES ONTO EXISTING WHEELCHAIR RAMP
2-L	WHEELCHAIR RAMP
2-M	GUARDRAIL INSTALLATION
2-N	GUARDRAIL INSTALLATION
2-O	GUARDRAIL INSTALLATION
2-P	GUARDRAIL INSTALLATION
2-Q	STRUCTURE ANCHOR UNITS
2-R	STRUCTURE ANCHOR UNITS
2-S	STANDARD TEMPORARY SHORING FOR MAINTENANCE OF TRAFFIC
3	SUMMARY OF QUANTITIES
3-A, 3-B, 3-C	PIPE SUMMARY
3-D	COMBINATION SUMMARY OF QUANTITIES SHEET
3-E	RIGHT OF WAY SUMMARY SHEET
3-F	PARCEL INDEX SHEET
4-9	PLAN SHEET
10	L PROFILE
11	L PROFILE / RAMP A PROFILE
12	RAMP B PROFILE
13	RAMP C PROFILE
14	RAMP D PROFILE
15	Y1 PROFILE
16	Y2 PROFILE
17	Y3 PROFILE
18	Y4 PROFILE
TCP-1 THRU TCP-24	TRAFFIC CONTROL PLANS
PM-1 THRU PM-4	PAVEMENT MARKING PLANS
EC-1 THRU EC-14	EROSION CONTROL PLANS
SIGN-1 THRU SIGN-10	SIGNING PLANS
SIG-1 THRU SIG-17	SIGNAL PLANS
UC-1 THRU UC-6	UTILITY CONSTRUCTION PLANS
UO-1 THRU UO-4	UTILITIES BY OTHERS PLANS
X-1A	CROSS SECTION SUMMARY
X-1 THRU X-78	CROSS SECTIONS
S-1 THRU S-51	STRUCTURE PLANS
W-1 THRU W-3	RETAINING WALL PLANS

**GENERAL NOTES:** 2002 SPECIFICATIONS  
EFFECTIVE: 01-15-02

**GRADE LINE:  
GRADING AND SURFACING OR RESURFACING AND WIDENING:**

THE GRADE LINES SHOWN DENOTE THE FINISHED ELEVATION OF THE PROPOSED SURFACING AT GRADE POINTS SHOWN ON THE TYPICAL SECTIONS. WHERE NO GRADE LINES ARE SHOWN, THE PROFILES SHOWN DENOTE THE TOP ELEVATION OF THE EXISTING PAVEMENT ALONG THE CENTER LINE OF SURVEY ON WHICH THE PROPOSED RESURFACING WILL BE PLACED. GRADE LINES MAY BE ADJUSTED BY THE ENGINEER IN ORDER TO SECURE A PROPER TIE-IN.

**CLEARING:**

CLEARING ON THIS PROJECT SHALL BE PERFORMED TO THE LIMITS ESTABLISHED BY METHOD III.

**SUPERELEVATION:**

ALL CURVES ON THIS PROJECT SHALL BE SUPERELEVATED IN ACCORDANCE WITH STD. NO. 225.04 USING THE RATE OF SUPERELEVATION AND RUNOFF SHOWN ON THE PLANS. SUPERELEVATION IS TO BE REVOLVED ABOUT THE GRADE POINTS SHOWN ON THE TYPICAL SECTIONS.

**SHOULDER CONSTRUCTION:**

ASPHALT AND EARTH SHOULDER CONSTRUCTION ON HIGH SIDE OF SUPERELEVATED CURVES SHALL BE IN ACCORDANCE WITH STD. NO. 560.02.

**SIDE ROADS:**

THE CONTRACTOR WILL BE REQUIRED TO DO ALL NECESSARY WORK TO PROVIDE SUITABLE CONNECTIONS WITH ALL ROADS, STREETS, AND DRIVES ENTERING THIS PROJECT. THIS WORK WILL BE PAID FOR AT THE CONTRACT UNIT PRICE FOR THE PARTICULAR ITEMS INVOLVED.

**DRIVEWAYS:**

DRIVEWAYS SHALL BE CONSTRUCTED IN ACCORDANCE WITH DETAILS IN PLANS AT LOCATIONS SHOWN ON PLANS OR AS DIRECTED BY THE ENGINEER.

STREET RETURNS SHALL BE CONSTRUCTED IN ACCORDANCE WITH STD. NO. 848.04 USING THE RADII NOTED ON PLANS.

**GUARDRAIL:**

THE GUARDRAIL LOCATIONS SHOWN ON THE PLANS MAY BE ADJUSTED DURING CONSTRUCTION AS DIRECTED BY THE ENGINEER. THE CONTRACTOR SHOULD CONSULT WITH THE ENGINEER PRIOR TO ORDERING GUARDRAIL MATERIAL.

**TEMPORARY SHORING:**

SHORING REQUIRED FOR THE MAINTENANCE OF TRAFFIC NOT SHOWN ON THE PLANS WILL BE PAID FOR AT THE CONTRACT PRICE FOR "TEMPORARY SHORING" OR "TEMPORARY SHORING-BARRIER SUPPORTED" DEPENDING UPON THE LOCATION OF THE SHORING.

**SUBSURFACE PLANS:**

NO SUBSURFACE PLANS ARE AVAILABLE ON THIS PROJECT. THE CONTRACTOR SHOULD MAKE HIS OWN INVESTIGATION AS TO THE SUBSURFACE CONDITIONS.

**END BENTS:**

THE ENGINEER SHALL CHECK THE STRUCTURE END BENT PLANS, DETAILS, AND CROSS-SECTION PRIOR TO SETTING OF THE SLOPE STAKES FOR THE EMBANKMENT OR EXCAVATION APPROACHING A BRIDGE.

**UTILITIES:**

UTILITY OWNERS ON THIS PROJECT ARE:

PIEDMONT GAS                      DUKE ENERGY(DISTRIBUTION)  
BELL SOUTH                      TIME WARNER

ANY RELOCATION OF EXISTING UTILITIES WILL BE ACCOMPLISHED BY OTHERS, EXCEPT AS SHOWN ON THE PLANS.

**RIGHT-OF-WAY MARKERS:**

ALL RIGHT-OF-WAY MARKERS ON THIS PROJECT SHALL BE PLACED BY CONTRACT.

EFF. 01-15-02

**ROADWAY ENGLISH STANDARD DRAWINGS**

The following Roadway Standards as appear in "Roadway Standard Drawings" Highway Design Branch - N. C. Department of Transportation - Raleigh, N. C., Dated January 15, 2002 are applicable to this project and by reference hereby are considered a part of these plans:

**DIVISION 2 - EARTHWORK**

200.03	Method of Clearing - Method III
225.01	Guide for Grading Subgrade - Interstate and Freeway
225.02	Guide for Grading Subgrade - Secondary and Local
225.03	Deceleration and Acceleration Lanes
225.04	Method of Obtaining Superelevation - Two Lane Pavement
225.06	Method of Grading Sight Distance at Intersections
225.09	Guide for Shoulder and Ditch Transition at Grade Separations

**DIVISION 3 - PIPE CULVERTS**

300.01	Method of Pipe Installation - Method 'A'
310.10	Driveway Pipe Construction

**DIVISION 4 - MAJOR STRUCTURES**

422.10	Reinforced Bridge Approach Fills
--------	----------------------------------

**DIVISION 5 - SUBGRADE, BASES AND SHOULDERS**

560.02	Method of Shoulder Construction - High Side of Superelevated Curve - Method II
--------	--

**DIVISION 6 - ASPHALT BASES AND PAVEMENTS**

654.01	Pavement Repairs
665.01	Milled Rumble Strips - Asphalt Pavements

**DIVISION 8 - INCIDENTALS**

840.00	Concrete Base Pad for Drainage Structures
840.01	Brick Catch Basin - 12" thru 54" Pipe
840.02	Concrete Catch Basin - 12" thru 54" Pipe
840.03	Frame, Grates and Hood - for Use on Standard Catch Basin
840.04	Concrete Catch Basin with Single and Multiple Pipes - 12" thru 48" Pipe
840.05	Brick Catch Basin with Single and Multiple Pipes - 12" thru 48" Pipe
840.14	Concrete Drop Inlet - 12" thru 30" Pipe
840.15	Brick Drop Inlet - 12" thru 30" Pipe
840.16	Drop Inlet Frame and Grates - for use with Std. Dwg.s 840.14 and 840.15
840.18	Concrete Median Drop Inlet Type 'B' - 12" thru 36" Pipe
840.20	Frames and Wide Slot Flat Grates
840.22	Frames and Wide Slot Sag Grates
840.27	Brick Median Drop Inlet Type 'B' - 12" thru 36" Pipe
840.34	Traffic Bearing Junction Box - for Use with Pipes 42" and Under
840.45	Precast Drainage Structure
840.66	Drainage Structure Steps
840.71	Concrete and Brick Pipe Plug
840.72	Pipe Collar
846.01	Concrete Curb, Gutter and Curb & Gutter
846.02	Expressway Gutter Transition for Drop Inlet
848.03	Driveway Turnout - Drop Curb Type
848.04	Street Turnout
848.05	Wheelchair Ramp - Curb Cut
850.01	Concrete Paved Ditches
850.10	Guide for Berm Drainage Outlet - 15" and 18" Pipe
852.01	Concrete Islands
852.06	Method for Placement of Drop Inlets in Concrete Islands
862.01	Guardrail Placement
862.03	Structure Anchor Units
866.02	Woven Wire Fence - with Wood Post
876.02	Guide for Rip Rap at Pipe Outlets
876.04	Drainage Ditches with Class 'B' Rip Rap