

U-2717

**Project Special Provisions
Erosion Control**

Guilford County

Seeding And Mulching

(3)

The kinds of seed and fertilizer, and the rates of application of seed, fertilizer, and limestone, shall be as stated below. During periods of overlapping dates, the kind of seed to be used shall be determined by the Engineer. All rates are in pounds per acre (kilograms per hectare).

August 1 - June 1

March 1 - September 1

100# (110kg) Tall Fescue	100# (110kg) Tall Fescue
15# (17kg) Kentucky Bluegrass	15# (17kg) Kentucky Bluegrass
15# (17kg) Hard Fescue	15# (17kg) Hard Fescue
500# (560kg) Fertilizer	25# (28kg) Kobe or Korean Lespedeza
4000# (4500kg) Limestone	500# (560kg) Fertilizer
	4000# (4500kg) Limestone

Approved Tall Fescue Cultivars:

Adventure	Adventure II	Amigo	Anthem
Apache	Apache II	Arid	Austin
Brookstone	Bonanza	Bonanza II	Chapel Hill
Chesapeake	Chieftain	Coronado	Crossfire II
Debutante	Duster	Falcon	Falcon II
Finelawn Petite	Finelawn	Finelawn I	Genesis
Grande	Guardian	Houndog	Jaguar
Jaguar III	Kentucky 31	Kitty Hawk	Monarch
Montauk	Mustang	Olympic	Pacer
Phoenix	Pixie	Pyramid	Rebel
Rebel Jr.	Rebel II	Renegade	Safari
Shenandoah	Tempo	Titan	Tomahawk
Trailblazer	Tribute	Vegas	Wolfpack
Wrangler			

Approved Kentucky Bluegrass Cultivars:

Adelphi	Baron	Bristol	Challenger
Columbia	Fylking	Glade	Kenblue
Merit	Plush	Ram I	Rugby
Sydsport	Touchdown	Vantage	

Approved Hard Fescue Cultivars:

Aurora	Bardur	Crystal	Reliant	Scaldis
--------	--------	---------	---------	---------

Spartan

Valda

Waldina

Warwick

On cut and fill slopes 2:1 or steeper add 30# (35 kg) Sericea Lespedeza January 1 - December 31.

Fertilizer shall be 10-20-20 analysis. Upon written approval of the Engineer, a different analysis of fertilizer may be used provided the 1-2-2 ratio is maintained and the rate of application adjusted to provide the same amount of plant food as a 10-20-20 analysis.

Temporary Seeding:

Fertilizer shall be the same analysis as specified for "Seeding and Mulching" and applied at the rate of 400 pounds (450kg) and seeded at the rate of 50 pounds per acre (55kg per hectare). Sweet Sudan Grass, German Millet, or Browntop Millet shall be used in summer months and rye grain during the remainder of the year. The Engineer will determine the exact dates for using each kind of seed.

Fertilizer Topdressing:

Fertilizer used for topdressing shall be 16-8-8 grade and shall be applied at the rate of 500 pounds per acre (560 kg per hectare). Upon written approval of the Engineer, a different analysis of fertilizer may be used provided the 2-1-1 ratio is maintained and the rate of application adjusted to provide the same amount of plant food as 16-8-8 analysis.

Supplemental Seeding:

The kinds of seed and proportions shall be the same as specified for "Seeding and Mulching", and the rate of application may vary from 25# to 75# per acre (28kg to 85kg per hectare). The actual rate per acre (hectare) will be determined by the Engineer prior to the time of topdressing and the Contractor will be notified in writing of the rate per acre (hectare), total quantity needed, and areas on which to apply the supplemental seed. Minimum tillage equipment, consisting of a sod seeder shall be used for incorporating seed into the soil as to prevent disturbance of existing vegetation. A clodbuster (ball and chain) may be used where degree of slope prevents the use of a sod seeder.

Mowing:

The minimum mowing height on this project shall be six inches (150 mm).

Lawn Type Appearance

All areas adjacent to lawns must be hand finished as directed by the Engineer to give a "lawn type appearance". Remove all trash, debris, and stones $\frac{3}{4}$ inch (19 mm) and larger in diameter or other obstructions that could interfere with providing a smooth "lawn type appearance". These areas shall be reseeded to match their original vegetative conditions, unless directed otherwise by the Field Operations Engineer.

Specialized Seeding Under Guiderail and Guardrail (Hard Fescue/Bluegrass):**General:**

Areas under guiderail and guardrail sections shall be seeded in accordance with these provisions and as directed by the Engineer. Perform the work covered by this provision including but not limited to litter and debris removal, mowing, disposal of weeds and other unacceptable growth, grading, soil preparation and amendment, surface smoothing, seed applications, and matting installation.

Materials:

Only approved Hard Fescue and Kentucky Bluegrass seed that complies with Section 1060 of the Standard Specifications shall be used.

Soil Preparation:

Remove litter and other debris. Mow and satisfactorily dispose of weeds or other unacceptable growth on the areas to be seeded.

Prior to seeding, all eroded, uneven and rough areas shall be contour graded and/or filled with soil as directed by the Engineer. The soil shall be scarified or otherwise loosened to a depth of not less than 5 inches (130 mm) with a minimum width of 48 inches (1145 mm) and a maximum width of 52 inches (1320 mm). Clods shall be broken and the top 2 to 3 inches (52 to 78 mm) of soil shall be worked into an acceptable soil bed by the use of soil pulverizers, drags, or harrows.

Soil amendments shall be as follows:

Limestone: Limestone shall be applied at a rate of 4000 pounds (4500 Kg/Hectare) per acre.

Fertilizer: Fertilizer shall be 10-20-20 analysis and applied at a rate of 500 pounds (560kg/Hectare) per acre.

After soil preparation, lime and fertilizer shall be uniformly distributed by mechanical means using a 48 inch (1065 mm) drop type spreader and thoroughly mixed with the top five inches (130 mm) of the soil by discing, harrowing, or other approved methods.

The area shall then be harrowed, dragged, raked, or prepared by other approved methods which will give a lawn type finish. All trash, debris and stones larger than 1-1/2 inch (38 mm) in diameter or other obstructions shall also be removed.

Application:

(Hard Fescue/Bluegrass) seed shall be uniformly distributed at a rate of 75 pounds per acre (85 kilograms per hectare) of Hard Fescue and 20 pounds per acre (28 kilograms per hectare) of Kentucky bluegrass by mechanical means.

Immediately following the placement of seed, the area shall be rolled or tamped carefully and firmly by means acceptable to the Engineer to ensure a smooth surface. Use of rubber tired equipment to roll shall not be allowed.

Matting:

Immediately upon completion of seeding work and herbicidal application, 48 inch wide matting shall be installed over the seeded area in accordance with Section 1631 of the Standard Specifications.

Basis of Payment:

The quantity of "Specialized Seeding Under Guiderail and Guardrail (Hard Fescue/Bluegrass)" to be paid for will be the actual number of acres (hectares) of guiderail and guardrail sections, measured along the surface of the ground, over which acceptable seeding has been performed. The quantity of seeding will be paid for at the contract unit price per acre (hectare) for "Specialized Seeding Under Guiderail and Guardrail (Fescue/Bluegrass)".

No payment shall be made for "Specialized Seeding Under Guiderail and Guardrail (Fescue/Bluegrass)" in which the work has not been satisfactorily completed. Complete work includes but is not limited to soil preparation, surface smoothing, seeding, and matting.

Specialized Hand Mowing:

The work covered by this section consists of specialized hand mowing around or under fixed objects, including but not limited to guardrails, signs, barriers and slopes in a method acceptable to the Engineer.

The work of specialized hand mowing shall be completed with mechanically powered trimmers, string trimmers, hand operated rotary mowers, or self-propelled mowers of sufficient size and quality to perform the work timely and efficiently.

The quantity of mowing to be performed will be affected by the actual conditions which occur during the construction of the project. The quantity of mowing may be increased, decreased or eliminated entirely at the direction of the Engineer. Such variations in quantity will not be considered as alterations in the details of construction or a change in the character of the work.

The quantity of specialized hand mowing to be paid for will be the actual number of man hours worked while hand mowing along the surface of the ground, at the direction of the Engineer. Where an area has been mowed more than once, at the direction of the Engineer, separate measurement will be made each time the area is mowed.

Payment will be made under:

Specialized Hand Mowing.....HR

Environmentally Sensitive Areas:

This project is located in an “Environmentally Sensitive Area”. This designation requires special procedures to be used for clearing and grubbing, temporary stream crossings, and grading operations within the area identified on the plans. This also requires special procedures to be used for seeding and mulching and staged seeding within the project.

Clearing and Grubbing:

In areas identified on the erosion control plans as “Environmentally Sensitive Areas”, the Contractor may perform clearing operations, but not grubbing operations until immediately prior to beginning grading operations as described in Section 200, Article 200-1, in the Standard Specifications. The “Environmentally Sensitive Area” shall be defined as a 50 foot (16 meter) buffer zone on both sides of the stream (or depression), measured from top of streambank, (or center of depression). Only clearing operations (not grubbing) shall be allowed in this buffer zone until immediately prior to beginning grading operations. Erosion control devices shall be installed immediately following the clearing operation.

Grading:

Once grading operations begin in identified “Environmentally Sensitive Areas”, work will progress in a continuous manner until complete. All construction within these areas must progress in a continuous manner such that each phase is complete and areas permanently stabilized prior to beginning of next phase. Failure on the part of the Contractor to complete any phase of construction in a continuous manner in “Environmentally Sensitive Areas” as specified will be just cause for the Engineer to direct the suspension of work in accordance with Section 108-7 of the Standard Specifications.

Temporary Stream Crossings:

Any crossing of streams within the limits of this project must be accomplished in accordance with Section 107-13(b) of the Standard Specifications.

Seeding and Mulching:

Seeding and mulching shall be performed in accordance with Section 1660 of the Standard Specifications and vegetative cover sufficient to restrain erosion shall be installed immediately following grade establishment.

Seeding and mulching shall be performed on the areas disturbed by construction immediately following final grade establishment. No appreciable time shall lapse into the contract time without stabilization of slopes, ditches and other areas within the "Environmentally Sensitive Areas" as indicated on the E.C. Plans.

Stage Seeding:

The work covered by this section shall consist of the establishment of a vegetative cover on cut and fill slopes as grading progresses. Seeding and mulching shall be done in stages on cut and fill slopes which are greater than 20 feet (6 meters) in height or greater than 2 acres (0.8 hectares) in area. Each stage shall not exceed the limits stated above.

All work described above will be paid for at the contract unit prices established in the contract for the work involved. Additional payments will not be made for the requirements of this section as the cost for this work should be included in the contract unit prices for the work involved.

Minimize Removal Of Vegetation

The Contractor shall minimize removal of vegetation at stream banks and disturbed areas within the project limits as directed by the Engineer.

Stockpile Areas

The Contractor shall install and maintain erosion control devices sufficient to contain sediment around any erodible material stockpile areas as directed by the Engineer.

Streambank Reforestation:

Streambank reforestation will be planted in areas designated on the plans and as directed by the Engineer. See the streambank reforestation detail sheet.

Type I Streambank Reforestation shall be live stakes, planted along both streambanks.

Coir fiber mat shall be installed on the streambanks where live staking is to be planted as shown on the streambank reforestation detail sheet and in locations as directed by the Engineer. Work includes providing all materials, excavating and backfilling, and placing and securing coir fiber mat.

Provide matting to meet the following requirements:

100 % coconut fiber (coir) twine woven into a high strength matrix.
Thickness - 0.30 in. minimum. (7.6 mm)
Tensile Strength - 1348 x 626 lb/ft minimum (1650.5 x 766.5 kg/m)
Elongation - 34% x 38% maximum
Flexibility (mg-cm)- 65030 x 29590
Flow Velocity- Observed 11 ft/sec (3.35 m/s)
Weight - 20 oz/SY (678 g/SM)
Size - 6.6 x 164 ft (120 SY) or (100 SM)
“C” Factor - 0.002
Open Area (measured) - 50%

Provide wooden stakes 12 in. (300 mm) in length with a notch cut 1 in. (25 mm) from top.

Place the matting immediately upon final grading. Provide a smooth soil surface free from stones, clods, or debris which will prevent the contact of the matting with the soil. Take care to preserve the required line, grade, and cross section of the area covered.

Unroll the matting and apply without stretching such that it will lie smoothly but loosely on the soil surface. Bury the top slope end of each piece of matting in a narrow trench at least 6 in. (150 mm) deep and tamp firmly. Where one roll of matting ends and a second roll begins, overlap the end of the upper roll over the buried end of the second roll so there is a 6 in. (150 mm) overlap. Construct check trenches at least 12 in. (0.3 m) deep every 50 ft. (16 m) longitudinally along the edges of the matting or as directed by the Engineer. Fold over and bury matting to the full depth of the trench, close and tamp firmly. Overlap matting at least 6 in. (150 mm) where 2 or more widths of matting are installed side by side.

Place stakes across the matting at ends, junctions, and check trenches approximately 1 ft. (0.3 m) apart with notch facing upslope.

Place stakes along the outer edges and down the center of each strip of matting 3 feet (1 meter) apart. Place stakes along all lapped edges 1 ft. (0.3 m) apart. Refer to details in the plan sheets.

The Engineer may require adjustments in the trenching or staking requirements to fit individual site conditions.

Live staking plant material shall consist of a random mix made up of 50% Black Willow (*Salix nigra*), 50% Silky Dogwood (*Cornus amomum*). Other species may be substituted upon approval of Engineer.

All plant material shall be harvested locally (within the same physiographic ecoregion and plant hardiness zone) or purchased from a local nursery, with the approval of the Engineer. All live stakes shall be dormant at time of acquisition and planting.

Live stakes shall be 1/2-2 inches (12-50 mm) in diameter. Stakes shall also be 2-3 feet (0.6-1 meter) in length.

During preparation, the basal ends of the live stakes shall be cleanly cut at an angle to facilitate easy insertion into the soil, while the tops shall be cut square or blunt for tamping. All limbs shall be removed from the sides of the live cutting prior to installation.

Live stakes shall be installed within 48 hours of cutting. Outside storage locations should be continually shaded and protected from wind and direct sunlight. Live cut plant material shall remain moist at all times before planting.

Install live stakes according to the streambank reforestation detail sheet.

Tamp live stakes perpendicularly into the finished bank slope with a dead blow hammer, with buds oriented in an upward direction. Stakes should be tamped until approximately 3/4 of the stake length is within the ground.

The area around each live stake shall be compacted by foot after the live stake has been installed.

Stakes shall be spaced approximately 4 feet (1.2 meters) on center. Live stakes should be installed according to the configuration presented in the details of the plan sheets.

One to two inches shall be cut cleanly off of the top of each live stake (with loppers) at an angle of approximately 15 degrees following installation.

Any stakes that are split or damaged during installation shall be removed and replaced.

Type II Streambank Reforestation shall be bare root seedlings. The seedlings shall be planted as soon as practical following permanent seeding and mulching. The seedlings shall be planted from top of bank out, along both sides of stream, as designated on the plans.

Seedlings shall be 12–18 inches (300-460mm) tall.

Root dip: The roots of reforestation seedlings shall be coated with a slurry of water, and either a fine clay ("kaolin") or a superabsorbent that is made to be used as a bare root dip. The type, mixture ratio, method of application, and the time of application shall be submitted to the Engineer for approval.

With the approval of the Engineer, seedlings may be coated before delivery to the job or at the time of planting, but at no time shall the roots of the seedlings be allowed to dry out. The roots shall be moistened immediately prior to planting.

Seasonal Limitations: Streambank reforestation shall be planted from November 15 through March 15.

Measurement:

The quantity of streambank reforestation to be paid for will be the actual number of acres (hectares) of land, measured along of the surface of ground, which has been acceptably planted with seedlings in accordance with these specifications.

Payment:

The quantity of streambank reforestation will be paid for at the contract unit price per acre (hectare) for "Streambank Reforestation".

Payment will be made under:

Streambank Reforestation.....ACR (HA)

Waste Areas And Borrow Sources:

Payment for temporary erosion control measures, except those made necessary by the Contractor's own negligence or for his own convenience, will be paid for at the appropriate contract unit price for the devices or measures utilized in borrow sources and waste areas.

No additional payment will be made for erosion control devices or permanent seeding and mulching in any commercial borrow or waste pit. All erosion and sediment control practices which may be required on a commercial borrow or waste site will be done at the Contractor's expense.

Temporary Diversion:

The work by this section for installation, maintenance, and cleanout of temporary diversions shall be in accordance with Section 1630. The quantity of excavation for installation and cleanout measured as provided in Article 1630-4 will be paid for at the contract unit price per cubic yard (cubic meter) as provided in Article 1630-5 for "Silt Excavation".

Safety Fence:

Description:

The work of "Safety Fence" shall consist of furnishing, installing and maintaining polyethylene or polypropylene fence along the outside riparian buffer, wetland, or water boundary as well as along the construction corridor within these boundaries to mark the areas that have been approved to infringe within the buffer, wetland or water, and as directed by the Engineer in accordance with the special provisions included herein. The fence shall be installed prior to any land disturbing activities.

Materials:**Fence Material:**

Polyethylene or polypropylene fence shall be a preconstructed safety fence approved by the Engineer.

Posts:

Either wood posts or steel posts may be used. Wood posts shall be nominal 2" x 4" (51 mm x 102 mm) or 4" x 4" (102 mm x 102 mm), lengths as required, structural light framing, grade No. 2, Southern Pine. Steel posts shall be at least 5 feet (1.6 m) in length, approximately 1 3/8" (35 mm) wide measured parallel to the fence, and have a minimum weight of 1.25 lb./ft. (1.9 kg/m) of length. The steel post shall be equipped with an anchor plate having a minimum area of 14 square inches (90 square centimeters).

Clearing and Grading:

No additional clearing and grubbing is anticipated for the installation of this fence; however, if any clearing and grubbing is required, it will be the minimum required for the installation of the safety fence. Such clearing shall include satisfactory removal and disposal of all trees, brush, stumps and other objectionable material.

The fence shall be erected to conform to the general contour of the ground. When determined necessary by the Engineer, minor grading along the fence line shall be done to meet this requirement provided no obstructions to proper drainage are created.

Installation:

Posts shall be set and maintained in a vertical position and may be hand set or set with a post driver. If hand set, all backfill material shall be thoroughly tamped. If power driven, wood posts may be sharpened to a dull point. Posts damaged by power driving shall be removed and replaced prior to final acceptance. The tops of all wood posts shall be cut at a 30 degree angle. The wood posts may, at the option of the Contractor, be cut at this angle either before or after the posts are erected.

The fence fabric shall be attached to the wood posts with one 2" (51 mm) galvanized wire staple across each cable or to the steel posts with wire or other acceptable means.

The Contractor shall be required to maintain the safety fence in a satisfactory condition for the duration of the project as determined by the Engineer.

Method of Measurement:

The quantity of safety fence to be paid for shall be the actual number of linear feet (meter) of "Safety Fence", installed in place and accepted. No direct payment will be

made for post and post bracing. Cost shall be included in the cost of the fence per linear foot (meter).

Basis of Payment:

The quantity of safety fence measured as provided above will be paid for at the contract unit price per linear foot (meter) of safety fence. Such payment will be full compensation for the work as described in the above paragraphs, including but not limited to clearing and grading, furnishing and installing fence fabric with necessary posts and post bracing, staples, tie wires, tools, equipment and incidentals necessary to complete the work.

Payment will be made under:

Safety Fence.....LF (M)

Gravel Construction Entrance:

Description:

The work covered by this section consists of furnishing, installing, and maintaining and removing any and all material required for the construction of a Gravel Construction Entrance.

Materials:

The filter fabric shall meet the requirements of Section 1056 for Type 2 Fabric.

Stone shall be Class A Stone and shall meet the requirements of Section 1042 for Stone for Erosion Control, Class A.

Construction:

The Contractor shall install a Gravel Construction Entrance in accordance with the details in the plans and at locations as directed by the Engineer.

Method Of Measurement:

Gravel Construction Entrance will not be measured for payment under this section.

Basis Of Payment:

Payment for installation of Filter Fabric shall be paid for at the contract unit price per square yard (square meter) "Filter Fabric for Drainage".

Payment for installation of Class A Stone shall be paid for at the contract unit price per ton (metric ton) "Stone for Erosion Control, Class A".

Such price and payment shall be considered full compensation for all work covered by this provision including all materials, construction, maintenance, and removal of Gravel Construction Entrance as directed by the Engineer.

Special Sediment Control Fence:

Description:

The work covered by this section consists of the construction, maintenance, and removal of special sediment control fence. Place special sediment control fence as shown on the plans or as directed by the Engineer.

Materials:

(A) Posts:

Either wood or steel posts may be used. Wood posts shall be a minimum of 6 feet long (1.8 m), at least 3 inches (75 mm) in diameter, and straight enough to provide a fence without noticeable misalignment. Steel posts shall be at least 5 feet (1.5 m) in length, approximately 1 3/8 inches (35 mm) wide measured parallel to the fence, and have a minimum weight of 1.25 lb/ft (1.86 kg/m) of length. The post shall be equipped with an anchor plate having a minimum area of 14.0 square inches (9000 square millimeters), and shall have a means of retaining wire in the desired position without displacement.

(B) 1/4 inch (6.4mm) Hardware Cloth:

Hardware cloth shall have 1/4 inch (6.4mm) openings constructed from #24 gauge wire. Install hardware cloth according to the detail shown on the plans.

(C) Sediment Control Stone:

Sediment control stone shall meet the requirements of Section 1005. Install stone according to the detail shown on the plans.

Maintenance and Removal:

The Contractor shall maintain the special sediment control fence until the project is accepted or until the fence is removed, and shall remove and dispose of silt accumulations at the fence when so directed by the Engineer in accordance with Section 1630.

Method of Measurement:

The quantity of 1/4 inch (6.4mm) hardware cloth to be paid for will be the actual number of linear feet (meters) measured along the ground, which has been completed and accepted.

The quantity of sediment control stone will be measured according to Article 1610-4.

Basis of Payment:

Payment for special sediment control fence will be as follows:

1/4 inch (6.4mm) Hardware Cloth.....LF (M)
Sediment Control Stone TON (MT)

Permanent Soil Reinforcement Mat:

General:

This work shall consist of furnishing and placing "Permanent Soil Reinforcement Mat", of the type specified, over previously prepared areas as directed by the Engineer.

Materials:

The product shall be permanent erosion control reinforcement mat and shall be constructed of 100% coconut fiber stitch bonded between a heavy duty UV stabilized cusped (crimped) netting overlaid with a heavy duty UV stabilized top net. The three nettings shall be stitched together on 1.5 inch (38 mm) centers UV stabilized polyester thread to form a permanent three dimensional structure. The mat shall have the following physical properties:

Property	Test Method	Value	Unit
Ground Cover	Image Analysis	93	%
Thickness	ASTM D1777	0.63 (16)	in (mm)
Mass Per Unit Area	ASTM D3776	0.92 (0.50)	lb/sy (kg/m ²)
Tensile Strength	ASTM D5035	480 (714.2)	lb/ft (kg/m)
Elongation	ASTM D5035	49	%
Tensile Strength	ASTM D5035	960 (1428.5)	lb/ft (kg/m)
Elongation	ASTM D5035	31	%
Tensile Strength	ASTM D1682	177 (80.3)	lbs (kg)
Elongation	ASTM D1682	22	%
Resiliency	ASTM D1777	>80	%
UV Stability *	ASTM D4355	151 (68.5)	lbs (kg)
Color(Permanent Net)		UV Black	
Porosity (Permanent Net)	Calculated	>95	%
Minimum Filament Diameter (permanent net)	Measured	0.03 (0.8)	in (mm)

*ASTM D1682 Tensile Strength and % strength retention of material after 1000 hours of exposure in a Xenon-arc weatherometer.

A certification (Type 1, 2, or 3) from the manufacturer showing:

- 1) the chemical and physical properties of the mat used, and
- 2) conformance of the mat with this specification will be required.

Matting shall be installed according to section 1060-8 of the Standard Specifications.

Soil Preparation:

All areas to be protected with the mat shall be brought to final grade and seeded in accordance with Section 1660. The surface of the soil shall be smooth, firm, stable and free of rocks, clods, roots or other obstructions which would prevent the mat from lying in direct contact with the soil surface. Areas where the mat is to be placed will not need to be mulched.

Measurement:

The quantity of "Permanent Soil Reinforcement Mat" to be paid for shall be the actual number of square yards (square meters), surface measure, completed, and accepted. Overlaps will not be included in the measurement, and will be considered as incidental to the work.

Basis of Payment:

This work will be paid for at the contract unit price per square yard (square meter) for "Permanent Soil Reinforcement Mat" of the type specified, complete in place and accepted. Such payment shall be full compensation for furnishing and installing the mat in accordance with this specification, and for all required maintenance.

Payment will be made under:

Permanent Soil Reinforcement Mat..... SY (M2)

Stream Channel Relocation Limitations:

The following sequence of construction must be followed in the areas designated on the plans as stream relocation. Failure on the part of the Contractor to follow this sequence, and complete each step prior to proceeding in this area as specified, will be just cause for the Engineer to direct the suspension of work in accordance with Section 108-7 of the Standard Specifications.

- 1. Clear, but do not grub area within the Environmentally Sensitive Area on the existing stream to be relocated.
- 2. Construct and stabilize, with vegetation or erosion control materials sufficient to restrain erosion, the proposed stream channel relocation as shown on the plans.
- 3. Divert water into newly constructed channel only after it has been stabilized and approved.

4. Begin grubbing and/or grading within Environmentally Sensitive Area of existing stream.

The contractor shall perform seeding and mulching and install erosion control matting to all cut/fill slopes adjacent to stream relocations in accordance with the provision contained in this contract and in accordance with Section 1631 of the Standards and Specification Manual.

The above requirements apply to the stream channels being constructed at the following stations:

Approx. Sta. 11+10 to 11+80 -RPD- Lt.