R:\XSC\L_earth_lt1.log

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY

PROJ. REFERENCE NO.	SHEET NO.
B-3470	X-A

Approximate quantities only. Unclassified excavation, borrow excavation, shoulder borrow, fine grading, clearing and grubbing, breaking of existing pavement and removal of existing pavement will be paid for at the lump sum price for "Grading".

NOTE: EMBANKMENT COLUMN INCLUDES BACKFILL FOR UNDERCUT

Station L (LEFT)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
11+50.00	0	0
12+00.00	5	0
12+50.00	8	1
13+00.00	3	16
13+50.00	0	111
14+00.00	0	113
14+50.00	0	42
14+56.94	0	8
14+74.00	0	8

Station L (LEFT)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
15+63.00	0	0
15+79.06	0	2
16+00.00	1	4
16+50.00	2	32
17+00.00	4	30
17+50.00	4	9
18+00.00	3	23
18+50.00	1	17

Station L (RIGHT)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
11+50.00	0	0
12+00.00	4	0
12+50.00	6	1
13+00.00	2	11
13+50.00	0	27
14+00.00	0	142
14+50.00	0	205
14+56.94	0	26
14+74.00	0	26

Station L (RIGHT)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
15+63.00	0	0
15+79.06	0	20
16+00.00	1	59
16+50.00	2	91
17+00.00	6	24
17+50.00	14	0
18+00.00	17	0
18+50.00	8	0

Station L (RIGHT)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	DDE (cu. yd.)
15+60.00	0	0	0
16+00.00	0	0	3
16+35.00	0	0	3