

30/58

EARTHWORK SUMMARIES

Volumes in Cubic Meters

PROJECT 34426.3.3
~~8.T190301~~

COUNTY Onslow

DATE 06/28/04

SHEET 1 OF 4 SHEETS

RD10S01C

LINE	STATION	STATION	TOTAL EXCAV. (UNCL.)	ROCK EXCAV.	UNDERCUT	UNSUIT. EXCAV.	SUITABLE EXCAV.	TOTAL EMB.	ROCK EMB.	EARTH EMB.	EMBANK. +25%	BORROW	SUITABLE WASTE	UNSUIT. WASTE	TOTAL WASTE
-LMED- RT	104+00	114+00	1,114		2,878	3,769	223	17,214		14,336	21,518	21,295		3,769	3,769
		SUBTOTAL	1,114		2,878	3,769	223	17,214		14,336	21,518	21,295		3,769	3,769
-LMED- RT	114+00	124+00	385		1	309	77	21,530		21,529	26,913	26,836		309	309
		SUBTOTAL	385		1	309	77	21,530		21,529	26,913	26,836		309	309
-LMED- RT	124+00	134+00	1,440			1,152	288	27,413		27,413	34,266	33,978		1,152	1,152
		SUBTOTAL	1,440			1,152	288	27,413		27,413	34,266	33,978		1,152	1,152
-LMED- RT	134+00	144+00	1,348			1,078	270	21,947		21,947	27,434	27,164		1,078	1,078
		SUBTOTAL	1,348			1,078	270	21,947		21,947	27,434	27,164		1,078	1,078
-LMED- RT	144+00	154+00	689			551	138	20,597		20,597	25,746	25,608		551	551
		SUBTOTAL	689			551	138	20,597		20,597	25,746	25,608		551	551
-LMED- RT	154+00	164+00	4,413			3,530	883	24,126		24,126	30,158	29,275		3,530	3,530
		SUBTOTAL	4,413			3,530	883	24,126		24,126	30,158	29,275		3,530	3,530
-LMED- RT	164+00	174+00	5,000		3,476	7,476	1,000	9,719		6,243	12,149	11,149		7,476	7,476
-Y2-	0+00	1+10	422			338	84	167		167	209	125		338	338
		SUBTOTAL	5,422		3,476	7,814	1,084	9,886		6,410	12,358	11,274		7,814	7,814
-LMED- RT	174+00	182+66.40	5,415		2,185	6,517	1,083	10,258		8,073	12,823	11,740		6,517	6,517
		SUBTOTAL	5,415		2,185	6,517	1,083	10,258		8,073	12,823	11,740		6,517	6,517
-LMED- RT	183+08.40	193+00	3,090		1,630	4,102	618	13,521		11,891	16,901	16,283		4,102	4,102
-Y4-	0+00	1+05	354			283	71	304		304	380	309		283	283
		SUBTOTAL	3,444		1,630	4,385	689	13,825		12,195	17,281	16,592		4,385	4,385
-LMED- RT	193+00	195+80	264		560	771	53	3,302		2,742	4,128	4,075		771	771
		SUBTOTAL	264		560	771	53	3,302		2,742	4,128	4,075		771	771
SHEET 1 TOTALS:			23,934		10,730	29,876	4,788	170,098		159,368	212,625	207,837		29,876	29,876