



PROJ. REFERENCE NO.	SHEET NO.
R-0513BB/C	PMP-1

# Pavement Marking Schedule

## TIP Project # R-0513BB/C

SYMBOL	DESCRIPTION	PAY ITEM QUANTITY BREAKDOWN		TOTAL QUANTITY
		FINAL		
PAVEMENT MARKINGS				
TA	WHITE EDGELINE	THERMOPLASTIC (100MM, 2.3MM)	3960 M	TOTAL 3960 M
TC	3 M. WHITE SKIP	THERMOPLASTIC (100MM, 3.1MM)	11 M	TOTAL 4366 M
TD	0.5 M. WHITE MINISKIP		18 M	
TE	WHITE SOLID LANE LINE		377 M	
TI	YELLOW DOUBLE CENTER		3960 M	
T6	WHITE EDGELINE	THERMOPLASTIC (150MM, 2.3MM)	58513 M	TOTAL 117442 M
T7	YELLOW EDGELINE		58929 M	
TJ	3 M. WHITE SKIP	THERMOPLASTIC (150MM, 3.1MM)	12947 M	TOTAL 13543 M
TK	0.5 M. WHITE MINISKIP		596 M	
TY	WHITE GORELINE	THERMOPLASTIC (300MM, 2.3MM)	6289 M	TOTAL 6289 M
T2	WHITE STOPBAR	THERMOPLASTIC (600MM, 3.1MM)	186 M	TOTAL 186 M
THERMOPLASTIC PAVEMENT MARKING SYMBOLS (2.3MM)				
UA	LEFT TURN ARROW		19 EA	TOTAL 90 EA
UB	RIGHT TURN ARROW		8 EA	
UC	STRAIGHT ARROW		58 EA	
UE	COMBO. STRAIGHT/RIGHT		5 EA	

24-SEP-2004 15:37  
 G:\TCP\FINAL PMS\RS13C-TC.pmp01.dgn  
 ms felemdn AT TETC\2231

APPROVED:  DATE: 9/27/04	<b>FINAL PAVEMENT MARKING SCHEDULE</b>			
	SCALE: NONE			
	DATE:			
	DESIGN BY:			
	REVIEWED BY:			
		REVISIONS <table border="1" style="width: 100%; height: 20px;"> <tr><td> </td><td> </td></tr> </table>		
		CARD FILE R513C TC PMP01.DGN		