

Volumes in Cubic Meters

PROJECT R-0513BB COUNTY: ROBESON

DATE: 11-26-02 UPDATED 6-7-04 COMPILED BY: T. SNELL

SHEET 1 OF 3 SHEETS

RD10S01C	STATION	STATION	EXCAVATION				EMBANKMENT			BORROW	WASTE					
			TOTAL UNCLASS.	ROCK	UNDERCUT	UNSUIT. UNCLASS.	SUITABLE UNCLASS.	TOTAL	ROCK		EARTH	EMBANK. (+) 25%	ROCK	SUITABLE	UNSUIT.	TOTAL
	Y5 9+24.000	BEG. BRDG. 13+89.254	3,449			172	3,277	88,084		88,084	110,105	106,828			172	172
	END BRDG. 14+66.854	20+40.000	6,239			312	5,927	58,112		58,112	72,640	66,713			312	312
	RB 11+29.443	16+64.964	0			0	0	42,382		42,382	52,978	52,978			0	0
	RC 11+23.727	14+56.946	206			10	196	63,187		63,187	78,984	78,788			10	10
	RA 10+06.021	12+54.560	0			0	0	20,625		20,625	25,781	25,781			0	0
	RD 10+06.139	15+58.180	0			0	0	82,086		82,086	102,608	102,608			0	0
	SR5 10+00.000	19+15.070	3,321			166	3,155	15,992		15,992	19,990	16,835			166	166
	SR5 19+15.070	28+15.070	0			0	0	42,334		42,334	52,918	52,918			0	0
	SR5 28+15.070	37+20.000	426			21	405	23,688		23,688	29,610	29,205			21	21
	SR5 37+20.000	38+79.318	1,321			66	1,255	1,012		1,012	1,265	10			66	66
	<b>SHEET TOTAL</b>		<b>14,962</b>			<b>747</b>	<b>14,215</b>	<b>437,502</b>		<b>437,502</b>	<b>546,879</b>	<b>532,664</b>			<b>747</b>	<b>747</b>