

STATE OF NORTH CAROLINA  
DIVISION OF HIGHWAYS  
**SUMMARY OF QUANTITIES**

STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C201004										ItemNumber	Sec #	Quantity	Unit	Description
ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description
0000100000-N	800	Lump Sum		MOBILIZATION	1525000000-E	SP	550	TON	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	4425000000-N	1125	2	EA	WARNING FLAG SETS
0000400000-N	801	Lump Sum		CONSTRUCTION SURVEYING	1560000000-E	620	82	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	4435000000-N	1135	50	EA	CONES
0029000000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (17+87.50)	1693000000-E	654	15	TON	ASPHALT PLANT MIX, PAVEMENT REPAIR	4445000000-E	1145	96	LF	BARRICADES (TYPE III)
0050000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUB-BING	2000000000-N	806	24	EA	RIGHT OF WAY MARKERS	4455000000-N	1150	8	MD	FLAGGER
0057000000-E	226	200	CY	UNDERCUT EXCAVATION	2220000000-E	838	10.1	CY	REINFORCED ENDWALLS	4810000000-E	1205	9,400	LF	PAINT PAVEMENT MARKING LINES (4")
0063000000-N	SP	Lump Sum		GRADING	2286000000-N	840	3	EA	MASONRY DRAINAGE STRUCTURES	4900000000-N	1252	25	EA	PERMANENT RAISED PAVEMENT MARKERS
0106000000-E	230	11,500	CY	BORROW EXCAVATION	2367000000-N	840	3	EA	FRAME WITH TWO GRATES, STD 840.29	6000000000-E	1605	600	LF	TEMPORARY SILT FENCE
0134000000-E	240	14	CY	DRAINAGE DITCH EXCAVATION	2556000000-E	846	285	LF	SHOULDER BERM GUTTER	6006000000-E	1610	115	TON	STONE FOR EROSION CONTROL, CLASS A
0195000000-E	265	100	CY	SELECT GRANULAR MATERIAL	2612000000-E	848	48	SY	6" CONCRETE DRIVEWAY	6009000000-E	1610	360	TON	STONE FOR EROSION CONTROL, CLASS B
0196000000-E	270	100	SY	FABRIC FOR SOIL STABILIZATION	2612000000-E	848	48	SY	6" CONCRETE DRIVEWAY	6012000000-E	1610	110	TON	SEDIMENT CONTROL STONE
0318000000-E	300	22	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	3030000000-E	862	862.5	LF	STEEL BM GUARDRAIL	6015000000-E	1615	4	ACR	TEMPORARY MULCHING
0343000000-E	310	24	LF	15" SIDE DRAIN PIPE	3045000000-E	862	106.25	LF	STEEL BM GUARDRAIL, SHOP CURVED	6018000000-E	1620	150	LB	SEED FOR TEMPORARY SEEDING
0366000000-E	310	12	LF	15" RC PIPE CULVERTS, CLASS III	3150000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS	6021000000-E	1620	0.75	TON	FERTILIZER FOR TEMPORARY SEEDING
0696000000-E	310	52	LF	*** BIT COAT CS PIPE CULVERTS, TYPE B ***** THICK, (3" X 1" CORRUGATIONS) (96", 0.109")	3195000000-N	862	2	EA	GUARDRAIL ANCHOR UNITS, TYPE AT-1	6024000000-E	1622	125	LF	TEMPORARY SLOPE DRAINS
0708000000-E	310	60	LF	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	3215000000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III	6027000000-N	1622	4	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS
0714000000-E	310	52	LF	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	3270000000-N	SP	4	EA	GUARDRAIL ANCHOR UNITS, TYPE 350	6030000000-E	1630	760	CY	SILT EXCAVATION
0806000000-E	310	4	EA	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	3436000000-N	862	2	EA	GENERIC GUARDRAIL ITEM 25'-0" CLEAR SPAN GUARDRAIL	6036000000-E	1631	1,370	SY	MATting FOR EROSION CONTROL
0995000000-E	340	24	LF	PIPE REMOVAL	3649000000-E	876	127	TON	PLAIN RIP RAP, CLASS B	6042000000-E	1632	60	LF	1/4" HARDWARE CLOTH
1121000000-E	520	160	TON	AGGREGATE BASE COURSE	3656000000-E	876	609	SY	FILTER FABRIC FOR DRAINAGE	6084000000-E	1660	4.5	ACR	SEEDING & MULCHING
1220000000-E	545	200	TON	INCIDENTAL STONE BASE	4025000000-E	901	45.25	SF	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	6087000000-E	1660	2.5	ACR	MOWING
1275000000-E	600	85	GAL	PRIME COAT	4072000000-E	903	105	LF	SUPPORTS, 3-LB STEEL U-CHANNEL	6090000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
1489000000-E	610	510	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B	4102000000-N	904	8	EA	SIGN ERECTION, TYPE E	6093000000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
1498000000-E	610	500	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	4155000000-N	907	14	EA	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	6096000000-E	1662	100	LB	SEED FOR SUPPLEMENTAL SEEDING
					4400000000-E	1110	454	SF	WORK ZONE SIGNS (STATIONARY)	6108000000-E	1665	3.25	TON	FERTILIZER TOPDRESSING
					4410000000-E	1110	94	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)	6114000000-N	SP	2.5	HR	SPECIALIZED HAND MOWING
										6117000000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL

5/28/99

13-JUL-2004 12:10  
RD196590\B3696\_rdy\_sum.dgn  
twhte