





FINAL PAVEMENT SCHEDULE	
C1	PROP. APPROX. 2 1/2" ASPHALT CONCRETE SURFACE COURSE, TYPE SF9.5A, AT AN AVERAGE RATE OF 137.5 LBS. PER SQ. YD. IN EACH OF TWO LAYERS.
C2	PROP. VAR. DEPTH ASPHALT CONCRETE SURFACE COURSE, TYPE SF9.5A, AT AN AVERAGE RATE OF 110 LBS. PER SQ. YD. PER 1" DEPTH. TO BE PLACED IN LAYERS NOT TO EXCEED 1 1/2" IN DEPTH.
D1	PROP. APPROX. 2 1/2" ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE I19.0B, AT AN AVERAGE RATE OF 285 LBS. PER SQ. YD.
D2	PROP. VAR. DEPTH ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE I19.0B AT AN AVERAGE RATE OF 114 LBS. PER SQ. YD. PER 1" DEPTH. TO BE PLACED IN LAYERS NOT LESS THAN 2 1/4" IN DEPTH OR GREATER THAN 4" IN DEPTH.
E1	PROP. APPROX. 3" ASPHALT CONCRETE BASE COURSE, TYPE B25.0B, AT AN AVERAGE RATE OF 342 LBS. PER SQ. YD.
E2	PROP. VAR. DEPTH ASPHALT CONCRETE BASE COURSE, TYPE B25.0B, AT AN AVERAGE RATE OF 114 LBS. PER SQ. YD. PER 1" DEPTH. TO BE PLACED IN LAYERS NOT LESS THAN 3" IN DEPTH OR GREATER THAN 5 1/2" IN DEPTH.
J1	PROP. 8" AGGREGATE BASE COURSE.
P1	PRIME COAT AT THE RATE OF .35 GAL. PER SQ. YD.
R	SHOULDER BERM GUTTER.
T	EARTH MATERIAL.
U	EXISTING PAVEMENT.
W	WEDGING (SEE STANDARD WEDGING DETAIL THIS SHEET).

NOTE: PAVEMENT EDGE SLOPES ARE 1:1 UNLESS SHOWN OTHERWISE.




USE TYPICAL SECTION No. 1
 -L- STA. 11+00.00 TO 12+00.00
 -L- STA. 20+50.00 TO 22+75.00


NOTE: -L- STA. 22+75.00 TO 23+48.00
 OVERLAY EXISTING PAVEMENT WITH 2.5" OF SF9.5A



USE TYPICAL SECTION No. 2
 -L- STA. 12+00.00 TO 17+40.00 (BEGIN BRIDGE)
 -L- STA. 18+35.00 (END BRIDGE) TO 20+50.00



USE TYPICAL SECTION No. 3
 -DR1- STA. 10+50.00 TO STA. 12+21.28



NOTE: -Y1- STA. 10+12.26 TO 10+64.00
 OVERLAY EXISTING W/2.5" SF9.5A
 SEE PLAN SHEET NO. 4

5/28/99

27-JUL-2004 12:32
 R:\Pro\33696_rdy_typ.dgn
 RWBrannan