

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (17+87.50)	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0106000000-E	230	BORROW EXCAVATION	11,500 CY		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	14 CY		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	100 CY		
0010	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	100 SY		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	22 TON		
0012	0343000000-E	310	15" SIDE DRAIN PIPE	24 LF		
0013	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	12 LF		
0014	0696000000-E	310	*** BIT COAT CS PIPE CULVERTS, TYPE B ***** THICK, (3" X 1" CORRUGATIONS) (96", 0.109")	52 LF		
0015	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	60 LF		
0016	0714000000-E	310	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	52 LF		
0017	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4 EA		
0018	0995000000-E	340	PIPE REMOVAL	24 LF		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1121000000-E	520	AGGREGATE BASE COURSE	160 TON		
0020	1220000000-E	545	INCIDENTAL STONE BASE	200 TON		
0021	1275000000-E	600	PRIME COAT	85 GAL		
0022	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	510 TON		
0023	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	500 TON		
0024	1525000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	550 TON		
0025	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	82 TON		
0026	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	15 TON		
0027	2000000000-N	806	RIGHT OF WAY MARKERS	24 EA		
0028	2220000000-E	838	REINFORCED ENDWALLS	10.1 CY		
0029	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
0030	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	3 EA		
0031	2556000000-E	846	SHOULDER BERM GUTTER	285 LF		
0032	2612000000-E	848	6" CONCRETE DRIVEWAY	48 SY		
0033	3030000000-E	862	STEEL BM GUARDRAIL	862.5 LF		
0034	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	106.25 LF		
0035	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0036	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	2 EA		
0037	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		

County: Rockingham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0039	3436000000-N	862	GENERIC GUARDRAIL ITEM 25'-0" CLEAR SPAN GUARDRAIL	2 EA		
0040	3649000000-E	876	PLAIN RIP RAP, CLASS B	127 TON		
0041	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	609 SY		
0042	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	45.25 SF		
0043	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	105 LF		
0044	4102000000-N	904	SIGN ERECTION, TYPE E	8 EA		
0045	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	14 EA		
0046	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	454 SF		
0047	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94 SF		
0048	4425000000-N	1125	WARNING FLAG SETS	2 EA		
0049	4435000000-N	1135	CONES	50 EA		
0050	4445000000-E	1145	BARRICADES (TYPE III)	96 LF		
0051	4455000000-N	1150	FLAGGER	8 MD		
0052	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	9,400 LF		
0053	4900000000-N	1252	PERMANENT RAISED PAVEMENT MARKERS	25 EA		
0054	6000000000-E	1605	TEMPORARY SILT FENCE	600 LF		
0055	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	115 TON		

County : Rockingham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	360 TON		
0057	6012000000-E	1610	SEDIMENT CONTROL STONE	110 TON		
0058	6015000000-E	1615	TEMPORARY MULCHING	4 ACR		
0059	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	150 LB		
0060	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.75 TON		
0061	6024000000-E	1622	TEMPORARY SLOPE DRAINS	125 LF		
0062	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4 EA		
0063	6030000000-E	1630	SILT EXCAVATION	760 CY		
0064	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,370 SY		
0065	6042000000-E	1632	1/4" HARDWARE CLOTH	60 LF		
0066	6084000000-E	1660	SEEDING & MULCHING	4.5 ACR		
0067	6087000000-E	1660	MOWING	2.5 ACR		
0068	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0069	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0070	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	100 LB		
0071	6108000000-E	1665	FERTILIZER TOPDRESSING	3.25 TON		
0072	6114000000-N	SP	SPECIALIZED HAND MOWING	2.5 HR		
0073	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	8 EA		

County: Rockingham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
STRUCTURE ITEMS						
0074	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (17+87.50 -L-)	Lump Sum	L.S.	
0075	8121000000-N	SP	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (17+87.50 -L-)	Lump Sum	L.S.	
0076	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	37.6 CY		
0077	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (17+87.50 -L-)	Lump Sum	L.S.	
0078	8217000000-E	425	REINFORCING STEEL (BRIDGE)	5,775 LB		
0079	8364000000-E	450	HP12X53 STEEL PILES	500 LF		
0080	8503000000-E	460	CONCRETE BARRIER RAIL	185.5 LF		
0081	8608000000-E	876	PLAIN RIP RAP CLASS II (2'-0" THICK)	330 TON		
0082	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	375 SY		
0083	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0084	8867000000-E	SP	GENERIC STRUCTURE ITEM 3'-0" X 3'-3" PRESTRESSED CONCRETE BOX BEAMS	1,112.63 LF		

1410/Sep08/Q38816.58/D326893500000/E84

Total Amount Of Bid For Entire Project :

C201004
ROCKINGHAM COUNTY

2/16/99

Contract No: C201004

County: Rockingham

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General